

**ACTON •
MICKELSON •
ENVIRONMENTAL, INC.**

June 17, 1998

Consulting Scientists, Engineers, and Geologists

Mr. Hamid Saebfar
Site Mitigation Branch, Region 3
Attn: Whittaker Project Manager
California Department of Toxic Substances Control
1011 North Grandview Avenue
Glendale, California 91201

21001.75/7

Subject: Area 317 RCRA Quarterly Ground Water Monitoring Report No. 38
January through March 1998, Whittaker Corporation, Bermite Facility
22116 West Soledad Canyon Road, Santa Clarita, California

Dear Mr. Saebfar:

Enclosed is the Area 317 RCRA Quarterly Ground Water Monitoring Report No. 38 for the first quarter, January through March 1998. The monitoring was completed according to the requirements of the *Water Quality Monitoring and Response Plan for the Interim Status Area 317 Surface Impoundment*.

The statistical analyses for this sampling event showed that the established tolerance limits for pH, conductivity, chloride, sulfate, trichloroethene, total organic carbon, or total organic halogens were not exceeded. The tolerance limit for sodium was exceeded for the sample from monitoring well MW-10. MW-1 was found to be hydraulically cross-gradient and/or down-gradient from MW-10, a point of compliance well. The potentiometric surface elevation in MW-1 was 1070.57 feet, while in MW-10 the elevation was 1070.66, a difference of +0.09 feet. Historically, MW-1 is usually upgradient from MW-10. For the thirty-eighth (and all previous quarterly monitoring assessments), in accordance with the Area 317 Monitoring Plan, MW-1 and MW-3 were considered to be upgradient or background monitoring wells for the purpose of tolerance limit calculation.

Please call me at (916) 939-7550 if there are any questions regarding the enclosed report.

Very truly yours,

ACTON • MICKELSON • ENVIRONMENTAL, INC.



Barbara J. Mickelson, P.E.
California Registered Professional Engineer #43417
BJM:lp
Enclosure

cc/enc: Ms. Lynne M. O. Brickner, Esq., Whittaker Corporation (2 copies)
Mr. Glen AbdunNur, Whittaker Corporation, Bermite Division
Mr. Jose Ochoa, Los Angeles County Fire Department
Ms. Mary Blevins, U.S. Environmental Protection Agency, Region IX

AREA 317 RCRA QUARTERLY
GROUND WATER MONITORING REPORT NO. 38
JANUARY THROUGH MARCH 1998

WHITTAKER CORPORATION, BERMITE FACILITY
22116 WEST SOLEDAD CANYON ROAD
SANTA CLARITA, CALIFORNIA 91350
AME PROJECT NO. 21001.75

June 17, 1998

Prepared By

ACTON • MICKELSON • ENVIRONMENTAL, INC.
5050 Robert J. Mathews Parkway
El Dorado Hills, California 95762
(916) 939-7550

PREPARED BY:

Robert L. Hammond
Robert L. Hammond
Project Engineer

REVIEWED BY:

Barbara J. Mickelson
Barbara J. Mickelson, P.E.
California Registered Professional
Engineer #43417

Date 6-17-98

Date 6/17/98



CONTENTS

	<u>Page</u>
LIST OF TABLES.....	ii
LIST OF FIGURES	ii
1.0 INTRODUCTION.....	1
2.0 GROUND WATER LEVEL MEASUREMENTS	2
3.0 SAMPLE COLLECTION AND ANALYSES	3
3.1 Required Ground Water Analyses	3
3.2 Approved Analytical Methods.....	4
4.0 GROUND WATER SAMPLE ANALYTICAL RESULTS	4
4.1 Ground Water Monitoring Parameters.....	4
4.2 Background Water Quality Parameters	5
5.0 STATISTICAL ANALYSIS OF RESULTS TO DATE	6
5.1 Assumptions Used in the Statistical Analysis	7
5.2 Data Preparation	7
5.3 Results	8
6.0 SUMMARY OF RESULTS, JANUARY THROUGH MARCH 1998.....	9
6.1 Ground Water Level Measurements.....	9
6.2 Ground Water Monitoring Parameters.....	9
6.3 Background Water Quality Parameters	9
6.4 Statistical Analysis.....	10
7.0 RECOMMENDATIONS.....	10
8.0 REMARKS	10
APPENDIX A. DOCUMENT SUBMITTAL CHRONOLOGY	
APPENDIX B. GROUND WATER SAMPLING PROCEDURES	
APPENDIX C. CHAIN-OF-CUSTODY FORMS	
APPENDIX D. SAMPLE ANALYSIS REQUEST FORMS	
APPENDIX E. FGL QUALITY ASSURANCE/QUALITY CONTROL PROGRAM	
APPENDIX F. ANALYTICAL REPORTS FOR GROUND WATER MONITORING PARAMETERS	
APPENDIX G. TRIP AND FIELD BLANK SAMPLE ANALYTICAL REPORTS	
APPENDIX H. STATISTICAL ANALYSES	

LIST OF TABLES

TABLE 1	POTENTIOMETRIC SURFACE ELEVATIONS
TABLE 2	GROUND WATER MONITORING PARAMETER ANALYTICAL RESULTS (MARCH 19, 1997 THROUGH APRIL 23, 1998)
TABLE 3	BACKGROUND WATER QUALITY PARAMETERS

LIST OF FIGURES

FIGURE 1	SITE LOCATION MAP
FIGURE 2	AREA 317 GROUND WATER MONITORING WELL LOCATIONS AND ESTIMATED GROUND WATER FLOW DIRECTION (03/23/98)
FIGURE 3	AREA 317 GROUND WATER MONITORING WELLS POTENTIOMETRIC SURFACE ELEVATIONS

**AREA 317 RCRA QUARTERLY
GROUND WATER MONITORING REPORT NO. 38
JANUARY THROUGH MARCH 1998**

**WHITTAKER CORPORATION, BERMITE FACILITY
22116 WEST SOLEDAD CANYON ROAD
SANTA CLARITA, CALIFORNIA 91350**

1.0 INTRODUCTION

The Whittaker Corporation (Whittaker), Bermite facility (site) is located at 22116 West Soledad Canyon Road in Santa Clarita, California (Figure 1). Whittaker had interim status permits for 14 Resource Conservation and Recovery Act (RCRA) Hazardous Waste Management Units (HWMUs) when operations were terminated in April 1987. A document entitled "Whittaker Corporation, Bermite Division, Santa Clarita, California, CAD064573108, Facility Closure Plan Modifications" (Closure Plan), was prepared by Whittaker and approved by the California Environmental Protection Agency, Department of Toxic Substances Control (Cal-EPA) and U.S. Environmental Protection Agency (EPA) on December 28, 1987. The Closure Plan outlined procedures for obtaining approval by Cal-EPA and EPA of clean closure certification for the different HWMUs, including the 317 Surface Impoundment (Area 317).

The Closure Plan required the installation of a ground water monitoring system capable of detecting and assessing the impact of the HWMU on the uppermost aquifer underlying Area 317. Implementation of the ground water monitoring program is described in the document "Water Quality Monitoring and Response Plan for the Interim Status Area 317 Surface Impoundment," dated October 9, 1992 (Area 317 Monitoring Plan). This monitoring plan, utilized for the nineteenth and subsequent sampling events, features an expanded list of analytical requirements over earlier versions in accordance with changes to Title 22 of the California Code of Regulations.

A total of six ground water monitoring wells (MW-1, MW-3, MW-4, MW-5, MW-6, and MW-10) have been installed around Area 317 (Figure 2). Monitoring well MW-4 was abandoned in 1992. Reports detailing the location and construction of monitoring wells, sampling and analysis plans for collecting and analyzing ground water samples from the ground water monitoring wells, abandonment of monitoring well MW-4, and quarterly sampling results which have been submitted to Cal-EPA and EPA are listed in Appendix A.

Quarterly ground water sampling activities were initiated on October 3, 1988, for monitoring wells MW-1, MW-3, and MW-4. The ground water monitoring program included analyses of water samples for volatile organic compounds (VOCs). Laboratory analytical results from the third quarterly sampling event reported trichloroethene (TCE) at 4,800 micrograms per liter ($\mu\text{g/l}$)

in the ground water sample collected from monitoring well MW-4. As a result, two additional monitoring wells were installed in Area 317 (MW-5 and MW-6).

The fourth quarterly monitoring event included sampling of the ground water from monitoring wells MW-1, MW-3, and MW-4. Monitoring wells MW-5 and MW-6 were not equipped for sampling during the fourth quarterly sampling event. Analytical results from the fourth quarter were similar to those reported in the third quarterly sampling event. The concentrations of VOCs reported in samples collected from monitoring wells MW-1 and MW-3 were below laboratory reporting limits; however, analysis of the ground water sample collected from monitoring well MW-4 reported TCE at 7,200 $\mu\text{g/l}$. Analysis of ground water samples collected from monitoring well MW-4 during the fifth through twelfth quarterly sampling events reported a steady decline in TCE concentration. Based on the results of the initial four sampling events, a reduced list of chemical parameters, approved by Cal-EPA, was utilized for the fifth through eighteenth quarterly sampling events.

Statistical analysis of indicator parameters was initiated during the fifth quarterly sampling event. The ground water samples collected and analyzed for indicator parameters from monitoring wells MW-1, MW-3, and MW-4 for the initial year of monitoring were evaluated to assess whether statistically significant changes to the ground water had occurred as a result of site activities.

A Comprehensive Ground Water Monitoring Evaluation (CME) was conducted by Cal-EPA on January 24 and 25, 1990, during the sixth quarterly monitoring event. Personnel from Cal-EPA were present during all phases of the sixth quarterly monitoring event, from the taking of initial potentiometric surface elevation measurements to the sealing of the coolers containing the quarterly ground water samples.

For the thirty-eighth quarterly monitoring event, ground water samples from monitoring wells MW-1, MW-5, and MW-10 were collected on March 25, 1998. Mechanical problems with the pumps in monitoring wells MW-3 and MW-6 delayed sampling from these wells until April 23, 1998. This report presents the results of the thirty-eighth quarterly ground water sampling event, along with recommendations for future quarterly ground water sampling events.

2.0 GROUND WATER LEVEL MEASUREMENTS

Water level measurements were taken on March 23, 1998, prior to well evacuation and sampling activities. Area 317 monitoring well locations are shown on Figure 2. Water levels were measured to the nearest 0.01 foot. Water level elevations increased 3.50, 3.20, 4.13, 3.21, and 3.77 feet in monitoring wells MW-1, MW-3, MW-5, MW-6, and MW-10, respectively, between the thirty-seventh and thirty-eighth quarters. Table 1 summarizes potentiometric surface elevation data for monitoring wells in Area 317. Figure 3 illustrates the historic changes in potentiometric

surface elevations in monitoring wells MW-1, MW-3, MW-5, MW-6, and MW-10. The March 23, 1998, water level measurements were used to develop the potentiometric surface contours illustrated on Figure 2. Figure 2 indicates that the inferred flow direction for March 23, 1998, is towards the north-northeast with a gradient of about 0.0025 foot per foot. The inferred flow direction and gradient are generally consistent with historic data, with the exception of data for MW-1. Based on these data, monitoring wells MW-6 and MW-10 are estimated to be located hydraulically downgradient from Area 317, monitoring well MW-5 is estimated to be located hydraulically downgradient and/or crossgradient from Area 317, monitoring well MW-1 is estimated to be located hydraulically crossgradient and/or downgradient from Area 317, and monitoring well MW-3 is estimated to be located hydraulically upgradient from Area 317.

3.0 SAMPLE COLLECTION AND ANALYSES

Ground water evacuation, stabilization, and sampling procedures are tabulated in Appendix B. Included in these procedures are revisions requested by Cal-EPA representatives during a June 26, 1996 field visit to observe Bermite facility personnel conduct quarterly ground water sampling.

3.1 Required Ground Water Analyses

For the thirty-eighth sampling event, samples collected from the Area 317 monitoring wells (MW-1, MW-3, MW-5, MW-6, and MW-10) were analyzed for the following parameters, in accordance with the Area 317 Monitoring Plan:

- Ground Water Monitoring Parameters: pH, conductivity, total organic carbon (TOC), total organic halogens (TOX), TCE, sulfate, sodium, manganese, iron, and chloride.

Background water quality parameters were not analyzed for the thirty-eighth sampling event based on the results from previous sampling events.

All ground water samples collected during the thirty-eighth sampling event were submitted to FGL Environmental (FGL) in Santa Paula, California. FGL Environmental subcontracted two analyses for TOC to Weck Laboratories, Inc. (Weck), because an instrument was temporarily unavailable. FGL Environmental and Weck are certified by Cal-EPA to perform the ground water analyses outlined in the Area 317 Monitoring Plan. Chain-of-custody and sample analysis request forms are included in Appendices C and D, respectively. A description of FGL's Quality Assurance/Quality Control (QA/QC) program is provided in Appendix E. Laboratory reports from FGL include QA/QC results for method blanks, calibrations, matrix spikes, and duplicate matrix spike samples.

3.2 Approved Analytical Methods

Ground water monitoring parameters were analyzed by EPA or other approved methodologies. Analytical methodologies were presented in the "Ground Water Sampling and Analysis Plan," dated August 1988. Modifications to this plan were approved by Cal-EPA prior to the fifth quarterly sampling event. Copies of the laboratory test method protocol were included in Appendix B of "Quarterly Sampling Report No. 1," dated December 1988.

A summary of sample volumes, sample containers, and laboratory analytical methods utilized during the thirty-eighth sampling event is presented in Table B-3, Appendix B. Procedures regarding sample containers, sample labeling, sample collection, and field QA/QC are tabulated in Appendix B. Field QA/QC includes trip and field blanks analyzed for TCE, TOX, and TOC.

4.0 GROUND WATER SAMPLE ANALYTICAL RESULTS

4.1 Ground Water Monitoring Parameters

Ground water samples collected from each monitoring well were analyzed for pH, conductivity, chloride, iron, manganese, sodium, sulfate, TCE, TOC, and TOX to serve as ground water monitoring parameters. Table 2 summarizes the results of the ground water monitoring parameter analyses for the thirty-eighth sampling event, along with results from the previous four sampling events. Copies of the original laboratory reports are presented in Appendix F.

Analysis for pH was not performed by the analytical laboratory for samples collected on March 25, 1998 from monitoring wells MW-1, MW-5, and MW-10 because the method hold time had expired; however, field measurements of pH are available because this parameter is monitored during well stabilization procedures. Field pH readings of 7.8, 7.8, and 7.9 were recorded for MW-1, MW-5, and MW-10, respectively. These field pH values have been incorporated into Tables 2, H-1, H-2, and H-4 in the thirty-eighth quarterly report. The analytical laboratory reported pH values of 7.3 and 7.5 for samples collected from monitoring wells MW-3 and MW-6, respectively, on April 23, 1998. The reported pH values for all monitoring wells are within the range observed in previous readings. The pH in monitoring well MW-1 appears to have rebounded sharply since the last monitoring event, rising from pH 7.0 to pH 7.8, as shown on the pH graph in Appendix H. However, the observed rebound in MW-1 pH is probably due to calibration/accuracy differences between the field and laboratory pH instruments.

Laboratory conductivity measurements of 810, 620, 570, 590, and 640 micromho per centimeter ($\mu\text{mho/cm}$) were reported for samples collected from monitoring wells MW-1,

MW-3, MW-5, MW-6, and MW-10, respectively. These values for conductivity are generally consistent with previous readings. The conductivity in monitoring well MW-1 has risen steadily since 1989, and this trend continued in the thirty-eighth quarter.

The results for chloride, sodium, and sulfate were 180, 52, and 12 milligrams per liter (mg/l), respectively, for the sample from monitoring well MW-1; 33, 50, and 71 mg/l for the sample from monitoring well MW-3; 62, 54, and 29 mg/l, respectively, for the sample from monitoring well MW-5; 77, 54, and 30 mg/l, respectively, for the sample from monitoring well MW-6; and 74, 81, and 43 mg/l, respectively, for the sample from monitoring well MW-10. The results for chloride, sodium, and sulfate are generally consistent with results from previous sampling events.

Manganese was not detected at or above the 30 $\mu\text{g/l}$ method detection limit in any of the samples collected from Area 317 monitoring wells during the thirty-eighth sampling event. Iron was detected at 50 $\mu\text{g/l}$ and 140 $\mu\text{g/l}$ in the samples collected from monitoring wells MW-3 and MW-6, respectively, and was not detected above the 50 $\mu\text{g/l}$ detection limit in the samples from monitoring wells MW-1, MW-5, and MW-10.

Laboratory analytical results for the samples collected from the Area 317 monitoring wells during the thirty-eighth sampling event did not indicate the presence of TCE or TOX above the detection limits of 0.5 $\mu\text{g/l}$ and 5 $\mu\text{g/l}$, respectively. Total organic carbon was not reported above the 0.5 $\mu\text{g/l}$ detection limit for samples collected from MW-1, MW-5, and MW-10 on March 25, 1998. Samples collected from monitoring wells MW-3 and MW-6 on April 23, 1998 were first analyzed for TOC by Weck. Weck reported TOC levels of 0.77 $\mu\text{g/l}$ and 0.67 $\mu\text{g/l}$ in samples from MW-3 and MW-6, respectively. FGL laboratories subsequently analyzed the samples and reported a TOC level of 0.6 $\mu\text{g/l}$ for both MW-3 and MW-6. The FGL data has been incorporated with the graphs and statistical analyses in Appendix H. The presence of total organic carbon was regularly reported in monitoring wells MW-1 and MW-3 in the three year period from 1988 to 1991, at levels ranging from 0.7 $\mu\text{g/l}$ to 7 $\mu\text{g/l}$, but had, until the thirty-eighth monitoring event, not been reported above the laboratory detection limit since 1992 (see TOC graph in Appendix H). Total organic carbon has not previously been reported in samples collected from monitoring well MW-6.

The analytical laboratory did not report the presence of TCE, TOX, or TOC in the trip and field blank samples. The laboratory reports for these samples are in Appendix G

4.2 Background Water Quality Parameters

Background water quality parameters were not tested during the thirty-eighth monitoring event. The background water quality parameters were last tested during the twenty-third monitoring event because of a third consecutive exceedance with respect to the tolerance limit established for sodium. A summary of historical background water quality parameters is presented in Table 3.

5.0 STATISTICAL ANALYSIS OF RESULTS TO DATE

As was indicated in the document "Ground Water Sampling and Analysis Plan," dated August 1988, and as required in 40 CFR Part 265.92, statistical analysis of the indicator parameters was previously performed to determine whether a statistically significant difference in the water quality existed between the individual downgradient monitoring wells and the upgradient or background monitoring wells. At that time, monitoring wells MW-1 and MW-3 were considered upgradient relative to Area 317, and monitoring wells MW-5, MW-6, and MW-10 were considered downgradient or crossgradient relative to Area 317. For the thirty-eighth quarter, monitoring well MW-1 was found to be hydraulically crossgradient and/or down-gradient from monitoring well MW-10, a point of compliance well. The potentiometric surface elevation in MW-1 was 1070.57 feet, while in MW-10 the elevation was 1070.66, a difference of +0.09 feet (Table 1). Historically, MW-1 is usually upgradient from MW-10, but during periods of rising water level, the reverse can be true. Prior to the current quarter, this situation was last observed in September 1996. For the thirty-eighth (and all previous quarterly monitoring assessments), in accordance with the Area 317 Monitoring Plan, MW-1 and MW-3 were considered to be upgradient or background monitoring wells for the purpose of tolerance limit calculation.

After four quarters of sampling and analysis of the monitoring system, the mean, standard deviation, variance, and coefficient of variance of the four indicator parameters were calculated. These values were reported to Cal-EPA in correspondence to Mr. Alan Sorsher, P.E., Cal-EPA, from Wenck Associates, Inc. (Wenck), dated October 25, 1989. The statistical analysis, presented in the fifth through tenth quarterly sampling reports, indicated only one statistically significant difference in water quality as determined by the indicator parameters. This was interpreted by Wenck to be caused by erroneous TOC results from the sixth quarter.

Since the approval of the Area 317 Monitoring Plan by Cal-EPA, a statistical comparison of analytical results for each downgradient monitoring well (MW-5, MW-6, and MW-10) is made against the tolerance limits calculated from the defined upgradient monitoring well (MW-1 and MW-3) results for the ten ground water monitoring parameters (chloride, sulfate, iron, manganese, sodium, TCE, TOC, TOX, conductivity, and pH). The tolerance limits for the ground water monitoring parameters are updated at a minimum annually to include the latest analytical data.

Concentrations of the ground water monitoring parameters in the samples collected from Area 317 down-gradient monitoring wells for the thirty-eighth quarter are included in Table H-1, presented in Appendix H. A summary of the quarterly statistics for each background monitoring well and the tolerance limit calculations for the ground water monitoring parameters are presented

in Appendix H, Tables H-2, H-3, and H-4. Graphical presentation of the statistical information is also included in Appendix H.

5.1 Assumptions Used in the Statistical Analysis

As recommended in the document "RCRA Ground Water Monitoring Technical Enforcement Guidance Document," the data points that are less than the detection limit are given a value equal to one-half the detection limit of the analyte for statistical calculations. As recommended in the document "Statistical Analysis of Ground Water Monitoring Data at RCRA Facilities, Interim Final Guidance" (Guidance Document), the statistical analysis assumes a value for the confidence coefficient (1- α) of 0.95 and a value for the proportion (γ) of 0.95. This corresponds to a 95 percent confidence that 95 percent of future background monitoring well results will fall within the predicted tolerance interval. The tolerance limits for pH were calculated using a two-tailed distribution, and the tolerance limits for the other parameters were calculated using a one-tailed distribution. It was assumed that the data are distributed normally.

5.2 Data Preparation

The ground water sample analytical results from the two defined background or upgradient monitoring wells (MW-1 and MW-3) for all ground water sampling to date, and the results for the three downgradient monitoring wells (MW-5, MW-6, and MW-10) for the thirty-eighth quarter of ground water sampling, have been tabulated and prepared for statistical analysis. In accordance with the tolerance limit methodology used for this statistical analysis, the analytical results for the ten ground water monitoring parameters are summarized by quarter and by monitoring well.

Arithmetic mean and standard deviation summary statistics have been calculated from background monitoring well results and are utilized in calculating the tolerance limits for each of the ground water monitoring parameters.

The statistical analysis for the ground water monitoring parameters requires a statistical comparison using tolerance intervals between water quality downgradient of Area 317 (wells MW-5, MW-6, and MW-10) and background water quality (wells MW-1 and MW-3). Tolerance intervals for each of the ten water quality parameters are based on the average of all the quarterly monitoring data for background wells MW-1 and MW-3. The most recent quarterly monitoring data for each downgradient well are compared to the established tolerance interval for each parameter to determine if an exceedance has occurred (Table H-1).

The calculations of the quarterly statistics were performed as outlined in the Area 317 Monitoring Plan. The K values used in the calculations were taken from the statistical tables based on the number of samples and a one-sided tolerance limit. Note that pH values have not been reported as hydrogen ion concentrations as was done previously and that the value of K for the analysis of pH is derived from the tables for two-sided tolerance limits. Trichloroethene has never been reported above the detection limit in samples from monitoring wells MW-1 and MW-3; therefore, the tolerance limit for TCE is set at the detection limit of 0.5 $\mu\text{g/l}$.

For manganese, the tolerance limit is set at the detection limit of 30 $\mu\text{g/l}$ for analysis by EPA Method 200.7, the method used by the laboratory for the thirty-eighth quarterly monitoring event. For the twenty-fourth through thirty-fourth quarterly monitoring events, the laboratory analyzed for manganese using EPA Method 200.8 with a detection limit of 0.5 $\mu\text{g/l}$. The laboratory analyzed for manganese using EPA Method 200.7 previous to the twenty-fourth quarterly monitoring event. Reported concentrations of manganese in the twenty-fourth through thirty-fourth quarterly monitoring events ranged from less than the detection limit of 0.5 to 4.0 $\mu\text{g/l}$ in the background monitoring wells (MW-1 and MW-3), and from 1.0 to 4.4 $\mu\text{g/l}$ in monitoring wells MW-5, MW-6, and MW-10. The tolerance limit for manganese calculated from the data through the thirty-fourth quarterly monitoring event was 21.0 $\mu\text{g/l}$. The laboratory indicates it will use EPA Method 200.7 for analysis of manganese until further notice. The statistical analysis will continue to use the detection limit of 30 $\mu\text{g/l}$ as the tolerance limit for manganese when the laboratory uses EPA Method 200.7 for manganese analysis.

5.3 Results

The thirty-eighth quarter results for each ground water monitoring parameter at each downgradient monitoring well were compared to the tolerance limits based on the first through thirty-eighth quarter results for the defined background monitoring wells MW-1 and MW-3. The statistical analysis, summarized in Table H-1, indicates that there is no excursion of tolerance limits for pH, conductivity, chloride, sulfate, iron, manganese, TCE, TOC, or TOX in downgradient ground water quality. The reported concentrations of sodium for monitoring wells MW-5 and MW-6 were below tolerance limits, but the analytical results for monitoring well MW-10 indicate a tolerance limit exceedance for sodium. In the past, an elevated sodium concentration in monitoring well MW-10 relative to sodium concentrations in the other four Area 317 wells has not indicated a statistical impact to ground water quality, based on the concentrations of the other ground water monitoring parameters and retesting of background water quality parameters.

6.0 SUMMARY OF RESULTS, JANUARY THROUGH MARCH 1998

6.1 Ground Water Level Measurements

The estimated direction of ground water flow based on the March 23, 1998 data is towards the north-northeast, which is within the range of ground water flow directions estimated during previous sampling events. Utilizing this data, monitoring wells MW-6 and MW-10 are estimated to be located hydraulically downgradient from Area 317, monitoring well MW-5 is estimated to be located hydraulically downgradient and/or from Area 317, monitoring well MW-1 is estimated to be located hydraulically crossgradient and/or downgradient from Area 317, and monitoring well MW-3 is estimated to be located hydraulically upgradient from Area 317.

6.2 Ground Water Monitoring Parameters

The reported pH results for the thirty-eighth sampling event range from 7.3 for the sample from monitoring well MW-3 to 7.9 for the sample from monitoring well MW-10. The conductivity in samples from the five monitoring wells ranged from 570 μ mhos/cm for monitoring well MW-5 to 810 μ mhos/cm for monitoring well MW-1. Total organic carbon was reported at 0.6 μ g/l in samples collected from MW-3 and MW-6, and was not detected above the 0.5 μ g/l detection limit in MW-1, MW-5, and MW-10. Total organic halogens were not detected in any of the samples collected at method detection limits of 5 μ g/l. The pH, conductivity, TOC, and TOX results reported for the thirty-eighth sampling event are generally consistent with the results reported for the previous sampling events. As noted in Section 4.1, monitoring well MW-1 is currently exhibiting an upward trend in conductivity. The ground water sample analytical results for chloride, iron, manganese, sodium, and sulfate from the five monitoring wells are also generally consistent with historic data. The primary constituent of concern for Area 317, TCE, was not present in any of the samples collected during the thirty-eighth sampling event.

6.3 Background Water Quality Parameters

Background water quality parameters were not tested in this quarter. The Area 317 Monitoring Plan indicates that if tolerance limits for any water quality parameters are exceeded for three consecutive monitoring events, then additional samples will be collected during the subsequent monitoring event and analyzed for the background water quality parameters.

The tolerance limit for sodium was exceeded for the fourteenth consecutive quarter in the sample from monitoring well MW-10. However, AME proposes that no further background water quality parameters be tested due to this exceedance at this time. Previous reports of elevated sodium concentrations in the samples from monitoring well MW-10 in comparison to concentrations for background wells has not indicated an impact with respect to the other ground water quality parameter concentrations. During the twenty-third sampling event, all six

background parameters were analyzed due to the exceedance of the tolerance limit for sodium in the sample from monitoring well MW-10. Analysis of the data indicated that the concentrations of background water quality parameters were consistent with the historical data for these parameters in samples from upgradient wells MW-1 and MW-3.

6.4 Statistical Analysis

The analytical results from the thirty-eighth quarter sampling event indicate that values for pH, conductivity, chloride, sulfate, iron, manganese, TCE, TOC, and TOX in the downgradient monitoring wells are within the tolerance limits set by calculations using historical results from the background monitoring wells. The tolerance limit for sodium was exceeded for the sample from monitoring well MW-10, but this statistical exceedance does not appear to reflect an actual degradation of ground water quality.

7.0 RECOMMENDATIONS

The following recommendations are presented:

- Conduct future sampling events in accordance with the procedures set forth in the document entitled "Water Quality Monitoring and Response Plan for the Interim Status Area 317 Surface Impoundment," dated October 9, 1992.
- Update the tolerance limits for the ground water monitoring parameters following the thirty-ninth quarterly sampling event.
- Evaluate water table elevations and gradient.

8.0 REMARKS

The recommendations contained in this report represent our professional opinions. These opinions are based on currently available information and were developed in accordance with currently accepted hydrogeologic and engineering practices at this time and location. Other than this, no warranty is implied or intended.

TABLE 1

POTENTIOMETRIC SURFACE ELEVATIONS
RCRA GROUND WATER MONITORING WELLS
WHITTAKER CORPORATION, BERMITE FACILITY

Well No.	MW-1	MW-3	MW-4	MW-5	MW-6	MW-10
Top of Casing Elevation ^a	1,561.32	1,538.51	1,538.43	1,493.37	1,521.09	1,537.49
Date	Potentiometric Surface Elevations ^a					
12/23/87	1,107.81	-- ^b				
01/27/88	1,108.03	1,109.51				
02/03/88	1,108.32	1,109.88				
02/04/88	1,108.36	1,109.14				
02/05/88	1,108.36	1,109.17				
02/09/88	1,108.24	1,109.13				
02/10/88	1,108.28	1,109.27				
02/12/88	1,108.28	1,109.27				
02/19/88	1,108.11	1,108.86				
03/28/88	1,107.69	1,108.23				
04/05/88	1,107.76	1,108.23				
04/12/88	1,107.66	1,108.23				
04/19/88	1,107.56	1,108.23				
04/26/88	1,107.61	1,108.23				
05/02/88	1,107.86	1,108.23				
07/27/88	1,103.58	1,104.19	1,102.61			
10/03/88	1,101.75	1,102.11	1,100.77			
01/23/89	1,099.82	1,100.25	1,098.92			
04/17/89	1,097.37	1,097.62	1,096.05			
07/27/89	1,094.67	1,094.85	1,093.53	1,093.02	1,093.15	
08/10/89	1,093.93	1,094.09	1,092.89	1,092.32	1,092.49	
08/18/89	1,093.62	1,093.76	1,092.64	1,092.03	1,092.19	
10/30/89	1,092.07	1,092.16	1,091.08	1,090.62	1,090.64	
01/24/90	1,090.56	1,090.54	1,089.68	1,089.17	1,089.50	
04/16/90	1,088.66	1,088.78	1,087.83	1,087.23	1,087.32	
07/16/90	1,083.56	1,083.53	1,082.29	1,081.41	1,081.85	
10/17/90	1,079.91	1,079.78	1,078.86	1,078.25	1,078.56	
01/28/91	1,076.52	1,076.54	1,075.46	1,074.64	1,074.91	
04/22/91	1,071.22	1,071.29	1,069.75	1,068.90	1,069.25	
07/17/91	1,063.63	1,063.79	1,061.66	1,060.53	1,061.14	
10/08/91	1,055.22	1,055.41	1,053.28	1,052.12	1,052.69	
01/29/92	1,051.88	1,052.29	1,050.63	1,049.76	1,050.06	1,050.57
04/20/92	1,050.47	1,050.88	1,049.33	1,048.78	1,048.92	1,049.37
07/28/92	1,046.84	1,047.40	-- ^c	1,045.14	1,045.20	1,045.77
10/19/92	1,043.87	1,044.58	-- ^c	1,042.05	1,042.13	1,042.77
01/25/93	1,044.79	1,045.61	-- ^c	1,044.22	1,043.64	1,044.29
06/07/93	1,049.24	1,050.36	-- ^c	1,049.19	1,048.70	1,049.21
09/20/93	1,052.40	1,054.11	-- ^c	1,052.47	1,051.79	1,052.53
12/06/93	1,054.26	1,056.27	-- ^c	1,054.29	1,053.58	1,054.53
03/07/94	1,057.58	1,059.63	-- ^c	1,057.69	1,056.92	1,057.77
06/21/94	1,056.22	1,058.38	-- ^c	1,055.41	1,054.93	1,055.86
09/13/94	1,053.94	1,056.25	-- ^c	1,052.79	1,052.44	1,053.43
12/12/94	1,054.62	1,056.79	-- ^c	1,054.00	1,053.55	1,054.50
03/27/95	1,059.54	1,061.45	-- ^c	1,059.80	1,059.28	1,059.89
06/26/95	1,060.73	1,062.97	-- ^c	1,060.35	1,059.87	1,060.82
09/08/95	1,061.46	1,063.59	-- ^c	1,061.06	1,060.66	1,061.58
12/04/95	1,064.21	1,066.41	-- ^c	1,064.15	1,063.65	1,064.51
03/18/96	1,068.60	1,070.83	-- ^c	1,068.75	1,067.99	1,068.99
06/24/96	1,066.82	1,068.94	-- ^c	1,065.99	1,065.54	1,066.61
09/17/96	1,067.92	1,070.21	-- ^c	1,067.71	1,067.28	1,068.24
12/03/96	1,066.73	1,068.66	-- ^c	1,065.75	1,065.37	1,066.43
03/17/97	1,067.47	1,069.39	-- ^c	1,066.59	1,066.27	1,067.17
06/16/97	1,065.85	1,067.58	-- ^c	1,065.02	1,064.71	1,065.56
09/09/97	1,066.10	1,067.78	-- ^c	1,065.30	1,065.01	1,065.91
12/01/97	1,067.07	1,068.56	-- ^c	1,066.39	1,065.98	1,066.89
03/23/98	1,070.57	1,071.76	-- ^c	1,070.52	1,069.19	1,070.66

^aNGVD = National Geodetic Vertical Datum.

^bMeasurement not recorded.

^cMonitoring well abandoned 05/28/92.

TABLE 2

GROUND WATER MONITORING PARAMETER ANALYTICAL RESULTS
(MARCH 19, 1997 THROUGH APRIL 23, 1998)

Monitoring Well	Date	Conductivity (μ mhos/cm) ^a	pH	TOC ^b (mg/l) ^c	TOX ^d (μ g/l) ^e	Chloride (mg/l)	Sulfate (mg/l)	TCE ^f (μ g/l)	Iron (μ g/l)	Manganese (μ g/l)	Sodium (mg/l)
MW-1	03/19/97	770	7.8	<0.5	<5	170	10	<0.5	100	3.2	53
	06/24/97	810	7.4	<0.5	<5	180	12	<0.5	130	<30	54
	09/30/97	790	7.1	<0.5	7	170	11	<0.5	<50	<30	53
	12/03/97	795	7.0	<0.5	<5	160	11	<0.5	70	<30	52
	03/25/98	810	7.8	<0.5	<5	180	12	<0.5	<50	<30	52
MW-3	03/19/97	600	7.6	<0.5	<5	29	71	<0.5	<50	<0.5	60
	06/18/97	600	7.7	<0.5	<5	31	71	<0.5	<50	<30	52
	09/10/97	600	7.2	<0.5	<5	32	71	<0.5	<50	<30	55
	12/03/97	614	7.3	<0.5	<5	32	72	<0.5	<50	<30	53
	04/23/98	620	7.3	0.6	<5	33	71	<0.5	<50	<30	50
MW-5	03/19/97	530	7.8	<0.5	<5	54	30	<0.5	60	<2.5	56
	06/18/97	530	7.9	<0.5	<5	58	29	<0.5	<50	<30	51
	09/10/97	550	7.3	<0.5	<5	60	28	<0.5	<50	<30	57
	12/03/97	577	7.4	<0.5	<5	63	29	<0.5	<50	<30	54
	03/25/98	570	7.8	<0.5	<5	62	29	<0.5	<50	<30	54
MW-6	03/19/97	550	7.7	<0.5	<5	73	29	<0.5	170	1.6	56
	06/18/97	570	7.9	<0.5	<5	73	33	<0.5	<50	<30	57
	09/10/97	590	7.4	<0.5	<5	71	35	<0.5	<50	<30	57
	12/03/97	599	7.4	<0.5	<5	72	35	<0.5	<50	<30	54
	04/23/98	590	7.5	0.6	<5	77	30	<0.5	140	<30	54
MW-10	03/19/97	600	7.8	<0.5	<5	68	38	<0.5	70	1.1	86
	06/18/97	620	7.9	<0.5	<5	74	43	<0.5	<50	<30	84
	09/10/97	620	7.5	<0.5	<5	75	43	<0.5	<50	<30	84
	12/03/97	638	7.6	<0.5	<5	78	47	<0.5	<50	<30	82
	03/25/98	640	7.9	<0.5	<5	74	43	<0.5	<50	<30	81

^a μ mhos/cm = Micromhos per centimeter.

^bTOC = Total organic carbon.

^cmg/l = Milligrams per liter.

^dTOX = Total organic halogens.

^e μ g/l = Micrograms per liter.

^fTCE = Trichloroethene.

TABLE 3
BACKGROUND WATER QUALITY PARAMETERS

Well No.	Date Sampled	Gross Alpha (pCi/l) ^a	Gross Beta (pCi/l)	Lead (mg/l) ^b	Fluoride (mg/l)	Nitrate (mg/l)	Turbidity (NTUs) ^c
Detection Limits				0.01 ^d -0.0002	0.1	0.4	0.2
MW-1	10/04/88	0.4 ± 2	0.7 ± 2	<0.01	-- ^e	--	--
	01/27/93	0 ± 1	4 ± 2	<0.01	0.2	--	--
	06/09/93	0.4 ± 1	0.7 ± 2	<0.01	0.2	3.9	0.4
	07/14/93	2 ± 2	0 ± 2	<0.01	0.4	4.8	0.9
	08/11/93	1 ± 1	4 ± 4	<0.01	0.3	4.8	0.9
	09/22/93	--	--	--	--	--	0.5
	03/10/94	--	--	--	--	ND	--
	06/22/94	2 ± 2	4 ± 2	<0.0002	0.2	3.6	1.0
MW-3	10/04/88	0.7 ± 1	2 ± 3	<0.01	--	--	--
	01/27/93	0.8 ± 1	2 ± 2	<0.01	0.3	--	--
	06/09/93	2 ± 1	1 ± 2	<0.01	0.2	1.6	<0.2
	07/14/93	2 ± 2	1 ± 2	<0.01	0.3	2.1	<0.2
	08/11/93	4 ± 2	3 ± 4	<0.01	0.2	2.2	0.3
	09/22/93	--	--	--	--	--	<0.2
	03/10/94	--	--	--	--	1.4	--
	06/22/94	1.0 ± 1	2 ± 2	4.9	0.2	3.6	0.3
MW-5 ^f	06/22/94	1.0 ± 1	3 ± 2	<0.0002	0.2	3.6	0.9
MW-6 ^f	06/22/94	0.1 ± 1	2 ± 2	<0.0002	0.2	3.8	0.8
MW-10 ^f	06/22/94	0.4 ± 1	4 ± 2	<0.0002	0.2	3.7	0.8

^apCi/l = Pico curies per liter.

^bmg/l = Milligrams per liter.

^cNTUs = Nephelometric turbidity units.

^dDetection limit lowered from 0.01 to 0.0002 mg/l on 6/22/94.

^eSample was not taken.

^fSamples collected from monitoring wells MW-5, MW-6, and MW-10 during the twenty-third sampling event were analyzed for the background water quality parameters because of a repeated tolerance interval exceedance for sodium during previous sampling events.




EXPLANATION:

--- SITE BOUNDARY

NOTES:

1. BASE MAP FOR U.S.G.S. MINT CANYON, AND NEWHALL CALIFORNIA, QUADRANGLES, 7.5 MINUTE SERIES (TOPOGRAPHIC), PHOTOREMISED 1988.
2. ALL LOCATIONS AND DIMENSIONS ARE APPROXIMATE.



QUADRANGLE LOCATION


0 2,000
Scale
(feet)




FIGURE 1

SITE LOCATION MAP
WHITTAKER CORPORATION, BERMITE FACILITY
22116 WEST SOLEDAD CANYON ROAD
SANTA CLARITA, CALIFORNIA

Project No.	21001.76	Drawn	DWR	Action • Mickelson • Environmental, Inc.
File No.	QMO17SM1	Prepared	PHB	Consulting Scientists, Engineers, and Geologists
Revision	0	Reviewed		5050 Robert J. Mathews Parkway El Dorado Hills, California 95762 (916) 939-7550




LEGEND:



MW-1 MONITORING WELL LOCATION

[1071.76]

GROUND WATER ELEVATION
(FEET ABOVE MEAN SEA LEVEL)



ESTIMATED GROUND WATER CONTOUR (FEET
ABOVE MEAN SEA LEVEL) WITH ARROW
INDICATING INFERRED DIRECTION OF GROUND
WATER FLOW




FIGURE 2


**AREA 317 GROUND WATER MONITORING WELL
LOCATIONS AND ESTIMATED GROUND WATER FLOW
DIRECTIONS (03/23/98)**

Whittaker Corporation, Bermite Facility
22116 West Soledad Canyon Road, Santa Clarita, California

Project No. 21001.75		Drawn AAC	Acton • Mickelson • Environmental, Inc. Consulting Scientists, Engineers, and Geologists 5050 Robert J. Mathews Parkway El Dorado Hills, California 95762 (916) 939-7550
File Name 2100175-001		Prepared RLH	
Revision		Reviewed	
Number 0	Date 5/7/98	Scale: As Noted	

FIGURE 3

**AREA 317 GROUND WATER MONITORING WELLS
POTENTIOMETRIC SURFACE ELEVATIONS**



APPENDIX A

DOCUMENT SUBMITTAL CHRONOLOGY

APPENDIX A

DOCUMENT SUBMITTAL CHRONOLOGY

The following documents have been submitted to Cal-EPA and U.S. EPA, Region IX, in fulfillment of the Closure Plan regarding ground water monitoring at Areas 317 and 342:

- Whittaker Corporation, Bermite Division, Santa Clarita, CA CAD064573108, Facility Closure Plan Modifications, April 1987.
- Revised Ground Water Monitoring Plan for the 317/342 Area, October 8, 1987.
- Proposed Interim Status Ground Water Monitoring Sampling and Analysis Program, December 1987.
- Documentation Report--Construction and Development of Wells for Ground Water Monitoring of the 342 and 317 Areas, February 1988.
- Verification Sampling Results at Selected RCRA Units, March 1988.
- RCRA Ground Water Monitoring System--Proposed Final Configuration, May 1988.
- Ground Water Sampling and Analysis Plan, August 1988.
- RCRA Ground Water Sampling, Quarterly Sampling Report No. 1, December 1988.
- RCRA Ground Water Sampling, Quarterly Sampling Report No. 2, March 1989.
- RCRA Ground Water Sampling, Quarterly Sampling Report No. 3, July 1989.
- Specific Plan for a Ground Water Quality Assessment Program, June 1989.
- Interim Response Action Plan, 317 Area Soil and Ground Water Remediation, June 1989.
- Site Ground Water Sampling and Analysis Plan, Appendix IV of 40 CFR 264.
- RCRA Ground Water Sampling, Quarterly Sampling Report No. 4, September 1989.
- Statistical Analysis--Well MW-2 Versus MW-1 and MW-3, October 1989.

- RCRA Ground Water Sampling, Quarterly Sampling Report No. 5, March 1990.
- RCRA Ground Water Sampling, Quarterly Sampling Report No. 6, May 1990.
- RCRA Ground Water Sampling, Quarterly Sampling Report No. 7, June 1990.
- RCRA Ground Water Sampling, Quarterly Sampling Report No. 8, October 1990.
- RCRA Ground Water Sampling, Quarterly Sampling Report No. 9, January 1991.
- RCRA Ground Water Sampling, Quarterly Sampling Report No. 10, April 1991.
- RCRA Ground Water Sampling, Quarterly Sampling Report No. 11, July 1991.
- RCRA Ground Water Sampling, Quarterly Sampling Report No. 12, October 1991.
- Specific Plan for a Ground Water Quality Assessment Program for the 317 Surface Impoundment Area.
- RCRA Ground Water Sampling, Quarterly Sampling Report No. 13, January 1992.
- Area 317 RCRA Quarterly Ground Water Quality Monitoring Report No. 14 and Report of Monitoring Well MW-10 Installation, January through March 1992.
- Area 317 RCRA Quarterly Ground Water Quality Monitoring Report No. 15, April through June 1992.
- Area 317 RCRA Quarterly Ground Water Quality Monitoring Report No. 16, July through September 1992.
- Water Quality Monitoring and Response Plan for the Interim Status Area 317 Surface Impoundment, October 1992.
- Area 317 RCRA Quarterly Ground Water Quality Monitoring Report No. 17, October through December 1992.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 18, January through March 1993.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 19, April through June 1993.

- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 20, July through September 1993.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 21, October through December 1993.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 22, January through March 1994.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 23, April through June 1994.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 24, June through September 1994.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 25, October through December 1994.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 26, January through March 1995.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 27, April through June 1995.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 28, July through September 1995.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 29, October through December 1995 and Annual 1995 Summary.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 30, January through March 1996.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 31, April through June 1996.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 32, July through September 1996.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 33, October through December 1996.

- Area 317 RCRA Quarterly Ground Water Monitoring, 1996 Annual Summary Report.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 34, January through March 1997.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 35, April through June 1997.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 36, July through September 1997.
- Area 317 RCRA Quarterly Ground Water Monitoring Report No. 37, October through December 1997 and 1997 Annual Summary

APPENDIX B

GROUND WATER SAMPLING PROCEDURES

APPENDIX B

GROUND WATER SAMPLING PROCEDURES

Initial depth to water measurements are collected prior to the onset of monitoring well evacuation activities. Operation of the pumps in monitoring wells MW-1, MW-3, MW-5, MW-6, and MW-10 is then initiated to evacuate stagnant water. Pumping durations to evacuate these five monitoring wells are summarized in Table B-1. Prior to sample collection, the pumping rate for each monitoring well is reduced in a 1/4-inch-diameter tube. In accordance with the "Ground Water Sampling and Analysis Plan," dated August 1988, evacuated ground water from monitoring wells MW-1, MW-3, MW-5, MW-6, and MW-10 is discharged to the ground surface, downgradient from each monitoring well.

Well Stabilization

Well stabilization measurements are periodically collected after well evacuation activities are initiated. Stabilization measurements for pH, temperature, turbidity, and conductivity are taken three times prior to sampling of each well to increase the likelihood that representative ground water samples are collected. Table B-2 summarizes the results of the stabilization tests.

Sample Containers

Sample containers are precleaned and sealed, and statistically certified as clean and free of volatile organic and metal compounds. Table B-3 lists the laboratory analytical methods, sample volume, and containers used.

Sample Labeling

Sample identification labels are filled out in the field at the time of sample collection in accordance with the "Ground Water Sampling and Analysis Plan," dated August 1988. A sample identification system has been established to clearly and properly label samples. Each label identifies the monitoring well number, analytical parameter required, and quarterly sampling event number.

Sample Collection

Sampling Volumetric Flow Rate

A Teflon sampling valve and stem is installed into the invert of the well discharge pipe of each monitoring well to minimize aeration and agitation of the collected ground water sample. The flow rates in the monitoring wells are reduced in a 1/4-inch-diameter tube prior to sampling.

Field Sample Preservation

Ground water samples collected for TOC and TOX are preserved by adjusting the pH. A 50 percent sulfuric acid solution is added to the sample containers after filtration of the ground water sample to lower the pH. The pH of the water sample is monitored with an electric pH meter as the acid is added with a small pipette. Acid is added until a pH of less than 2 is achieved.

Following collection, labeling, and sealing, samples are placed on ice in a cooler.

Field and Trip Sample Blanks

During each quarterly sampling event, field and trip blanks are analyzed for TCE, TOC, and TOX in accordance with the "Ground Water Sampling and Analysis Plan," dated August 1988.

The trip blanks are prepared in the laboratory, transferred to the site in coolers, stored in the refrigerator overnight, transferred to each sampling location during sampling activities, and stored with collected ground water samples throughout the sampling event and delivered to the laboratory.

The field blanks are prepared in the field using water provided by the analytical laboratory. These field blanks, once prepared, are stored with the ground water samples throughout the sampling event and delivered to the laboratory.

Field Quality Assurance/Quality Control

Washing of Field Test Equipment

To minimize the potential for cross-contamination between well samples, field equipment used during sampling activities is decontaminated between each well. Decontamination procedures involve cleaning and rinsing with deionized water before and after each sample is collected at each well. The mercury thermometer, pH probe, sulfuric acid eye droppers, turbidity meter, conductivity probe, and the water level meter probe are all decontaminated between samples.

Unused sampling gloves are worn by sampling personnel prior to sealing the sample containers with the chain-of-custody seals.

Sample Container Labeling and Seals

As previously stated, the sample containers are labeled in the field as each sample is collected. A unique sample identification number is assigned to each ground water sample. Chain-of-custody seals are then placed on the sample containers after sampling and labeling. The ground water samples are placed on ice in a cooler, and the cooler is sealed with chain-of-custody seals prior to shipment to the laboratory.

Chain-of-Custody and Sample Analysis Request Forms

Chain-of-custody forms are filled out at the time of sample collection and kept with the samples until delivered to the laboratory. Copies of the signed chain-of-custody forms are provided in Appendix C.

Sample analysis request forms are also filled out at the time of sample collection and kept with the samples until delivered to the laboratory. Sample analysis request forms are used to inform the laboratory of the analysis to run on each ground water sample. Copies of the sample analysis request forms are provided in Appendix D.

Delivery of Samples to Laboratory

Ground water samples are delivered to FGL in Santa Paula, California, by personnel of Whittaker after sampling activities are completed. FGL is approximately 45 minutes by car from the site. Maximum and minimum thermometers are placed in each cooler for temperature verification. Upon arrival at the laboratory, the temperature is recorded on the sample analysis request form. The temperature of the samples is kept below 4° C.

Security

Security measures are implemented to minimize the likelihood that unauthorized personnel have access to the wells or ground water samples before, during, or after sampling activities. The site is fenced-in with locking gates and has 24-hour security personnel present. Each monitoring well has a locking cap to deter unauthorized access to the well. The ground water samples are handled by Whittaker personnel only during sampling activities and delivery to FGL.

TABLE B-1

AREA 317 WELL EVACUATION
WHITTAKER CORPORATION, BERMITE FACILITY

Well Number	Date Pump Started	Evacuation	Sampling*	Time and Date of Sample Collection
		Approximate Duration of Pumping (hours)	Duration of Pumping (minutes)	
MW-1	03-24-98	22.5	10	1010 (03-25-98)
MW-3	04-22-98	21.25	9	0830 (04-23-98)
MW-5	03-24-98	22	13	0920 (03-25-98)
MW-6	04-22-98	21.75	10	0850 (04-23-98)
MW-10	03-24-98	22.25	9	0948 (03-25-98)

*Flow rate from wells was reduced prior to sampling.

TABLE B-2

WELL STABILIZATION TESTS
WHITTAKER CORPORATION, BERMITE FACILITY

Well	Time and Date	Temperature (°C.)	pH	Conductivity (μ mhos/cm) ^a	Turbidity (NTUs) ^b
MW-1	1135 (03-24-98)	23.2	7.58	798	20.1
	1550 (03-25-98)	22.5	7.57	804	2.85
	1820 (03-25-98)	21.4	7.83	801	1.96
MW-3	1110 (04-22-98)	24.1	7.11	597	2.00
	1515 (04-22-98)	23.8	7.69	608	2.27
	0710 (04-23-98)	23.4	8.07	618	1.79
MW-5	1125 (03-24-98)	22.7	7.51	556	5.18
	1540 (03-24-98)	22.6	7.75	583	2.85
	0810 (03-25-98)	22.1	7.77	574	2.80
MW-6	1115 (04-22-98)	23.4	7.87	590	39.8
	1520 (04-22-98)	23.3	7.79	584	15.97
	0715 (04-23-98)	23.0	8.21	594	3.10
MW-10	1130 (03-24-98)	22.9	7.47	629	7.55
	1545 (03-24-98)	22.4	7.56	641	3.05
	0815 (03-25-98)	21.9	7.86	644	2.68

^a μ mhos/cm = Micromhos per centimeter.

^bNTUs = Nephelometric turbidity units.

TABLE B-3

LABORATORY ANALYTICAL METHODS AND SAMPLE VOLUME
AND CONTAINER REQUIREMENTS
AREA 317 GROUND WATER MONITORING WELLS
WHITTAKER CORPORATION, BERMITE FACILITY

Constituent	Analytical Method	Sample Volume	Container Type
Ground Water Monitoring Parameters			
pH/Conductivity	4500-HB/2510B	16 oz.	Plastic
Total Organic Carbon	EPA 415.1	250 ml.	Amber glass-TFE cap
Total Organic Halogen	EPA 9020	250 ml.	Amber glass-TFE cap
Trichloroethene	EPA 624	3 x 40 ml.	Amber glass-TFE cap
Sulfate/Chloride	300.0/300.0	32 oz.	Plastic
Sodium/Iron/Manganese	200.7/200.7/200.7	32 oz.	Plastic

APPENDIX C

CHAIN-OF-CUSTODY FORMS



CHAIN OF CUSTODY

Laboratory Copy (1 of 3)

QUARTERLY

Corporate Offices & Laboratory
P.O. Box 272 / 853 Corporation Street
Santa Paula, CA 93061-0272

Office and Laboratory
2500 Stagecoach Road
Stockton, CA 95215
TEL: (209) 942-0181

Field Office
Visalia, California
TEL: (209) 734-9473
Mobile: (209) 737-2399

APR 10 1998



CHAIN OF CUSTODY

QUARTERLY

Laboratory Copy (1 of 3)

MAY - 6 1998

Office and Laboratory
2500 Stagecoach Road
Stockton, CA 95215
TEL: (209) 942-0181

Field Office
Visalia, California
TEL: (209) 734-9473
Mobile: (209) 737-2399



ENVIRONMENTAL

QUARTERLY

CHAIN OF CUSTODY

Laboratory Copy (1 of 3)

Client : Bermite Division of Whittaker Address: 22116 W. Soledad Canyon Road Santa Clarita CA 91350 Phone : (805)259-2242 Fax : (805)259-2244				TEST DESCRIPTIONS - See reverse side for Container, Preservative and Sampling information											
Project Name : MW5 Qtrly 317 Area Monitoring Contact person : Mr. Glen Abdun-nur Purchase order Number: QA/QC report required: Yes No				Type of Sampling: Composite(C) Grab(G)											
Sampler(s): <u>[Signature]</u> Comp sampler setup Date: ___/___/___ Time: ___:___ Rush Results due By: ___/___/___ Date Received: ___/___/___ Lab Number: <u>802142</u>				Type of Sample **SEE REVERSE SIDE**											
Samp Num	Location/Description	Date Sampled	Time Sampled	(P) Potable	(NP) Non-Potable	Wet Chem - E.C., pH Cont. 16oz.(p)	TOC Cont. 250ml(at)-H ₂ SO ₄	TOX Cont. 250ml(at)-HNO ₃	Wet Chem - Cl, SO ₄ Cont. 32oz.(p)	EPA 624 Cont. 40ml(v)	Trace Metals-P - Fe, Mn, Na Cont. 72oz.(p)	Sample Temp °C	Sample Cond.: ___ Sealed? ___		
1	MW5/A/38	3/25/98	0925	G	MW	1									
2	MW5/B/38	3/25/98	0926	G	MW		1.								
3	MW5/C/38	3/25/98	0927	G	MW			1							
4	MW5/H/38	3/25/98	0929	G	MW				1.						
5	MW5/O/38	3/25/98	0933	G	MW					3					
6	MW5/R/38	3/25/98	0931	G	MW						1				
Misc. Notes:				Relinquished By: <u>[Signature]</u> 3-25-98 12:29		Date: Time:		Relinquished By: <u>[Signature]</u> 3-25-98 1:35		Date: Time:		Relinquished By: <u>[Signature]</u> 3-25-98 1:35		Date: Time:	
Final Sample Disposition:				Received by: <u>[Signature]</u> 3-25-98 12:30		Date: Time:		Received by: <u>[Signature]</u> 3-25-98 1:35		Date: Time:		Received by: <u>[Signature]</u> 3-25-98 1:35		Date: Time:	
Lab Disposal: ___/___/___ Returned to Client				Meth. of Disposal: ___ Date Ret. ___/___/___											

APR 10 1998



CHAIN OF CUSTODY

QUARTERLY

Laboratory Copy (1 of 3)

Client : Bermite Division of Whittaker Address: 22116 W. Soledad Canyon Road Santa Clarita CA 91350 Phone : (805)259-2242 Fax : (805)259-2244				TEST DESCRIPTIONS - See reverse side for Container, Preservative and Sampling information											
Project Name : MWS-1A Qtrly 317 Area Monitor. Contact person : Mr. Glen Abdun-nur Purchase order Number: QA/QC report required: Yes No				**SEE REVERSE SIDE**											
Sampler(s): <u>[Signature]</u> Comp sampler setup Date: ___/___/___ Time: ___:___ Rush Results due By: ___/___/___ Date Received: ___/___/___ Lab Number: <u>802141</u>				Type of Sampling: Composite(C) Grab(G) Type of Sample (P) Potable (NP) Non-Potable TOC Cont. 250ml(at)-H2SO4 TOX Cont. 250ml(at)-HNO3 EPA 624 Cont. 40ml(v)											
Smp Num Location/Description Date Sampled Time Sampled				Type of Sample (P) Potable (NP) Non-Potable											
1 MWS/B38/1A 3/25/98 0939				1											
2 MWS/C38/1A 3/25/98 0940				1											
3 MWS/O38/1A 3/25/98 0941				3											
Misc. Notes:				Relinquished By: <u>[Signature]</u> Date: Time: 3-25-98 12:29 Received by: <u>[Signature]</u> Date: Time: 3-25-98 12:30											
Final Sample Disposition: Lab Disposal: ___/___/___ Returned to Client Meth. of Disposal: ___ Date Ret. ___/___/___				Relinquished By: <u>[Signature]</u> Date: Time: 3-25-98 1:35 Received by: <u>[Signature]</u> Date: Time: 3-25-98 1:35											

Corporate Offices & Laboratory
P.O. Box 272 : 853 Corporation Street
Santa Paula, CA 93061-0272
TEL: 805-550-2010

Office and Laboratory
2500 Stagecoach Road
Stockton, CA 95215
TEL: (209) 942-0181

APR - 7 1998

Field Office
Visalia, California
TEL: (209) 734-9473
Mobile: (209) 737-2399



ENVIRONMENTAL

QUARTERLY

CHAIN OF CUSTODY

Laboratory Copy (1 of 3)

Client : Bermite Division of Whittaker Address: 22116 W. Soledad Canyon Road Santa Clarita CA 91350 Phone : (805)259-2242 Fax : (805)259-2244 2-4570				TEST DESCRIPTIONS - See reverse side for Container, Preservative and Sampling information																		
Project Name : MW6 Qtrly 317 Area Monitoring Contact person : Mr. Glen Abdun-nur Purchase order Number: QA/QC report required: Yes No				Type of Sampling: Composite(C) Grab(G)	Type of Sample	(P) Potable (NP) Non-Potable	Wet Chem - E.C., pH Cont. 16oz.(p)	TOC Cont. 250ml (at)-H ₂ SO ₄	TOX Cont. 250ml (at)-HNO ₃	Wet Chem - Cl, SO ₄ Cont. 32oz.(p)	EPA 624 Cont. 40ml (v)	Trace Metals-P - Fe, Mn, Na Cont. 32oz.(p)-HNO ₃										
Sampler(s):	Comp sampler setup Date: / / Time: :	Rush Results due By: / /	Date Received: / /	Lab Number: 802916																		
Sam Num	Location/Description	Date Sampled	Time Sampled	Type of Sample	Type of Sample	(P) Potable (NP) Non-Potable	Wet Chem - E.C., pH Cont. 16oz.(p)	TOC Cont. 250ml (at)-H ₂ SO ₄	TOX Cont. 250ml (at)-HNO ₃	Wet Chem - Cl, SO ₄ Cont. 32oz.(p)	EPA 624 Cont. 40ml (v)	Trace Metals-P - Fe, Mn, Na Cont. 32oz.(p)-HNO ₃										
1	MW6/A/ 38	4/23/98	0853	G	MW		1															
2	MW6/B/ 38		0852	G	MW			1														
3	MW6/C/ 38		0854	G	MW				1													
4	MW6/H/ 38		0856	G	MW					1												
5	MW6/O/ 38		0800	G	MW						3											
6	MW6/R/ 38		0858	G	MW							1										
Misc. Notes:				Relinquished By: [Signature] Date: 4-23-98 Time: 15				Relinquished By: [Signature] Date: 4/23/98 Time: 1028				Relinquished By: [Signature] Date: [] Time: []										
Final Sample Disposition:				Received by: [Signature] Date: 4/23/98 Time: 0915				Received by: [Signature] Date: 4/23/98 Time: 1028				Received by: [Signature] Date: [] Time: []										
Lab Disposal: / / Returned to Client				Meth. of Disposal: / / Date Ret. / /																		



ENVIRONMENTAL

QUARTERLY

CHAIN OF CUSTODY

Laboratory Copy (1 of 3)

Client : Bermite Division of Whittaker

Address: 22116 W. Soledad Canyon Road

Santa Clarita CA 91350

Phone : (805)259-2242

Fax : (805)259-2244

2-4570

Project Name : MM6-1A Qtrly 317 Area Monitor.

Contact person : Mr. Glen Abdun-nur

Purchase order Number:

QA/QC report required: Yes No

Sampler(s): *[Signature]*

Comp sampler setup Date: ___/___/___ Time: ___:___

Rush Results due By: ___/___/___

Date Received: ___/___/___

Lab Number:

402140

TEST DESCRIPTIONS - See reverse side for Container, Preservative and Sampling information

Address: 22116 W. Soledad Canyon Road				Santa Clarita CA 91350		Phone : (805)259-2242		Fax : (805)259-2244		2-4570	
Project Name : MW6-1A Qtrly 317 Area Monitor.											
Contact person : Mr. Glen Abdun-nur											
Purchase order Number:											
QA/QC report required: Yes No											
Sampler(s):											
Comp sampler setup Date: / / Time: :											
Rush Results due By: / /											
Date Received: / /											
Lab Number: 602140											
Type of Sampling: Composite(C) Grab(G)											
Type of Sample											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											
Type of Sample (NP) Non-Potable											
Type of Sample (P) Potable											



ENVIRONMENTAL

QUARTERLY

CHAIN OF CUSTODY

Laboratory Copy (1 of 3)

Client : Bermite Division of Whittaker Address: 22116 W. Soledad Canyon Road Santa Clarita CA 91350 Phone : (805)259-2242 Fax : (805)259-2244 2-4570				TEST DESCRIPTIONS - See reverse side for Container, Preservative and Sampling information												Sample Temp °C: Sample Cond.: Sealed?						
Project Name : MW10 Qtrly 317 Area Monitoring Contact person : Mr. Glen Abdun-nur Purchase order Number: QA/QC report required: Yes No																						
Sampler(s): Comp sampler setup Date: / / Time: : Rush Results due By: / / Date Received: / / Lab Number: 502144																						
Samp Num	Location/Description	Date Sampled	Time Sampled	Type of Sampling: Composite(C) Grab(G)	Type of Sample	(P) Potable (NP) Non-Potable	Wet Chem - E.C., pH Cont. 16oz.(p)	TOC Cont. 250ml(at)-H ₂ SO ₄	TOX Cont. 250ml(at)-HNO ₃	Wet Chem - Cl, SO ₄ Cont. 32oz.(p)	EPA 624 Cont. 40ml(V)	Trace Metals-P - Fe, Mn, Na Cont. 32oz.(p)										
1	MW10/A/38	3/25/98	0948	G	MW		1															
2	MW10/B/38	3/25/98	0949	G	MW			1														
3	MW10/C/38	3/25/98	0951	G	MW				1													
4	MW10/H/38	3/25/98	0953	G	MW					1												
5	MW10/O/38	3/25/98	0957	G	MW						3											
6	MW10/R/38	3/25/98	0955	G	MW							1										
Misc. Notes:				Relinquished By: [Signature] 3-25-98 12:28				Relinquished By: [Signature] 3-25-98 1:35				Relinquished By:				Date: Time:						
Final Sample Disposition:				Received by: [Signature] 3-25-98 12:38				Received by: [Signature] 3-25-98 1:35				Received by:				Date: Time:						
Lab Disposal: / / Returned to Client				Meth. of Disposal: Date Ret. / /																		

APR 11 1998

CLIENT DETAILS

SECTION I

Client: _____
Customer Number: _____
Address: _____
Phone: _____
FAX: _____
Project name: 802915
Contact person: _____
Billing Information (if different from above)
Name: FGL ENVIRONMENTAL
Address: PO BOX 272
Santa Paula, CA 93061-0272
Phone: _____
FAX: _____
Contact person: _____
Purchase order/contract/FGL quote number: _____
Pre Log Required: yes _____ no _____

SAMPLING

SECTION II

Sampler (s): Abdun-Nur/Bricker
Comp Sampler Set up Date: _____ Time: _____
Time: _____ Mileage: _____

REPORT INFORMATION

SECTION III

Rush Analysis: 5 Days _____ 2 Days _____ 24 hrs. _____
Subject to surcharge
QA/QC report required: yes _____ no _____
Electronic Data Transfer: yes _____ no _____
If yes, To: State _____ Client _____ Other _____
Lab number: 802915
Lab Loc: SP ☐ STK ☐ VI ☐ _____

SAMPLE INFORMATION

SECTION IV

Sample Number	Location/Description	Date Sampled	Time Sampled	Type of Sampling: Composite (C) Grab (G)	Number of Containers	Type of Containers: (G) Glass (P) Plastic (V) VOA (MT) Metal Tube	(P) Potable (NP) Non-Potable	(SW) Surface Water (MW) Monitoring Well	(GW) Ground Water (TB) Travel Blank	(WW) Wastewater (DW) Drinking Water	(S) Soil (SLG) Sludge (SLD) Solid (O) Oil	BacT: (Sys) System (SRC) Source (W) Waste	BacT: Routine (ROUT) Repeat (RPT) Other (OTH) Replace (RPL)	(LT) Leaf Tissue (PET) Petiole Tissue (PRD) Produce	Preservative: (1) NaOH + ZnAc, (2) NaOH, (3) HCl, (4) H2SO4, (5) HNO3, (6) Na2S2O3, (7) Other _____	ANALYSES REQUESTED	Sample Condition: Received Intact (L) Leaking (B) Broken (HS) VOA Headspace Temp: Ambient _____ Chilled _____ Actual _____	Custody Seal (Y) (N)
2	MW3/B/38	4/23/98	0831	G	1	G	MW											

REMARKS

SECTION V

WECK

CUSTODY

SECTION VI

Relinquished by and subject to the terms and conditions on the reverse of this document:

Received by: C. Dorley Date: 4/23/98 Time: 1410
Received by: [Signature] Date: 4/24 Time: 10:25a
Relinquished by: _____ Date: _____ Time: _____
Received by: _____ Date: _____ Time: _____

Relinquished by: _____ Date: _____ Time: _____
Received by: _____ Date: _____ Time: _____
Relinquished by: _____ Date: _____ Time: _____
Received by: _____ Date: _____ Time: _____

CLIENT DETAILS

SECTION I

Client: _____
Customer Number: _____
Address: _____
Phone: _____
FAX: _____
Project name: 802916
Contact person: _____
Billing Information (if different from above)
Name: EGL ENVIRONMENTAL
Address: PO Box 272
Santa Paula, CA 93061-0272
Phone: _____
FAX: _____
Contact person: _____
Purchase order/contract/FGL quote number: _____
Pre Log Required: yes _____ no _____

SAMPLING

SECTION II

Sampler(s): Abdun-Nur BRICKER
Comp Sampler Set up Date: _____ Time: _____
Time: _____ Mileage: _____

REPORT INFORMATION

SECTION III

Rush Analysis: 5 Days _____ 2 Days _____ 24 hrs. _____
Subject to surcharge
QA/QC report required: yes _____ no _____
Electronic Data Transfer: yes _____ no _____
If yes, To: State _____ Client _____ Other _____
Lab number: 802916
Lab Loc: SP ☐ STK ☐ VI ☐ _____

SAMPLE INFORMATION

SECTION IV

Sample Number	Location/Description	Date Sampled	Time Sampled	Type of Sampling: Composite (C) Grab (G)	Number of Containers	Type of Containers: (G) Glass (P) Plastic (V) VOA (MT) Metal Tube	(P) Potable (NP) Non-Potable	(SW) Surface Water (MW) Monitoring Well	(GW) Ground Water (TB) Travel Blank	(WW) Wastewater (DW) Drinking Water	(S) Soil (SLG) Sludge (SLD) Solid (O) Oil	BacT: (Sys) System (SRC) Source (W) Waste	BacT: Routine (ROUT) Repeat (RPT) Other (OTH) Replace (RPL)	(LT) Leaf Tissue (PET) Petiole Tissue (PRD) Produce	Preservative: (1) NaOH + ZnAc, (2) NaOH, (3) HCl, (4) H2SO4, (5) HNO3, (6) Na2S2O3, (7) Other _____	ANALYSES REQUESTED	Sample Condition: Received Intact (L) Leaking (B) Broken (HS) VOA Headspace Temp: Ambient _____ Chilled _____ Actual _____	Custody Seal (Y) (N)
2	8 MW6/B/38	4/23/98	0852	G	1	G	MW									X		

REMARKS

SECTION V

WECK

CUSTODY

SECTION VI

Relinquished by and subject to the terms and conditions on the reverse of this document:

Received by: C. Derley Date: 4/23/98 Time: 1410
Received by: P. Camo Date: 4/24 Time: 10:28
Relinquished by: _____ Date: _____ Time: _____
Received by: _____ Date: _____ Time: _____

Relinquished by: _____ Date: _____ Time: _____
Received by: _____ Date: _____ Time: _____
Relinquished by: _____ Date: _____ Time: _____
Received by: _____ Date: _____ Time: _____

APPENDIX D

SAMPLE ANALYSIS REQUEST FORMS

SAMPLE ANALYSIS REQUEST

Sampling Information

Project No. 85-01.4 Project Name: 317 AREA BERMITE 38TH. QTR. SAMPLING
 Sampler Name: GLEN ABDUN-NOR/TIM BRICKER Tele. No. (805) 259-2241
 Name of Person Receiving Samples: Shawn Teck
 Date Samples Received: 3/25/98
 Internal Temperature of Sample Container: 5°C
 Notes on Samples: _____

Analysis Required

Sample I.D.	Laboratory I.D.	PH, EC	TOC	TOX	SULFATE CHLORIDE	EPA 624 TCE ONLY	IRON, MANGANESE, SODIUM
MW1/A/38	802143-1	X					
MW1/B/38	802143-2		X				
MW1/C/38	802143-3			X			
MW1/H/38	802143-4				X		
MW1/O/38	802143-5					X	
MW1/R/38	802143-6						X
MW5/A/38	802142-1	X					
MW5/B/38	802142-2		X				
MW5/C/38	802142-3			X			
MW5/H/38	802142-4				X		
MW5/O/38	802142-5					X	
MW5/R/38	802142-6						X

SAMPLE ANALYSIS REQUEST

Sampling Information

Project No. 85-01.4 Project Name: 317 AREA BERMITE 38TH.GTR. SAMPLING
 Sampler Name: GLEN ABDUN-NUR/TIM BRICKER Tele. No. (805) 259-2241
 Name of Person Receiving Samples: Stacey Berrington
 Date Samples Received: 4/23/98
 Internal Temperature of Sample Container: 0
 Notes on Samples: _____

Analysis Required

Sample I.D.	Laboratory I.D.	PH, EC	TOC	TOX	SULFATE, CHLORIDE	EPA 624 TCE ONLY	IRON, MANGANESE, SODIUM
MW3/A/38	802915	X					
MW3/B/38			X				
MW3/C/38				X			
MW3/H/38					X		
MW3/O/38						X	
MW3/R/38							X
MW6/A/38	802916	X					
MW6/B/38			X				
MW6/C/38				X			
MW6/H/38					X		
MW6/O/38						X	
MW6/R/38							X

SAMPLE ANALYSIS REQUEST

Sampling Information

Project No. 85-01.4

Project Name: BERMITE 38TH. QTR. SAMPLING

Sampler Name: GLEN ABDON-NUR/TIM BRICKER

Tele. No. (805) 259-2241

Name of Person Receiving Samples: Shawn Peck

Date Samples Received: 3/25/98

Internal Temperature of Sample Container: 5°C

Notes on Samples: _____

Analysis Required


Sample I.D.	Laboratory I.D.	pH EC	TOC	TOX	SULFATE, CHLORIDE	EPA 624 TCE ONLY	IRON, MANGANESE, SODIUM
MW10/A/38	802144-1	X					
MW10/B/38	802144-2		X				
MW10/C/38	802144-3			X			
MW10/H/38	802144-4				X		
MW10/O/38	802144-5					X	
MW10/R/38	802144-6						X
MW5/B/38/1A	802141-1		X				
MW5/C/38/1A	802141-2			X			
MW5/O/38/1A	802141-3					X	
MW6/B/38/1A	802140-1		X				
MW6/C/38/1A	802140-2			X			
MW6/O/38/1A	802140-3					X	


APPENDIX E

FGL QUALITY ASSURANCE/QUALITY CONTROL PROGRAM

FGL ENVIRONMENTAL

QUALITY ASSURANCE MANUAL

Reviewed by:  6/4/96
Yee Ren, M.S. Date
Data Validator

Concurred by:  6/4/96
Kurt Wilkinson, B.S. Date
Quality Assurance Director


Approved by:  6/4/96
Darrell H. Nelson, B.S. Date
Laboratory Director

TABLE OF CONTENTS

<u>Section</u>	<u>Revision</u>	<u>Date</u>	<u>Pages</u>
1 Title Page	2.2	5-22-96	1
2 Table of Contents	2.5	5-22-96	3
3 QA Plan Description	2.2	5-22-96	2
4 Laboratory Organization and Responsibilities	2.4	5-22-96	18
5 Quality Assurance Objectives for Measurement Data in Terms of Precision, Accuracy, Completeness, and Detection Limits for Reporting	2.2	5-22-96	33
6 Sampling Procedures	2.3	5-22-96	16
7 Sample Custody	2.1	10-3-94	7
8 Calibration Procedures and Frequency	2.3	5-22-96	6
9 Analytical Procedures	2.3	5-22-96	14
10 Data Reduction, Validation, and Reporting	2.2	5-9-95	2
11 Internal Quality Control Checks	2.2	5-22-96	19
12 Performance and System Audits	2.3	5-22-96	31
13 Preventative Maintenance	2.2	5-9-95	5
14 Specific Routine Procedures Used to Assess Data Precision, Accuracy & Completeness	2.2	5-9-95	3
15 Corrective Actions	2.1	10-3-94	3
16 Quality Assurance Reports to Management	2.1	10-3-94	3
Appendix A - Equipment List	2.4	5-22-96	6
Appendix B - Document Control and Records Management	1.0	9-22-95	2

LIST OF TABLES

- Table 5-1 - Quality Assurance Objectives for Drinking Water Methods**
- Table 5-2 - Quality Assurance Objectives for Wastewater / Hazardous Waste Liquid Methods**
- Table 5-3 - Quality Assurance Objectives for Solid Waste / Hazardous Waste Methods**
- Table 5-4 - Quality Assurance Objectives for Ambient Air / Air Pollution Methods**
- Table 6-1 - Recommended Sample Containers, Preservation and Holding Times**
- Table 8-1 - GC/MS Volatile Organic and Air Toxics Key Ion Abundance Tuning Criteria using BFB**
- Table 8-2 - GC/MS Semivolatile Organic Key Ion Abundance Tuning Criteria using DFTPP**
- Table 9-1 - Specific Analytical Drinking Water Methods**
- Table 9-2 - Specific Analytical Wastewater / Hazardous Waste Liquid Methods**
- Table 9-3 - Specific Analytical Solid Waste / Hazardous Waste Methods**
- Table 9-4 - Specific Analytical Ambient Air / Air Pollution Methods**
- Table 11-1 - Quality Controls for Drinking Water Methods**
- Table 11-2 - Quality Controls for Wastewater / Hazardous Waste Liquid Methods**
- Table 11-3 - Quality Controls for Solid Waste / Hazardous Waste Methods**
- Table 11-4 - Quality Controls for Ambient Air / Air Pollution Methods**

LIST OF FIGURES

- Figure 4-1 - Organization Chart - Corporate Personnel**
- Figure 4-2 - Organization Chart - Santa Paula Laboratory**
- Figure 4-3 - Organization Chart - Stockton Laboratory**
- Figure 4-4 - Organization Chart - Visalia Field Services**
- Figure 7-1 - Chain of Custody**
- Figure 9-1 - FGL SOP Format**
- Figure 11-1 - FGL Control Chart for LCS**
- Figure 11-2 - FGL Control Chart for MS/MSD and RPD**
- Figure 12-1 - FGL QA Audit Form**

LIST OF FIGURES continued

- Figure 12-2 - FGL Santa Paula - California ELAP Certification**
- Figure 12-3 - FGL Stockton - California ELAP Certification**
- Figure 12-4 - FGL Santa Paula - Utah Department of Health Certification**
- Figure 12-5 - FGL Santa Paula - Hawaii Department of Health Certification**
- Figure 13-1 - Repair/Maintenance Logbook Cover**
- Figure 13-2 - Repair/Maintenance Logbook Record**
- Figure 15-1 - Corrective Action Report Form**
- Figure 16-1 - FGL QC Inspection Summary Report Form**

QA Plan Description

FGL Environmental's Quality Assurance Policy

"Management and staff are committed to providing data that is scientifically valid, legally defensible and of known precision and accuracy in order to meet or exceed the data quality objectives of our clientele."

"Management and staff are committed to providing our clientele with services that satisfy their definitions and expectations of quality."

This manual describes the protocols utilized by FGL Environmental to ensure adherence with this policy. It outlines quality control procedures to be used with field and analytical methods. It also includes the individual analysis data quality objectives. Detailed project-specific FGL standard operating procedures to supplement this manual are provided when requested or deemed necessary.

FGL's QA manual is based on the 16 essential elements contained in the U.S. Environmental Protection Agency manual "Interim Guidelines and Specifications for Preparing Quality Assurance Project Plans," QAMS-005/80. Two additional appendices have been added. The first appendix lists the laboratory equipment. The second describes FGL's document control program.

As of the date of revision, this manual reflects the current quality assurance program in effect and procedures in the process of being adopted.

References for this manual include field and laboratory methods published by the U.S. Environmental Protection Agency and other agencies mainly through the following sources:

- (1) "Standard Methods for the Analysis of Water and Wastewater," 18th Edition, 1992.
- (2) "Methods for Chemical Analysis in Waters and Waste," (MCAWW) EPA-600/4-79-020
- (3) "Methods for the Determination of Organic Compounds in Drinking Water," EPA Method Book, EPA-600/4-88-039, December 1988.
- (4) "Methods for the Determination of Organic Compounds in Drinking Water-Supplement I," EPA Method Book, EPA-600/4-90-020, July 1990.
- (5) "Methods for the Determination of Organic Compounds in Drinking Water-Supplement II," EPA Method Book, EPA-600/4-90-020, July 1990.
- (6) "Methods for Organic Chemical Analysis of Municipal and Industrial Wastewater," EPA Method Book, EPA 600/4-82-057, July 1982.
- (7) "Methods for Evaluating Solid Waste," EPA Method Book, SW-846, 3rd edition, and Proposed Revisions
- (8) "Prescribed Procedures for Measurement of Radioactivity in Drinking Water," EPA Method Book, EPA-600/4-80-032, August 1980.
- (9) "Handbook for Sampling and Sample Preservation of Water and Wastewater," EPA Method Book, EPA-600/4-82-029, September 1982.
- (10) "Eastern Environmental Radiation Facility Radiochemistry Procedures Manual," EPA Method Book, EPA 520/5-84-006, August 1984.

QA Plan Description

References continued

- (11) "Environmental Measurements Laboratory Procedures," HASL-300, 27th Edition, February 1992.
- (12) "Compendium of Methods for the Determination of Toxic Organic Compounds in Ambient Air," EPA Method Book, EPA-600/4-, June 1988.
- (13) "Technical Assistance Document for Sampling and Analysis of Toxic Organic Compounds in Ambient Air," EMSL, EPA Method Book, EPA-600/4-83-027, 1983


Laboratory Organization and Responsibilities

Personnel of FGL Incorporated

Our commitment to providing a superior service requires the high caliber staff employed by FGL. These professionals have considerable experience to meet the technical demand of environmental analysis. Figures 4-1 - 4-4 show the organization for the corporation and each laboratory or field service facility. Following the figures are qualification summaries for key personnel.


Laboratory Organization and Responsibilities

Figure 4-1 Organization Chart Corporate Personnel




Laboratory Organization and Responsibilities


Figure 4-2 Organization Chart Santa Paula Laboratory



Laboratory Organization and Responsibilities
Figure 4-3 Organization Chart Stockton Laboratory



Laboratory Organization and Responsibilities
Figure 4-4 Organization Chart Visalia Field Office



Laboratory Organization and Responsibilities

Key Personnel Qualification Summary - Santa Paula

Darrell H. Nelson

Current Responsibilities:

President and Lab Director

- To oversee all operational aspects of the Santa Paula and Stockton laboratories
- To guide and direct managers towards the corporation's goals
- To report to the Board of Directors and the stockholders

Work Experience:

Assistant Manager, FGL

- Chemical analysis of drinking and waste waters, soils and plant materials
- Supervision of a number of lab operations including work scheduling and field services
- Customer Interface

Formal Education:

- B.S. (1970) in Soil and Water Science, University of California, Davis.

Continuing Education:

- University of Southern California (USC) School of Business Administration, "Customer Service Management," April 1990.
- Hazardous Waste Operations and Emergency Response Training, OSHA 29 CFR 1910.120, 40 hr plus annual refresher.
- American Chemical Society (ACS), "Quality Assurance for Analytical Chemistry," Nov. 1991.
- University of California Davis (UCD), "Marketing Professional Services," Feb. 1988.
- University of California Davis (UCD), "Guerrilla Marketing," Feb. 1988.
- University of California Davis (UCD), "Enhancing Sales Skills," Feb. 1988.
- American Water Works Association, "Approved Water Sampling Procedures," March 1991.
- California Agricultural Leadership Program, 1976 - 1978.
- NPDES Requirements for Industrial and Construction Site Storm Water Discharges, ASCE, Feb. 1992.
- Senate bill #198, compliance training (State Fund Insurance)
- Nevada Nuclear Associates, "Fundamentals of Radiochemistry", February 1994.

Memberships:

Professional:

- American Chemical Society
- American Water Works Association
- Association of California Testing Laboratories

Laboratory Organization and Responsibilities

Key Personnel Qualification Summary - Santa Paula

Kelly Dunnahoo

Current Responsibilities:

Vice President

- To support the president in all operational, technical and strategic aspects relating to the corporation.

Inorganic, Organic and Air Toxics Lab Manager:

- Organization of work flow in the above departments
- Personnel training, methods development, instrument troubleshooting
- Response to specific customer enquiries

Work Experience:

- 10 years experience in environmental and geochemical analysis
- 6 years of supervisory and management roles in organic laboratory operations

Formal Education:

- B.S. (1987) in Biochemistry, University of California, Los Angeles

Continuing Education:

- AOAC, "QA for Analytical Labs", November 1991.

Laboratory Organization and Responsibilities

Key Personnel Qualification Summary - Santa Paula

Denis Barry

Current Responsibilities:

Marketing Director

- Responsible for marketing of FGL's services to city, county and state and federal agencies in addition to private companies
- Compilation and implementation of FGL's marketing plans
- Responsible for FGL's informational and promotional materials

Work Experience:

- 6 years experience in marketing analytical services
- Marketing consultancy experience focused on small to medium sized companies
- International programs targeted mainly at the European Economic Community for small U.S. companies

Formal Education:

- B. Comm (Bachelor of Commerce), University College, Dublin, Ireland

Continuing Education:

- Computer Appreciation - Moorpark College, 1989

Memberships:

- Vice President - Irish American Club of Ventura County

Laboratory Organization and Responsibilities

Key Personnel Qualification Summary - Santa Paula

Cheryl Long

Current Responsibilities:

Administrative Services Director

- **Management of Santa Paula Office**
- **Organize and prioritize work load**
- **Document Control**

Work Experience:

20 years' management experience environmental field

- **Supervision of office personnel, customer service, marketing, data input, invoicing, accounts receivable, bacteriologist, laboratory technician, sample receiving, and field sampling.**
- **Additional experience in analyzing animal feed rations/rumen digestions.**
- **Environmental laboratory experience to include agricultural and air testing**
- **Physical testing - construction and inspection laboratory - affidavits, Notary Public**

Formal Education:

- **Associates of Arts Degree, Porterville College, Porterville, California**

Continuing Education:

- **Bakersfield College - Business Education and Management classes**
- **Water Treatment Plant Operator I License**

Laboratory Organization and Responsibilities

Key Personnel Qualification Summary - Santa Paula

Kurt Wilkinson

Current Responsibilities:

Quality Assurance Director

- Design, implementation and maintenance of FGL's Quality Assurance Program

Work Experience:

- 10 years experience in environmental testing of drinking water, wastewater, hazardous waste and air analysis
- Additional experience in agricultural testing of soils, plant tissue and food products

Formal Education:

- B.S. (1987) in Biochemistry, California Polytechnic State University, San Luis Obispo

Continuing Education:

- American Chemical Society (ACS), "Environmental Analytical Chemistry, Water and Waste," Nov. 1991.
- American Chemical Society (ACS), "Gas Chromatography/Mass Spectrometry," April 1992.
- Halliburton NUS, "Solving the Mysteries, Collecting Environmental Samples," April 1992.

Memberships:

Professional:

- American Chemical Society (ACS)

Laboratory Organization and Responsibilities

Key Personnel Qualification Summary - Santa Paula

Roger Perry

Current Responsibilities:

Health and Safety Officer

- Design, implementation and maintenance of FGL's Health and Safety programs
- Organic Department Chemist

Experience:

- 14 years experience as an environmental analytical chemist
- Health and Safety regulations and compliance
- Handling accumulation and disposal of Hazardous Wastes and Radioactive Materials

Formal Education:

- B.A. (1982) in Chemistry, Sonoma State University, Sonoma

Continuing Education:

- Hazardous Waste Operations and Emergency Response Training, OSHA 29 CFR 1910.120, 40 hr plus annual refreshers.

Laboratory Organization and Responsibilities

Key Personnel Qualification Summary - Santa Paula

Michel M. Franco

Current Responsibilities:

Radiochemistry Lab Manager

- Work scheduling and staff supervision
- Oversee data analysis, data validation and recording
- Method and Standard Operating Procedure development and review for maximizing efficiency and turnaround time for the Radiochemistry Laboratory
- Personnel training and instrument troubleshooting
- Client interface and project management

Radiation Safety Officer

- Conduct personnel training and dosimetry program
- Maintenance of safety systems and spill cleanup kits
- Internal inspections of logs and storage areas
- Perform required leak tests of sealed sources
- Monitor radioactive material receiving, tracking, waste handling and holding areas

Work Experience:

- 8 years experience in radiochemical analysis, general inorganic analysis and organic analysis for TOX, TOC, HPLC and GC.
- Developed instrument analysis experiment for CSUN (1988)
- Sample trouble shooting, processing and department liason at Reference Laboratory(1986)

Formal Education:

- B.A. (1990) Chemistry, California State University, Northridge

Continuing Education:

- Nevada Nuclear Associates, "Fundamentals of Radiochemistry", February 1994.
- Canberra Industries Inc., "Environmental Radioactivity Quantification Workshop", March 1994.
- Health Physics Seminar June 1994.
- Aptec Inc., "Gamma Ray Spectroscopy Interactive Training", January 1995.

Laboratory Organization and Responsibilities

Key Personnel Qualification Summary - Santa Paula

Jason Heitschmidt

Current Responsibilities

Trace Metals Laboratory Supervisor

- Work scheduling and staff supervision
- Oversee data analysis, data validation and recording
- Method and Standard Operating Procedure development and review for maximizing efficiency and turnaround time for the Radiochemistry Laboratory
- Personnel training and instrument troubleshooting

Work Experience:

- 5 years experience in environmental testing of drinking water, waste water, hazardous waste

Formal Education:

- B. S. (1991) in Zoology, Texas Tech University, Lubbock

Laboratory Organization and Responsibilities

Key Personnel Qualification Summary - Santa Paula

Christine Wilkinson

Current Responsibilities

Wet Chemistry Laboratory Supervisor

- Work scheduling and staff supervision
- Oversee data analysis, data validation and recording
- Method and Standard Operating Procedure development and review for maximizing efficiency and turnaround time for the Radiochemistry Laboratory
- Personnel training and instrument troubleshooting

Work Experience:

- 6 years experience in environmental testing of drinking water, waste water, hazardous waste
- 3 years supervisory experience in inorganic laboratory operations

Formal Education:

- B. A. & S. (1988) in Biological Sciences and Anthropology, University of California, Davis

Laboratory Organization and Responsibilities

Key Personnel Qualification Summary - Santa Paula

Ricardo Sandoval

Current Responsibilities:

Agriculture Lab Manager

- Management of Agricultural Department
- Supervision and training of staff

Work Experience:

- 11 years experience in agricultural testing of soils and plant tissue
- Ranch and Nursery experience dealing with irrigation, fertilization and transplantation of avocado trees and horticultural plants

Formal Education:

- B.S. (1985) in Crop Science and Technical Degree in Fruit Science, California Polytechnic State University, San Luis Obispo.

Laboratory Organization and Responsibilities

Key Personnel Qualification Summary - Santa Paula

Eric Cetting

Current Responsibilities:

Computer Systems Manager

- Design, implementation and maintenance of FGL's Laboratory Information Management System (LIMS)
- Training of personnel in the effective use of LIMS

Work Experience:

- Developed customized LIMS system for FGL
- As research assistant with the University of Wisconsin, was involved in the modification of an existing theoretical computational program designed to model quantum mechanical properties of the Helium Atom

Formal Education:

- B.S. (1981) Chemistry, University of Alaska, Fairbanks
- B.S. (1981) Math, University of Alaska, Fairbanks
- B.S. (1981) Physics, University of Alaska, Fairbanks
- M.S. (1987) Physical Chemistry, University of Wisconsin, Madison

Continuing Education:

- Computer Networking Seminar: Santa Barbara, CA. January 1991
- Nevada Nuclear Associates, "Fundamentals of Radiochemistry", February 1994.

Laboratory Organization and Responsibilities

Key Personnel Qualification Summary - Stockton

Charles Johnson

Current Responsibilities:

Laboratory Director

- Management of the Stockton Laboratory
- Liason with Santa Paula (Corporate) on Stockton lab's performance, budgets and financial results
- To support the president in all operational, technical and strategic aspects relating to the corporation

Work Experience:

- One year general management with FGL at the Santa Paula laboratory
- One year as Research Assistant University of California, Davis - Designing and performing experiments, presentation of results.
- One year as Laboratory Assistant-sample preparation of food crops for pesticide residue analysis.

Formal Education:

- B.S. (1995) - Environmental Toxicology - University of California, Davis

Instrument Experience:

- GC, HPLC, GCMS, and Spectrophotometry

Continuing Education:

- Hazardous Waste Operations and Emergency Response Training, OSHA s9 CFR 1910.120, 40 hours

Laboratory Organization and Responsibilities

Key Personnel Qualification Summary - San Joaquin

Neil Jessup

Current Responsibilities:

- Agronomist/Field service - Visalia**
- Technical Representative - San Joaquin Valley**
- Coordinating sampling and sample pick up in the South San Joaquin Valley**
- Consultation with clients on sampling and analysis requirements**
- Proposal preparation for contracts on environmental and agricultural testing**

Work Experience:

- 12 years experience in areas of field service and sampling**
- Considerable background in city, county, state and federal regulations for environmental testing requirements**

Formal Education:

- B.S. (1977) in Agronomy, California Polytechnic State University, San Luis Obispo**

Continuing Education:

- OSHA 40 hour trained for hazardous waste and emergency response, confined space entry and SCBA**
- American Water Works Association, "Approved Water Sampling Procedures," March 1991.**
- Halliburton NUS, "Solving the Mysteries, Collecting Environmental Samples," April 1992.**

Memberships:

Professional:

- California Agriculture Production Consultants Association (CAPCA)**

Civic:

- Tulare County Hazardous Waste Advisory Committee**

Quality Assurance Objectives

The quality assurance objectives for accuracy, precision, and Detection Limits for Reporting (DLR) are listed in Tables 5-1 (Drinking Water Methods), 5-2 (Wastewater / Hazardous Waste Liquid Methods) and 5-3 (Solid Waste / Hazardous Waste Solids Methods).

Accuracy - is based on the recovery measurement of a target analyte after known addition to a given sample or representative sample matrix (see section 14.2). Accuracy values are expressed as the percent recovery of the known value, and serve as a reflection of the total measurement error (random and systematic). The acceptance ranges for recovery (%REC-AR) are used for data validation.

Precision - is based on the difference measurement of duplicate data points (see section 14.1). Precision values are expressed as relative percent difference (RPD) and serve as a reflection of the variability in measurement replication. Surrogates are not run in duplicate, therefore RPDs are not applicable. The Maximum Acceptance Value for the RPD's (RPD-MAV) are used for data validation.

Detection Limit for Reporting (DLR) - is the routine detection limit FGL uses for reporting purposes. Method Detection limit studies are performed annually or as specified in the method reference to ensure that the DLR's listed in this section are met. DLR's for surrogates are not listed as surrogates are required for quality control purposes only.

Completeness - FGL is currently introducing controls to document incomplete reports. These are reports that are known to lack information at the time of delivery or reports where we are notified by the client that information is not complete. Future QA manuals will have the results for data completeness documented.

TABLE 5-1 Quality Assurance Objectives for Drinking Water Methods

<u>CONSTITUENT</u>	<u>ACCURACY % REC-AR</u>	<u>PRECISION RPD-MAV</u>	<u>DLR ug/L</u>
EPA Method 501.2			
Bromodichloromethane	70-130	20	0.5
Bromoform	70-130	20	0.5
Chloroform	70-130	20	0.5
Dibromochloromethane	70-130	20	0.5
EPA Method 502.2			
Surrogates			
BFB	70-130	N/A	N/A
Fluorobenzene	70-130	N/A	N/A
Chlorofluorobenzene	70-130	N/A	N/A
Analytes			
Benzene	37-151	30	0.5
Bromobenzene	50-150	30	0.5
Bromochloromethane	50-150	30	0.5
Bromodichloromethane	35-155	30	0.5
Bromoform	45-169	30	0.5
Bromomethane	D-242	30	0.5
n-Butylbenzene	50-150	30	0.5
sec-Butylbenzene	50-150	30	0.5

Quality Assurance Objectives

TABLE 5-1 Quality Assurance Objectives for Drinking Water Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 502.2 continued			
tert-Butylbenzene	50-150	30	0.5
Carbon tetrachloride	70-140	30	0.5
Chlorobenzene	37-160	30	0.5
Chloroethane	14-320	30	0.5
Chloroform	51-128	30	0.5
Chloromethane	D-273	30	0.5
2-Chlorotoluene	50-150	30	0.5
4-Chlorotoluene	50-150	30	0.5
DBCP	50-150	30	0.5
Dibromochloromethane	53-149	30	0.5
1,2-Dibromoethane	50-150	30	0.5
Dibromomethane	50-150	30	0.5
1,2-Dichlorobenzene	50-150	30	0.5
1,3-Dichlorobenzene	50-150	30	0.5
1,4-Dichlorobenzene	50-150	30	0.5
Dichlorodifluoromethane	50-150	30	0.5
1,1-Dichloroethane	59-155	30	0.5
1,2-Dichloroethane	49-155	30	0.5
1,1-Dichloroethylene	D-234	30	0.5
cis-1,2-Dichloroethylene	50-150	30	0.5
trans-1,2-Dichloroethylene	54-156	30	0.5
1,2-Dichloropropane	D-210	30	0.5
1,3-Dichloropropane	50-150	30	0.5
2,2-Dichloropropane	50-150	30	0.5
1,1-Dichloropropene	50-150	30	0.5
cis-1,3-Dichloropropene	D-227	30	0.5
trans-1,3-Dichloropropene	17-183	30	0.5
Ethylbenzene	37-162	30	0.5
Hexachlorobutadiene	50-150	30	0.5
Isopropylbenzene	50-150	30	0.5
p-Isopropyltoluene	50-150	30	0.5
Methylene Chloride	D-221	30	0.5
Naphthalene	50-150	30	0.5
n-Propylbenzene	50-150	30	0.5
Styrene	50-150	30	0.5
1,1,1,2-Tetrachloroethane	50-150	30	0.5
1,1,2,2-Tetrachloroethane	46-157	30	0.5
Tetrachloroethylene	64-148	30	0.5
Toluene	47-163	30	0.5
1,2,3-Trichlorobenzene	50-150	30	0.5
1,2,4-Trichlorobenzene	50-150	30	0.5
1,1,1-Trichloroethane	52-150	30	0.5
1,1,2-Trichloroethane	71-157	30	0.5
Trichloroethylene	71-157	30	0.5
Trichlorofluoromethane	17-181	30	0.5

Quality Assurance Objectives

TABLE 5-1 Quality Assurance Objectives for Drinking Water Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 502.2 continued			
1,2,3-Trichloropropane	50-150	30	0.5
1,1,2-Trichlorotrifluoroeth	50-150	30	0.5
1,2,4-Trimethylbenzene	52-150	30	0.5
1,3,5-Trimethylbenzene	50-150	30	0.5
Vinyl Chloride	D-251	30	0.5
Xylenes m,p	50-150	30	0.5
Xylenes o	50-150	30	0.5
Method EPA 504			
DBCP	70-130	30	0.02
EDB	70-130	30	0.01
Method EPA 505			
Alachlor	50-150	30	0.2
Aldrin	42-122	30	0.01
Chlordane	45-119	30	0.1
Dieldrin	36-146	30	0.01
Endrin	30-147	30	0.01
Heptachlor	34-111	30	0.01
Heptachlor Epoxide	37-142	30	0.01
Hexachlorobenzene	50-150	30	0.01
Lindane	32-127	30	0.05
Methoxychlor	50-150	30	0.1
Toxaphene	41-126	30	0.5
PCB 1016	50-114	30	0.3
PCB 1221	15-178	30	0.3
PCB 1232	10-215	30	0.3
PCB 1242	39-150	30	0.3
PCB 1248	38-158	30	0.3
PCB 1254	29-131	30	0.3
PCB 1260	8-127	30	0.3
Method EPA 507			
Surrogates			
1,3-Dimethyl-2-nitrobenzene	53-105	N/A	N/A
9-Nitroanthracene	50-134	N/A	N/A
Analytes			
Alachlor	70-130	30	1
Atrazine	70-130	30	1
Bromocil	70-130	30	5
Butachlor	70-130	30	1
Diazinon	70-130	30	2
Dimethoate	70-130	30	2
Metolachlor	70-130	30	1
Metribuzin	70-130	30	0.1

Quality Assurance Objectives

TABLE 5-1 Quality Assurance Objectives for Drinking Water Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 507 continued			
Molinate	70-130	30	2
Prometryne	70-130	30	2
Propachlor	70-130	30	1
Simazine	70-130	30	1
Thiobencarb	70-130	30	1
Method EPA 508			
Surrogate			
Hexachlorobenzene	70-130	N/A	N/A
Analytes			
Chlorothalonil	70-130	30	0.2
PCB 1016	50-114	30	0.08
PCB 1221	15-178	30	0.2
PCB 1232	10-215	30	0.2
PCB 1242	39-150	30	0.2
PCB 1248	38-158	30	0.1
PCB 1254	29-131	30	0.1
PCB 1260	8-127	30	0.2
Method EPA 508A			
PCB's as Decachlorobiphenyl	70-130	30	0.2
Method EPA 510			
Bromodichloromethane	70-130	30	0.5
Bromoform	70-130	30	0.5
Chloroform	70-130	30	0.5
Dibromochloromethane	70-130	30	0.5
Method EPA 515.1			
Surrogate			
2,4-DCAA	30-150	N/A	N/A
Analytes			
Bentazon	30-150	30	2
Chloramben	30-150	30	1
2,4-D	30-150	30	2
2,4-DB	30-150	30	2
Dalapon	30-150	30	2
Dicamba	30-150	30	5
Dichloroprop	30-150	30	2
Dinoseb	30-150	30	1
Pentachlorophenol	30-150	30	0.2
Picloram	30-150	30	1
2,4,5-T	30-150	30	1
2,4,5-TP (Silvex)	30-150	30	1

Quality Assurance Objectives

TABLE 5-1 Quality Assurance Objectives for Drinking Water Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 524.2			
Surrogates			
1,2-Dichloroethane-d4	76-114	N/A	N/A
Toluene-d8	88-110	N/A	N/A
BFB	86-115	N/A	N/A
Analytes			
Acetone	50-150	30	0.5
Benzene	37-151	30	0.5
Bromobenzene	50-150	30	0.5
Bromochloromethane	50-150	30	0.5
Bromodichloromethane	35-155	30	0.5
Bromoform	45-169	30	0.5
Bromomethane	D-242	30	0.5
2-Butanone (MEK)	50-150	30	0.5
n-Butylbenzene	50-150	30	0.5
sec-Butylbenzene	50-150	30	0.5
tert-Butylbenzene	50-150	30	0.5
Carbon disulfide	50-150	30	0.5
Carbon tetrachloride	70-140	30	0.5
Chlorobenzene	37-160	30	0.5
Chloroethane	14-230	30	0.5
Chloroform	51-138	30	0.5
Chloromethane	D-273	30	0.5
2-Chlorotoluene	50-150	30	0.5
4-Chlorotoluene	50-150	30	0.5
Dibromochloromethane	53-149	30	0.5
1,2-Dibromoethane (EDB)	50-150	30	0.5
Dibromomethane	50-150	30	0.5
1,2-Dibromo-3-chloropropane	50-150	30	0.5
1,2-Dichlorobenzene	50-150	30	0.5
1,3-Dichlorobenzene	50-150	30	0.5
1,4-Dichlorobenzene	50-150	30	0.5
Dichlorodifluoromethane	50-150	30	0.5
1,1-Dichloroethane	59-155	30	0.5
1,2-Dichloroethane	49-155	30	0.5
1,1-Dichloroethylene	D-234	30	0.5
cis-1,2-Dichloroethylene	50-150	30	0.5
trans-1,2-Dichloroethylene	54-156	30	0.5
1,2-Dichloropropane	D-210	30	0.5
1,3-Dichloropropane	50-150	30	0.5
2,2-Dichloropropane	50-150	30	0.5
1,1-Dichloropropene	50-150	30	0.5
cis-1,3-Dichloropropene	D-227	30	0.5
trans-1,3-Dichloropropene	17-183	30	0.5
Ethylbenzene	37-162	30	0.5
Hexachlorobutadiene	50-150	30	0.5

Quality Assurance Objectives

TABLE 5-1 Quality Assurance Objectives for Drinking Water Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 524.2 continued			
2-Hexanone	50-150	30	0.5
Isopropylbenzene	50-150	30	0.5
p-Isopropyltoluene	50-150	30	0.5
Methylene chloride	D-221	30	0.5
4-Methyl-2-pentanone (MIBK)	50-150	30	0.5
Naphthalene	50-150	30	0.5
n-Propylbenzene	50-150	30	0.5
Styrene	50-150	30	0.5
1,1,1,2-Tetrachloroethane	50-150	30	0.5
1,1,2,2-Tetrachloroethane	46-157	30	0.5
Tetrachloroethylene	64-148	30	0.5
Toluene	47-163	30	0.5
1,2,3-Trichlorobenzene	50-150	30	0.5
1,2,4-Trichlorobenzene	50-150	30	0.5
1,1,1-Trichloroethane	52-162	30	0.5
1,1,2-Trichloroethane	52-150	30	0.5
Trichloroethylene	71-157	30	0.5
Trichlorofluoromethane	17-181	30	0.5
1,2,3-Trichloropropane	50-150	30	0.5
1,1,2-Trichlorotrifluoroeth	50-150	30	0.5
1,2,4-Trimethylbenzene	50-150	30	0.5
Vinyl acetate	50-150	30	0.5
Vinyl chloride	D-251	30	0.5
Xylenes m,p	50-150	30	0.5
Xylenes o	50-150	30	0.5
Method EPA 525			
Surrogate			
Perylene-d12	50-150	N/A	N/A
Analytes			
Acenaphthylene	50-150	30	1
Anthracene	50-150	30	1
Benzo(a)anthracene	50-150	30	1
Benzo(b)fluoranthene	50-150	30	1
Benzo(k)fluoranthene	50-150	30	1
Benzo(g,h,i)perylene	50-150	30	1
Benzo(a)pyrene	50-150	30	0.1
Butylbenzylphthalate	50-150	30	1
Chrysene	50-150	30	1
Dibenzo(a,h)anthracene	50-150	30	1
Dimethylphthalate	50-150	30	1
Diethylphthalate	50-150	30	1
Di-n-butylphthalate	50-150	30	1
bis(2-Ethylhexyl)adipate	50-150	30	1
bis(2-Ethylhexyl)phthalate	29-137	30	3

Quality Assurance Objectives

TABLE 5-1 Quality Assurance Objectives for Drinking Water Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 525 continued			
Fluorene	50-150	30	1
Hexachlorobenzene	50-150	30	1
Hexachlorocyclopentadiene	50-150	30	1
Indeno(1,2,3-c,d)pyrene	50-150	30	1
Pentachlorophenol	50-150	30	4
Phenanthrene	50-150	30	1
Pyrene	50-150	30	1
Method EPA 531.1			
Surrogate			
BDMC	70-130	N/A	N/A
Analytes			
Aldicarb	70-130	30	3
Aldicarb Sulfone	70-130	30	3
Aldicarb Sulfoxide	70-130	30	3
Carbofuran	70-130	30	5
Carbaryl	70-130	30	5
3-Hydroxycarbofuran	70-130	30	10
Methiocarb	70-130	30	10
Methomyl	70-130	30	5
1-Napthol	70-130	30	5
Oxymal	70-130	30	5
Propoxur	70-130	30	5
Method EPA 547			
Glyphosate	70-130	20	20
Method EPA 548			
Endothall	70-130	20	40
Method EPA 549			
Diquat	70-130	20	2
Paraquat	70-130	20	1
Method EPA 550.1			
Acenaphthene	70-130	20	3
Acenaphthylene	70-130	20	2
Anthracene	70-130	20	0.1
Benzo(a)anthracene	70-130	20	0.1
Benzo(a)pyrene	70-130	20	0.1
Benzo(b)fluoranthene	70-130	20	0.2
Benzo(g,h,i)perylene	70-130	20	0.1
Benzo(k)fluoranthene	70-130	20	0.1
Chrysene	70-130	20	0.1
Dibenzo(a,h)anthracene	70-130	20	0.3

Quality Assurance Objectives

TABLE 5-1 Quality Assurance Objectives for Drinking Water Methods

<u>CONSTITUENT</u>		<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 550.1 continued				
Fluoranthene		70-130	20	2
Fluorene		70-130	20	2
Indeno(1,2,3-c,d)pyrene		70-130	20	0.1
1-Methylnaphthalene		70-130	20	2
2-Methylnaphthalene		70-130	20	2
Naphthalene		70-130	20	2
Phenanthrene		70-130	20	2
Pyrene		70-130	20	0.1
Method EPA 552				
Bromochloroacetic acid		70-130	20	1
Dibromoacetic acid		70-130	20	1
Dichloroacetic acid		70-130	20	1
2,4-Dichlorophenol		70-130	20	1
Monobromoacetic acid		70-130	20	1
Monochloroacetic acid		70-130	20	1
Trichloroacetic acid		70-130	20	1
2,4,6-Trichlorophenol		70-130	20	1
<u>CONSTITUENT</u>	<u>Method</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>mg/L</u>
Inorganic Chemicals				
Acidity	305.1	N/A	20	1
Alkalinity (as CaCO ₃)	310.0	N/A	20	1
Bicarbonate	310.1	N/A	20	1
BOD	405.1	80-120	20	2
Bromide	300.0	80-120	20	0.5
Carbon Dioxide	SM4500C	N/A	20	1
Carbonate	310.1	N/A	20	1
COD	410.4	75-125	20	4
Chloride	300.0	80-120	20	1
Chlorine Residual	330.2	N/A	20	0.1
Chlorine Residual	330.5	N/A	20	0.1
Color	110.3	N/A	20	3 units
Electrical Conductivity	120.1	80-120	20	1 umhos
Cyanide, Total	335.2	75-125	20	0.01
Fluoride by electrode	340.2	80-120	20	0.1
Hydroxide	310.0	N/A	20	1
MBAS	425.1	70-130	20	0.05
Nitrogen				
Ammonia	350.1	80-120	20	1
Nitrate	300.0	80-120	20	0.1
Nitrite	300.0	80-120	20	0.1

Quality Assurance Objectives

TABLE 5-1 Quality Assurance Objectives for Drinking Water Methods

<u>CONSTITUENT</u>	<u>Method</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>mg/L</u>
Inorganic Chemical EPA Methods continued				
Nitrate	353.2	80-120	20	0.1
Nitrite	353.2	80-120	20	0.1
Total Kjeldahl	351.2	80-120	20	1
Odor	140.1	N/A	20	1 TON
Oil and Grease	413.1	N/A	20	3
Oxygen, dissolved	360.1	N/A	20	0.5
pH	150.1	N/A	20	N/A
Phenols	420.1	75-125	20	0.1
Phosphorous				
Phosphate	300.0	80-120	20	0.1
Total	365.2	75-125	20	0.1
Solids/Residue				
Filterable (TDS)	160.1	NA	20	40
Non-filterable (TSS)	160.2	NA	20	10
Total	160.3	NA	20	40
Volatile	160.4	NA	20	40
Settleable	160.5	NA	20	0.1 ml/L
Sulfate	300.0	80-120	20	1
Sulfide				
Total	376.2	N/A	20	0.1
Dissolved	376.2	N/A	20	0.1 Sulfite
	377.1	N/A	20	0.1
Tannin & Lignin	SM5500B	N/A	20	1
Titration - pH adjust.	N/A	N/A	20	1
Turbidity	180.1	N/A	20	0.2 NTU
<u>CONSTITUENT</u>	<u>Method</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Trace Metals				
Aluminum	200.9	75-125	20	20
Aluminum	200.8	75-125	20	20
Calcium	200.7	80-120	20	1 mg/L
Chromium	200.9	75-125	20	5
Chromium	200.8	75-125	20	2
Chromium VI	7196	D-120	20	10
Cobalt	200.7	80-120	20	50
Cobalt	200.8	75-125	20	0.5
Copper	200.7	80-120	20	50
Copper	200.8	75-125	20	2
Iron	200.7	80-120	20	50
Lead	200.9	75-125	20	5
Lead	200.8	75-125	20	0.5
Lithium	SM3500L	80-120	20	10

Quality Assurance Objectives

TABLE 5-1 Quality Assurance Objectives for Drinking Water Methods

<u>CONSTITUENT</u>	<u>Method</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Trace Metals continued				
Magnesium	200.7	80-120	20	1 mg/L
Manganese	200.7	80-120	20	30
Manganese	200.8	75-125	20	1
Mercury	245.1	75-125	20	0.2
Mercury	245.2	75-125	20	0.2
Molybdenum	200.7	80-120	20	50
Molybdenum	200.8	75-125	20	0.5
Nickel	200.7	80-120	20	50
Nickel	200.8	75-125	20	1
Potassium	200.7	80-120	20	1 mg/L
Selenium	200.9	75-125	20	2
Selenium	200.8	75-125	20	2
Silica	200.7	80-120	20	1 mg/L
Silver	200.9	75-125	20	0.5
Silver	200.8	75-125	20	0.5
Sodium	200.7	80-120	20	1 mg/L
Strontium	200.7	80-120	20	50
Thallium	200.9	75-125	20	2
Thallium	200.8	75-125	20	0.5
Tin	200.9	75-125	20	50
Uranium	200.7	80-120	20	100
Vanadium	200.7	80-120	20	20
Zinc	200.7	80-120	20	50
Zinc	200.8	75-125	20	5

<u>CONSTITUENT</u>	<u>Method</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>MDA</u> <u>pCi/L</u>
Radiochemistry				
Gamma Emitters	901.1	80-120	20	1
Gross Alpha	900.0	60-140	30	1
Gross Beta	900.0	0-140	30	1
Radon	913.0	N/A	20	10
Strontium 90	905.0	60-140	30	1
Total Radium	900.1	75-125	20	1
Radium 226	903.1	75-125	20	1
Radium 228	904.0	75-125	20	1
Tritium	906.0	75-125	20	300
Uranium	908.0	75-125	20	1

Quality Assurance Objectives

TABLE 5-2 Quality Assurance Objectives for Wastewater / Hazardous Waste Liquid Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 601/8010			
Surrogates			
BFB	50-150	N/A	N/A
Fluorobenzene	50-150	N/A	N/A
Chlorofluorobenzene	50-150	N/A	N/A
Analytes			
Bromodichloromethane	42-172	20	0.5
Bromoform	13-159	20	0.5
Bromomethane	D-144	20	0.5
Carbon tetrachloride	43-143	20	0.5
Chlorobenzene	38-150	20	0.5
Chloroethane	46-137	20	0.5
Chloroform	49-133	20	0.5
Chloromethane	D-193	20	0.5
Dibromochloromethane	24-191	20	0.5
1,2-Dichlorobenzene	D-208	20	0.5
1,3-Dichlorobenzene	7-187	20	0.5
1,4-Dichlorobenzene	42-143	20	0.5
Dichlorodifluoromethane	50-150	20	0.5
1,1-Dichloroethane	47-132	20	0.5
1,2-Dichloroethane	51-147	20	0.5
1,1-Dichloroethylene	28-167	20	0.5
trans-1,2-Dichloroethylene	38-155	20	0.5
1,2-Dichloropropane	44-156	20	0.5
cis-1,3-Dichloropropene	22-178	20	0.5
trans-1,3-Dichloropropene	22-178	20	0.5
Methylene chloride	25-162	20	0.5
1,1,2,2-Tetrachloroethane	50-150	20	0.5
Tetrachloroethylene	26-162	20	0.5
1,1,1-Trichloroethane	41-138	20	0.5
1,1,2-Trichloroethane	39-139	20	0.5
Trichloroethylene	81-119	20	0.5
Trichlorofluoromethane	21-156	20	0.5
Vinyl chloride	28-163	20	0.5
Method EPA 8015M TPH (purgeable)			
Gas	50-150	40.0	500
Method EPA 8015M TPH (extractable)			
Crude oil	50-150	40.0	500
Diesel fuel	50-150	40.0	500
Hydraulic oil	50-150	40.0	500
Jet fuel	50-150	40.0	500
Stoddard solvent	50-150	40.0	500
Waste oil	50-150	40.0	2000

Quality Assurance Objectives

TABLE 5-2 Quality Assurance Objectives for Wastewater / Hazardous Waste Liquid Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 602/8020			
Surrogates			
BFB	50-150	N/A	N/A
Analytes			
Benzene	78-133	20	0.3
Chlorobenzene	73-132	20	0.3
1,2-Dichlorobenzene	64-143	20	0.3
1,3-Dichlorobenzene	61-150	20	0.3
1,4-Dichlorobenzene	61-151	20	0.3
Ethylbenzene	75-129	20	0.3
Toluene	61-164	20	0.3
Xylene, o	69-137	20	0.3
Xylene, p	71-135	20	0.3
Xylene, m	68-133	20	0.3
Method EPA 604/8040 (analyzed by method 625/8270)			
2-Chlorophenol	23-134	30	10
2,4-Dichlorophenol	39-135	30	10
2,4-Dimethylphenol	42-109	30	10
4,6-Dinitro-o-cresol	D-181	30	50
2,4-Dinitrophenol	D-191	30	50
2-Methylphenol	50-150	30	10
4-Methylphenol	50-150	30	10
2-Nitrophenol	29-182	30	10
4-Nitrophenol	29-182	30	50
p-Chloro-m-cresol	22-147	30	20
Pentachlorophenol	14-176	30	50
Phenol	5-112	30	10
2,4,5-Trichlorophenol	37-144	30	10
2,4,6-Trichlorophenol	37-144	30	10
Method EPA 608/8080			
Surrogates			
Hexachlorobenzene	26-116	N/A	N/A
Dibutylchloroendate	44-125	N/A	N/A
Analytes			
Aldrin	20-123	30	0.2
Alpha BHC	37-134	30	0.2
Beta BHC	17-147	30	0.2
Delta BHC	19-140	30	0.2
Chlordane	45-119	30	0.2
o,p - DDD	31-141	30	0.2
p,p - DDD	31-141	30	0.2
o,p - DDE	30-145	30	0.2
p,p - DDE	30-145	30	0.2
o,p - DDT	25-160	30	0.2

Quality Assurance Objectives

TABLE 5-2 Quality Assurance Objectives for Wastewater / Hazardous Waste Liquid Methods

<u>CONSTITUENT</u>	<u>ACCURACY % REC-AR</u>	<u>PRECISION RPD-MAV</u>	<u>DLR ug/L</u>
Method EPA 608/8080 continued			
p,p - DDT	70-160	30	0.2
Dieldrin	47-126	30	0.2
Endosulfan I	45-153	30	0.2
Endosulfan II	D-202	30	0.2
Endosulfan sulfate	26-144	30	0.2
Endrin	30-147	30	0.2
Endrin aldehyde	50-150	30	0.2
Heptachlor	25-133	30	0.2
Heptachlor epoxide	37-142	30	0.2
Lindane	81-119	30	0.2
Methoxychlor	50-150	30	0.5
Toxaphene	41-126	30	5
PCB 1016	50-114	30	2
PCB 1221	15-178	30	2
PCB 1232	10-215	30	2
PCB 1242	39-150	30	2
PCB 1248	38-158	30	2
PCB 1254	29-131	30	2
PCB 1260	8-127	30	2
Method EPA 610/8310			
Acenaphthene	70-130	20	3
Acenaphthylene	70-130	20	2
Anthracene	70-130	20	0.1
Benzo(a)anthracene	70-130	20	0.1
Benzo(b)fluoranthene	70-130	20	0.2
Benzo(k)fluoranthene	70-130	20	0.1
Benzo(g,h,i)perylene	70-130	20	0.1
Benzo(a)pyrene	70-130	20	0.2
Chrysene	70-130	20	0.1
Dibenzo(a,h)anthracene	70-130	20	0.3
Fluoranthene	70-130	20	2
Fluorene	70-130	20	2
Indeno(1,2,3-c,d)pyrene	70-130	20	0.1
Naphthalene	70-130	20	2
Phenanthrene	70-130	20	2
Pyrene	70-130	20	0.1
Method EPA 614/8140			
Surrogates			
1,3-Dimethyl-2-nitrobenzene	50-150	N/A	N/A
9-Nitroanthracene	50-150	N/A	N/A
Analytes			
Azinphos methyl	50-150	30	2
Bolstar	50-150	30	2

Quality Assurance Objectives

TABLE 5-2 Quality Assurance Objectives for Wastewater / Hazardous Waste Liquid Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 614/8140 continued			
Chlorpyrifos	50-150	30	2
Coumaphos	50-150	30	2
Demeton-o,s	50-150	30	2
Diazinon	50-150	30	2
Dichlorvos	50-150	30	2
Disulfoton	50-150	30	2
Ethion	50-150	30	2
Ethoprop	50-150	30	2
Fensulfoton	50-150	30	2
Fenthion	50-150	30	2
Malathion	50-150	30	2
Merphos	50-150	30	2
Mevinphos	50-150	30	2
Naled	50-150	30	2
Parathion, ethyl	50-150	30	2
Parathion, methyl	50-150	30	2
Phorate	50-150	30	2
Ronnel	50-150	30	2
Stirophos	50-150	30	2
Tokuthion	50-150	30	2
Trichlornate	50-150	30	2
Method EPA 615/8150			
Surrogate			
2,4-DCAA	30-150	N/A	N/A
Analytes			
Bentazon	30-150	30	20
Chloramben	30-150	30	10
2,4-D	30-150	30	100
Dalapon	30-150	30	10
2,4-DB	30-150	30	100
Dicamba	30-150	30	10
Dichlorprop	30-150	30	20
Dinoseb	30-150	30	10
Pentachlorophenol	30-150	30	10
Picloram	30-150	30	10
2,4,5-T	30-150	30	10
2,4,5-TP (Silvex)	30-150	30	10
Method EPA 624/8240			
Surrogates			
1,2-Dichloroethane-d4	76-114	30	N/A
Toluene-d8	88-110	30	N/A
BFB	86-115	30	N/A

Quality Assurance Objectives

TABLE 5-2 Quality Assurance Objectives for Wastewater / Hazardous Waste Liquid Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 624/8240 continued			
Analytes			
Acetone	50-150	30	10
Acrolein	50-150	30	100
Acrylonitrile	50-150	30	100
Benzene	37-151	30	0.5
Bromodichloromethane	35-155	30	1
Bromoform	45-169	30	1
Bromomethane	D-242	30	1
Carbon disulfide	50-150	30	5
Carbon tetrachloride	70-140	30	0.5
Chlorobenzene	37-160	30	0.5
Chloroethane	14-230	30	1
2-Chloroethylvinyl ether	50-150	30	10
Chloroform	51-138	30	0.5
Chloromethane	D-273	30	1
Dibromochloromethane	53-149	30	1
1,2-Dichlorobenzene	50-150	30	1
1,3-Dichlorobenzene	50-150	30	1
1,4-Dichlorobenzene	50-150	30	1
Dichlorodifluoromethane	50-150	30	0.5
1,1-Dichloroethane	59-155	30	1
1,2-Dichloroethane	49-155	30	1
1,1-Dichloroethylene	D-234	30	1
trans-1,2-Dichloroethylene	54-156	30	1
1,2-Dichloropropane	D-210	30	1
cis-1,3-Dichloropropene	D-227	30	2
trans-1,3-Dichloropropene	17-183	30	1
Ethanol	50-150	30	5000.
Ethylbenzene	37-162	30	0.5
2-Hexanone	50-150	30	5
Methylene chloride	D-221	30	0.5
2-Butanone (MEK)	50-150	30	10
4-Methyl-2-pentanone (MIBK)	50-150	30	5
Styrene	50-150	30	1
1,1,2,2-Tetrachloroethane	46-157	30	1
Tetrachloroethylene	64-148	30	1
Toluene	47-163	30	0.5
1,1,1-Trichloroethane	52-162	30	0.5
1,1,2-Trichloroethane	52-150	30	0.5
Trichloroethylene	71-157	30	1
Trichlorofluoromethane	17-181	30	1.5
Vinyl acetate	50-150	30	100
Vinyl chloride	D-251	30	0.5
Xylenes	50-150	30	1

Quality Assurance Objectives

TABLE 5-2 Quality Assurance Objectives for Wastewater / Hazardous Waste Liquid Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 625/8270			
Surrogates			
2-Fluorobiphenyl	43-106	30	N/A
Nitrobenzene-d5	39-98	30	N/A
p-Terphenyl-d14	62-114	30	N/A
2-Fluorophenol	21-100	30	N/A
Phenol-d6	10-94	30	N/A
2,4,6-Tribromophenol	11-100	30	N/A
Analytes			
Acenaphthene	36-130	30	10
Acenaphthylene	33-145	30	10
Aniline	50-150	30	50
Anthracene	27-133	30	10
Benzo(a)anthracene	33-143	30	10
Benzo(a)pyrene	17-163	30	10
Benzo(b)fluoranthene	24-159	30	10
Benzo(k)fluoranthene	11-162	30	10
Benzo(g,h,i)perylene	D-219	30	10
Benzylalcohol	50-150	30	20
bis(2-Chloroethoxy)methane	33-184	30	10
bis(2-Chloroethyl)ether	12-158	30	10
bis(2-Chloroisopropyl)ether	36-166	30	10
bis(2-Ethylhexyl)phthalate	29-137	30	10
4-Bromophenylphenylether	65-114	30	10
Butylbenzylphthalate	D-152	30	10
Chloroaniline	50-150	30	10
Chloronaphthalene	60-180	30	10
Chlorophenylphenylether	25-158	30	10
Chrysene	17-168	30	10
Dibenzo(a,h)anthracene	D-227	30	10
Dibenzofuran	50-150	30	10
1,2-Dichlorobenzene	32-129	30	10
1,3-Dichlorobenzene	D-172	30	10
1,4-Dichlorobenzene	33-114	30	10
3,3'-Dichlorobenzidine	8-213	30	20
Diethylphthalate	D-114	30	10
Dimethylphthalate	D-112	30	10
Di-n-butylphthalate	1-118	30	10
2,4-Dinitrotoluene	37-111	30	10
2,6-Dinitrotoluene	50-158	30	10
Di-n-octylphthalate	4-146	30	10
Fluoranthene	26-137	30	10
Fluorene	59-121	30	10
Hexachlorobenzene	50-150	30	10
Hexachlorobutadiene	24-116	30	10
Hexachlorocyclopentadiene	50-150	30	10

Quality Assurance Objectives

TABLE 5-2 Quality Assurance Objectives for Wastewater / Hazardous Waste Liquid Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 625/8270 continued			
Hexachloroethane	40-113	30	10
Indeno(1,2,3-c,d)pyrene	50-150	30	10
Isophorone	21-196	30	10
2-Methylnaphthalene	50-150	30	10
Naphthalene	21-133	30	10
Nitrobenzene	35-180	30	10
N-Nitrosodimethylamine	50-150	30	10
N-Nitrosodi-N-propylamine	D-112	30	10
N-Nitrosodiphenylamine	50-150	30	10
2-Nitroaniline	50-150	30	50
3-Nitroaniline	50-150	30	50
4-Nitroaniline	50-150	30	50
Phenanthrene	54-120	30	10
Pyrene	73-119	30	10
1,2,4-Trichlorobenzene	35-122	30	10
2-Chlorophenol	27-143	30	10
2,4-Dichlorophenol	39-135	30	10
2,4-Dimethylphenol	42-109	30	10
4,6-Dinitro-o-cresol	D-181	30	50
2,4-Dinitrophenol	D-191	30	50
2-Methylphenol	50-150	30	10
4-Methylphenol	50-150	30	10
2-Nitrophenol	29-182	30	10
4-Nitrophenol	D-53	50	50
p-Chloro-m-cresol	22-147	30	20
Pentachlorophenol	D-112	30	50
Phenol	D-82	30	10
2,4,5-Trichlorophenol	50-150	30	10
2,4,6-Trichlorophenol	37-144	30	10
Method EPA 632			
Barban	30-150	30	0.5
Carbaryl	30-150	30	0.2
Carbofuran	30-150	30	30
Chlorpropham	30-150	30	0.3
Diuron	30-150	30	0.1
Fluometuron	30-150	30	100
Linoron	30-150	30	0.1
Methiocarb	30-150	30	0.2
Methomyl	30-150	30	100
Monuron	30-150	30	0.1
Neburon	30-150	30	0.1
Oxamyl	30-150	30	100
Propham	30-150	30	0.7
Propoxur	30-150	30	1

Quality Assurance Objectives

TABLE 5-2 Quality Assurance Objectives for Wastewater / Hazardous Waste Liquid Methods

<u>CONSTITUENT</u>		<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/L</u>
Method EPA 415.1/9060				
TOC		80-120	20	0.5 mg/L
Method EPA 9020				
TOX		80-120	20	0.5
Method EPA 418.1				
TRPH-By IR		50-150	20	0.5 mg/L
<u>CONSTITUENT</u>	<u>Method</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>mg/L</u>
Inorganic Chemicals				
Acidity	305.1	N/A	20	1
Alkalinity (as CaCO ₃)	310.0	N/A	20	1
Bicarbonate	310.1	N/A	20	1
BOD	405.1	80-120	20	2
Bromide	300.0	80-120	20	0.5
Carbon Dioxide	SM4500C	N/A	20	1
Carbonate	310.1	N/A	20	1
COD	410.4	75-125	20	4
Chloride	300.0	80-120	20	1
Chlorine Residual	330.2	N/A	20	0.1
Chlorine Residual	330.5	N/A	20	0.1
Color	110.3	N/A	20	3 units
Electrical Conductivity	120.1	80-120	20	1 umhos
Cyanide, Total	335.2	75-125	20	0.01
Fluoride by electrode	340.2	80-120	20	0.1
Hydroxide	310.0	N/A	20	1
MBAS	425.1	70-130	20	0.05
Nitrogen				
Ammonia	350.1	80-120	20	1
Nitrate	300.0	80-120	20	0.1
Nitrite	300.0	80-120	20	0.1
Nitrate	353.2	80-120	20	0.1
Nitrite	353.2	80-120	20	0.1
Total Kjeldahl	351.2	80-120	20	1
Odor	140.1	N/A	20	1 TON
Oil and Grease	413.1	N/A	20	3
Oxygen, dissolved	360.1	N/A	20	0.5
pH	150.1	N/A	20	N/A
Phenols	420.1	75-125	20	0.1
Phosphorous				
phosphate	300.0	80-120	20	0.1
Total	365.2	75-125	20	0.1

Quality Assurance Objectives

TABLE 5-2 Quality Assurance Objectives for Wastewater / Hazardous Waste Liquid Methods

<u>CONSTITUENT</u>	<u>Method</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>mg/L</u>
Inorganic Chemicals continued				
Solids/Residue				
Filterable (TDS)	160.1	NA	20	40
Non-filterable (TSS)	160.2	NA	20	10
Total	160.3	NA	20	40
Volatile	160.4	NA	20	40
Settleable	160.5	NA	20	0.1 ml/L
Sulfate	300.0	80-120	20	1
Sulfide				
Total	376.2	N/A	20	0.1
Dissolved	376.2	N/A	20	0.1
Sulfite	377.1	N/A	20	0.1
Tannin & Lignin	SM5500B	N/A	20	1
Titration - pH adjust.	N/A	N/A	20	1
Turbidity	180.1	N/A	20	0.2 NTU
Trace Metals				
Aluminum	200.9	75-125	20	0.02
Aluminum	200.8	75-125	20	0.1
Antimony	200.9	75-125	20	0.02
Antimony	200.8	75-125	20	0.005
Arsenic	200.9	75-125	20	0.005
Arsenic	200.8	75-125	20	0.02
Barium	200.7	80-120	20	0.02
Barium	200.8	75-125	20	0.005
Beryllium	200.7	80-120	20	0.01
Beryllium	200.8	75-125	20	0.005
Boron	200.7	80-120	20	0.1
Boron	200.8	75-125	20	0.1
Cadmium	200.9	75-125	20	0.005
Cadmium	200.8	75-125	20	0.005
Calcium	200.7	80-120	20	1
Chromium	200.9	75-125	20	0.01
Chromium	200.8	75-125	20	0.02
Chromium VI	7196	D-120	20	0.01
Cobalt	200.7	80-120	20	0.05
Cobalt	200.8	75-125	20	0.005
Copper	200.7	80-120	20	0.05
Copper	200.8	75-125	20	0.02
Iron	200.7	80-120	20	0.05
Gold	231.1	75-125	20	0.05
Lead	200.9	75-125	20	0.01
Lead	200.8	75-125	20	0.005
Organic Lead	LUFT	50-150	20	0.05
Lithium	SM3500L	80-120	20	0.05
Magnesium	200.7	80-120	20	1

Quality Assurance Objectives

TABLE 5-2 Quality Assurance Objectives for Wastewater / Hazardous Waste Liquid Methods

<u>CONSTITUENT</u>	<u>Method</u>	<u>ACCURACY % REC-AR</u>	<u>PRECISION RPD-MAV</u>	<u>DLR mg/L</u>
Trace Metals continued				
Manganese	200.7	80-120	20	0.03
Manganese	200.8	75-125	20	0.01
Mercury	245.1	75-125	20	0.0002
Mercury	245.2	75-125	20	0.0002
Molybdenum	200.7	80-120	20	0.05
Molybdenum	200.8	75-125	20	0.005
Nickel	200.7	80-120	20	0.05
Nickel	200.8	75-125	20	0.01
Potassium	200.7	80-120	20	1
Selenium	200.9	75-125	20	0.005
Selenium	200.8	75-125	20	0.02
Silica	200.7	80-120	20	1
Silver	200.9	75-125	20	0.01
Silver	200.8	75-125	20	0.005
Sodium	200.7	80-120	20	1
Strontium	200.7	80-120	20	0.05
Thallium	200.9	75-125	20	0.02
Thallium	200.8	75-125	20	0.005
Tin	200.9	75-125	20	0.05
Titanium	200.7	80-120	20	0.1
Uranium	200.7	80-120	20	0.1
Vanadium	200.7	80-120	20	0.02
Zinc	200.7	80-120	20	0.05
Zinc	200.8	75-125	20	0.05

<u>CONSTITUENT</u>	<u>Method</u>	<u>ACCURACY % REC-AR</u>	<u>PRECISION RPD-MAV</u>	<u>MDA pCi/L</u>
Radiochemistry				
Gamma Emitters	901.1	80-120	20	1
Gross Alpha	900.0	60-140	30	1
Gross Beta	900.0	60-140	30	1
Radon	913.0	N/A	20	10
Strontium 90	905.0	60-140	30	1
Total Radium	900.1	75-125	20	1
Radium 226	903.1	75-125	20	1
Radium 228	904.0	75-125	20	1
Tritium	906.0	75-125	20	300
Uranium	908.0	75-125	20	1

Quality Assurance Objectives

TABLE 5-3 Quality Assurance Objectives for Solid Waste / Hazardous Waste Methods

<u>CONSTITUENT</u>	<u>ACCURACY % REC-AR</u>	<u>PRECISION RPD-MAV</u>	<u>DLR mg/Kg</u>
Method EPA 8010			
Surrogates			
BFB	50-150	N/A	N/A
Fluorobenzene	50-150	N/A	N/A
Chlorofluorobenzene	50-150	N/A	N/A
Analytes			
Azobenzene	50-150	30	5
Benzidine	50-150	30	5
Benzoic acid	50-150	30	5
Benzylchloride	50-150	20	5
bis(2-Chloroisopropyl)ether	50-150	20	5
Bromobenzene	50-150	20	5
Bromochloromethane	50-150	20	5
Bromodichloromethane	42-172	20	5
Bromoform	13-159	20	5
Bromomethane	D-144	20	5
Carbon tetrachloride	43-143	20	5
Chlorobenzene	38-150	20	5
Chloroethane	46-137	20	5
Chloroform	49-133	20	5
1-Chlorohexane	50-150	20	5
Chloromethane	D-193	20	5
2-Chlorotoluene	50-150	20	5
Chlorotoluene	50-150	20	5
DBCP	50-150	20	5
Dibromochloromethane	24-191	20	5
1,2-Dibromoethane	50-150	20	5
Dibromomethane	50-150	20	5
1,2-Dichlorobenzene	D-208	20	5
1,3-Dichlorobenzene	7-187	20	5
1,4-Dichlorobenzene	42-143	20	5
1,1-Dichloroethane	47-132	20	5
1,2-Dichloroethane	51-147	20	5
1,1-Dichloroethylene	28-167	20	5
cis-1,2-Dichloroethylene	50-150	20	5
trans-1,2-Dichloroethylene	38-155	20	5
1,2-Dichloropropane	44-156	20	5
1,3-Dichloropropane	50-150	20	5
2,2-Dichloropropane	50-150	20	5
1,1-Dichloropropene	50-150	20	5
cis-1,3-Dichloropropene	22-178	20	5
trans-1,3-Dichloropropene	22-178	20	5
Hexachlorobutadiene	50-150	20	5
Methylene chloride	25-162	20	5
1,1,1,2-Tetrachloroethane	50-150	20	5
1,1,2,2-Tetrachloroethane	50-150	20	5

Quality Assurance Objectives

TABLE 5-3 Quality Assurance Objectives for Solid Waste / Hazardous Waste Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>mg/Kg</u>
Method EPA 8010 continued			
Tetrachloroethylene	26-162	20	5
1,2,3-Trichlorobenzene	50-150	20	5
1,2,4-Trichlorobenzene	50-150	20	5
1,1,1-Trichloroethane	41-138	20	5
1,1,2-Trichloroethane	39-136	20	5
Trichloroethylene	35-146	20	5
Trichlorofluoromethane	21-156	20	5
Trichloropropane	50-150	20	5
Vinyl chloride	28-163	20	5
Method EPA 8011			
EDB	50-150	30	0.0005
DBCP	50-150	30	0.0005
Method EPA 8015			
Acrylamide	50-150	40	0.05
Diethyl ether	50-150	40	0.05
Ethanol	50-150	40	0.05
Methyl ethyl ketone	50-150	40	0.05
Methyl isobutyl ketone	50-150	40	0.05
Paraldehyde	50-150	40	0.05
Method EPA 8015M TPH (purgeable)			
Gas	50-150	40	5
Method EPA 8015M TPH (extractable)			
Crude oil	50-150	40	10
Diesel fuel	50-150	40	10
Hydraulic oil	50-150	40	10
Jet fuel	50-150	40	10
Stoddard solvent	50-150	40	10
Waste oil	50-150	40	50
Method EPA 8020			
Benzene	39-159	20	0.003
Chlorobenzene	55-135	20	0.003
Ethylbenzene	32-160	20	0.003
1,2-Dichlorobenzene	37-154	20	0.003
1,3-Dichlorobenzene	50-141	20	0.003
1,4-Dichlorobenzene	42-143	20	0.003
Toluene	46-148	20	0.003
Xylene, o	50-150	20	0.003
Xylene, p	50-150	20	0.003
Xylene, m	50-150	20	0.003

Quality Assurance Objectives

TABLE 5-3 Quality Assurance Objectives for Solid Waste / Hazardous Waste Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>mg/Kg</u>
Method EPA 8040 (analyzed by method 8270)			
2-s-Butyl-4-6-dinitrophenol	50-150	30	0.1
2-Chlorophenol	23-134	30	0.1
4-Chloro-3-methylphenol	22-147	30	0.2
2,4-Dichlorophenol	39-135	30	0.1
2,4-Dimethylphenol	42-109	30	0.1
2,4-Dinitrophenol	D-191	30	0.5
2-Methyl-4,6-Dinitrophenol	D-181	30	0.5
2-Methylphenol	50-150	30	0.1
4-Methylphenol	50-150	30	0.1
2-Nitrophenol	29-182	30	0.1
4-Nitrophenol	29-182	30	0.5
Pentachlorophenol	14-176	30	0.5
Phenol	5-112	30	0.1
2,3,4,6-Tetrachlorophenol	50-150	30	0.1
2,3,5,6-Tetrachlorophenol	50-150	30	0.1
2,3,4-Trichlorophenol	37-144	30	0.1
2,3,5-Trichlorophenol	37-144	30	0.1
2,3,6-Trichlorophenol	37-144	30	0.1
2,4,5-Trichlorophenol	37-144	30	0.1
2,4,6-Trichlorophenol	37-144	30	0.1
Method EPA 8080			
Surrogates			
Hexachlorobenzene	50-150	30	N/A
Dibutylchloroendate	20-150	30	N/A
Analytes			
Aldrin	34-132	43	0.05
Alpha BHC	37-134	30	0.05
Beta BHC	17-147	30	0.05
Delta BHC	19-140	30	0.05
Chlordane	45-119	30	0.05
o,p - DDD	31-141	30	0.05
p,p - DDD	31-141	30	0.05
o,p - DDE	30-145	30	0.05
p,p - DDE	30-145	30	0.05
o,p - DDT	23-134	50	0.05
p,p - DDT	23-134	50	0.05
Dieldrin	31-134	38	0.05
Endosulfan I	45-153	30	0.05
Endosulfan II	D-202	30	0.05
Endosulfan sulfate	26-144	30	0.05
Endrin	42-139	45	0.05
Endrin aldehyde	50-150	30	0.05
Heptachlor	35-130	30	0.05
Heptachlor epoxide	37-142	30	0.05

Quality Assurance Objectives

TABLE 5-3 Quality Assurance Objectives for Solid Waste / Hazardous Waste Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>mg/Kg</u>
Method EPA 8080 continued			
Lindane	46-127	50	0.05
Methoxychlor	50-150	30	0.1
Toxaphene	41-126	30	0.1
PCB 1016	50-114	30	0.5
PCB 1221	15-178	30	0.5
PCB 1232	10-215	30	0.5
PCB 1242	39-150	30	0.5
PCB 1248	38-158	30	0.5
PCB 1254	29-131	30	0.5
PCB 1260	8-127	30	0.5
Method EPA 8140			
Surrogates			
1,3-Dimethyl-2-nitrobenzene	50-150	30	N/A
9-Nitroanthracene	50-150	30	N/A
Analytes			
Azinphos methyl	50-150	30	0.02
Bolstar	50-150	30	0.02
Chlorpyrifos	50-150	30	0.02
Coumaphos	50-150	30	0.02
Demeton-o,s	50-150	30	0.02
Diazinon	50-150	30	0.02
Dichlorvos	50-150	30	0.02
Disulfoton	50-150	30	0.02
Ethoprop	50-150	30	0.02
Fensulfoton	50-150	30	0.02
Fenthion	50-150	30	0.02
Merphos	50-150	30	0.02
Mevinphos	50-150	30	0.02
Naled	50-150	30	0.02
Parathion methyl	50-150	30	0.02
Phorate	50-150	30	0.02
Ronnel	50-150	30	0.02
Stirophos	50-150	30	0.02
Tokuthion	50-150	30	0.02
Trichlornate	50-150	30	0.02
Method EPA 8150			
Surrogate			
2,4-DCAA	30-150	N/A	N/A
Analytes			
Bentazon	30-150	30	0.2
Chloramben	30-150	30	0.1
2,4-D	30-150	30	1
Dalapon	30-150	30	0.1

Quality Assurance Objectives

TABLE 5-3 Quality Assurance Objectives for Solid Waste / Hazardous Waste Methods

<u>CONSTITUENT</u>	<u>ACCURACY % REC-AR</u>	<u>PRECISION RPD-MAV</u>	<u>DLR mg/Kg</u>
Method EPA 8150 continued			
2,4-DB	30-150	30	1
Dicamba	30-150	30	0.1
Dichlorprop	30-150	30	0.2
Dinoseb	30-150	30	0.1
Pentachlorophenol	30-150	30	0.1
Picloram	30-150	30	0.1
2,4,5-T	30-150	30	0.1
2,4,5-TP (Silvex)	30-150	30	0.2
Method EPA 8240			
Surrogates			
1,2-Dichloroethane-d4	61-164	N/A	N/A
Toluene-d8	81-117	N/A	N/A
BFB	67-124	N/A	N/A
Analytes			
Acetone	50-150	30	0.01
Acrolein	50-150	30	0.1
Acrylonitrile	50-150	30	0.1
Benzene	66-142	21	0.005
Bromodichloromethane	35-155	30	0.005
Bromoform	45-169	30	0.005
Bromomethane	D-242	30	0.01
Carbon disulfide	50-150	30	0.005
Carbon tetrachloride	70-140	30	0.005
Chlorobenzene	60-133	21	0.005
Chloroethane	14-230	30	0.01
2-Chloroethylvinyl ether	50-150	30	0.01
Chloroform	51-138	30	0.005
Chloromethane	D-273	30	0.01
Dibromochloromethane	53-149	30	0.005
1,2-Dichlorobenzene	50-150	30	0.005
1,3-Dichlorobenzene	50-150	30	0.005
1,4-Dichlorobenzene	50-150	30	0.005
Dichlorodifluoromethane	50-150	30	0.0005
1,1-Dichloroethane	59-172	21	0.005
1,2-Dichloroethane	49-155	30	0.005
1,1-Dichloroethylene	D-234	30	0.005
trans-1,2-Dichloroethylene	54-156	30	0.005
1,2-Dichloropropane	D-210	30	0.005
cis-1,3-Dichloropropene	D-227	30	0.005
trans-1,3-Dichloropropene	17-183	30	0.005
Ethanol	50-150	30	10
Ethylbenzene	37-162	30	0.005
2-Hexanone	50-150	30	0.005
Methylene chloride	D-221	30	0.005

Quality Assurance Objectives

TABLE 5-3 Quality Assurance Objectives for Solid Waste / Hazardous Waste Methods

<u>CONSTITUENT</u>	<u>ACCURACY % REC-AR</u>	<u>PRECISION RPD-MAV</u>	<u>DLR mg/Kg</u>
Method EPA 8240 continued			
2-Butanone (MEK)	50-150	30	0.01
4-Methyl-2-pentanone (MIBK)	50-150	30	0.005
Styrene	50-150	30	0.005
1,1,2,2-Tetrachloroethane	46-157	30	0.005
Tetrachloroethylene	64-148	30	0.005
Toluene	59-139	21	0.005
1,1,1-Trichloroethane	52-162	30	0.005
1,1,2-Trichloroethane	52-150	30	0.005
Trichlorethylene	62-137	24	0.005
Trichlorofluoromethane	17-181	30	0.005
Vinyl acetate	50-150	30	0.1
Vinyl chloride	D-251	30	0.01
Xylenes	50-150	30	0.005
Method EPA 8270			
Surrogates			
2-Fluorobiphenyl	30-115	30	N/A
Nitrobenzene-d5	23-120	30	N/A
p-Terphenyl-d14	18-137	30	N/A
2-Fluorophenol	25-121	30	N/A
Phenol-d6	24-113	30	N/A
2,4,6-Tribromophenol	19-122	30	N/A
Analytes			
Acenaphthene	31-137	19	1
Acenaphthylene	33-145	30	1
Aniline	50-150	30	5
Anthracene	27-133	30	1
Benzo(a)anthracene	33-143	30	1
Benzo(a)pyrene	17-163	30	1
Benzo(b)fluoranthene	24-159	30	1
Benzo(k)fluoranthene	11-162	30	1
Benzo(g,h,i)perylene	D-219	30	1
Benzylalcohol	50-150	30	2
bis(2-Chloroethoxy)methane	33-184	30	1
bis(2-Chloroethyl)ether	12-158	30	1
bis(2-Chloroisopropyl)ether	36-166	30	1
bis(2-Ethylhexyl)phthalate	29-137	30	1
4-Bromophenylphenylether	65-114	30	1
Butylbenzylphthalate	D-152	30	1
Chloroaniline	50-150	30	2
Chloronaphthalene	60-180	30	1
Chlorophenylphenylether	25-158	30	1
Chrysene	17-168	30	1
Dibenzo(a,h)anthracene	D-227	30	1
Dibenzofuran	50-150	30	1

Quality Assurance Objectives

TABLE 5-3 Quality Assurance Objectives for Solid Waste / Hazardous Waste Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>mg/Kg</u>
Method EPA 8270 continued			
1,2-Dichlorobenzene	32-129	30	1
1,3-Dichlorobenzene	D-172	30	1
1,4-Dichlorobenzene	28-104	27	1
3,3'-Dichlorobenzidine	8-213	30	2
Diethylphthalate	D-114	30	1
Dimethylphthalate	D-112	30	1
Di-n-butylphthalate	1-118	30	1
2,4-Dinitrotoluene	28-100	47	1
2,6-Dinitrotoluene	50-158	30	1
Di-n-octylphthalate	4-146	30	1
Fluoranthene	26-137	30	1
Fluorene	59-121	30	1
Hexachlorobenzene	50-150	30	1
Hexachlorobutadiene	24-116	30	1
Hexachlorocyclopentadiene	50-150	30	2
Hexachloroethane	40-113	30	1
Indeno(1,2,3-c,d)pyrene	50-150	30	1
Isophorone	21-196	30	1
2-Methylnaphthalene	50-150	30	1
Naphthalene	21-133	30	1
Nitrobenzene	35-180	30	1
N-Nitrosodimethylamine	50-150	30	1
N-Nitrosodi-N-propylamine	41-126	38	1
N-Nitrosodiphenylamine	50-150	30	1
2-Nitroaniline	50-150	30	5
3-Nitroaniline	50-150	30	5
4-Nitroaniline	50-150	30	5
Phenanthrene	54-120	30	1
Pyrene	35-142	36	1
1,2,4-Trichlorobenzene	38-107	23	1
2-Chlorophenol	25-102	50	1
2,4-Dichlorophenol	39-135	30	1
2,4-Dimethylphenol	42-109	30	1
4,6-Dinitro-o-cresol	D-181	30	5
2,4-Dinitrophenol	D-191	30	5
2-Methylphenol	50-150	30	1
4-Methylphenol	50-150	30	1
2-Nitrophenol	29-182	30	1
4-Nitrophenol	11-114	50	5
p-Chloro-m-cresol	26-103	33	2
Pentachlorophenol	17-109	47	5
Phenol	26-90	35	1
2,4,5-Trichlorophenol	50-150	30	1
2,4,6-Trichlorophenol	37-144	30	1
Azobenzene	50-150	30	5

Quality Assurance Objectives

TABLE 5-3 Quality Assurance Objectives for Solid Waste / Hazardous Waste Methods

<u>CONSTITUENT</u>	<u>ACCURACY % REC-AR</u>	<u>PRECISION RPD-MAV</u>	<u>DLR mg/Kg</u>
Method EPA 8270 continued			
Benidine	50-150	30	5
Benzoic Acid	50-150	30	5
Method EPA 8310			
Acenaphthene	70-130	20	3
Acenaphthylene	70-130	20	2
Anthracene	70-130	20	0.1
Benzo(a)anthracene	70-130	20	0.1
Benzo(b)fluoranthene	70-130	20	0.2
Benzo(k)fluoranthene	70-130	20	0.1
Benzo(g,h,i)perylene	70-130	20	0.1
Benzo(a)pyrene	70-130	20	0.2
Chrysene	70-130	20	0.1
Dibenzo(a,h)anthracene	70-130	20	0.3
Fluoranthene	70-130	20	2
Fluorene	70-130	20	2
Indeno(1,2,3-c,d)pyrene	70-130	20	0.1
Naphthalene	70-130	20	2
Phenanthrene	70-130	20	2
Pyrene	70-130	20	0.1
Method EPA 9060			
TOC	80-120	20	50
Method EPA 9020			
TOX	80-120	20	1
EPA Method 418.1M			
TRPH-By IR	50-150	20	10

<u>CONSTITUENT</u>	<u>Method</u>	<u>ACCURACY % REC-AR</u>	<u>PRECISION RPD-MAV</u>	<u>DLR mg/L</u>
Inorganic Chemicals				
Chloride	9056	70-130	30	10
Electrical Conductivity	120.1	80-120	20	1 umhos
Cyanide, Total	335.2	65-135	30	1
Fluoride	335.2	65-135	30	50

Quality Assurance Objectives

TABLE 5-3 Quality Assurance Objectives for Solid Waste / Hazardous Waste Methods

<u>CONSTITUENT</u>	<u>Method</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>mg/L</u>
Inorganic Chemicals				
Nitrogen				
Ammonia-N	350.1	70-130	30	4
Nitrate	9056	70-130	30	4
Nitrite	9056	70-130	30	3
Organic	Calc.	N/A	30	100
Kjeldahl	351.1	65-135	30	100
Total	Calc.	N/A	30	100
Moisture	ASA/UL	N/A	20	N/A
Oil and Grease, Soxhlet	413.1	N/A	30	300
pH	150.1	N/A	20	N/A
Phenols	420.1	65-135	30	5
Phosphorous				
Phosphate	9056	70-130	30	3
Total (see Trace Metals)				
Sulfate	9056	70-130	30	10
Sulfide	376.2	N/A	30	5
Hazardous Waste Characterization				
Corrosivity (pH)	9045	20.0	N/A	N/A
Ignitability	1020	N/A	N/A	N/A
Reactivity	SW-846	N/A	N/A	N/A
Generation	SW-846	N/A	N/A	N/A
Trace Metals				
Aluminum	6010	70-130	30	50
Aluminum	6020	70-130	30	20
Antimony	7041	65-135	30	3
Antimony	6020	65-135	30	1
Arsenic	7060	65-135	30	1
Arsenic	6020	65-135	30	4
Barium	6010	70-130	30	1
Barium	6020	70-130	30	1
Beryllium	6010	70-130	30	0.5
Beryllium	6020	70-130	30	1
Boron	6010	70-130	30	5
Boron	6020	70-130	30	5
Cadmium	6010	70-130	30	3
Cadmium	6020	70-130	30	1
Calcium	6010	70-130	30	50
Chromium	6010	70-130	30	3
Chromium	6020	70-130	30	4
Chromium VI	7196	D-130	30	0.2
Cobalt	6010	70-130	30	3
Cobalt	6020	70-130	30	4
Copper	6010	70-130	30	3

Quality Assurance Objectives

TABLE 5-3 Quality Assurance Objectives for Solid Waste / Hazardous Waste Methods

<u>CONSTITUENT</u>	<u>Method</u>	<u>ACCURACY % REC-AR</u>	<u>PRECISION RPD-MAV</u>	<u>DLR mg/L</u>
Trace Metals continued				
Copper	6020	70-130	30	4
Gold	231.1	70-130	30	3
Iron	6010	70-130	30	3
Lead	7420	70-130	30	4
Lead	6020	70-130	30	1
Organic Lead	LUFT	50-150	20	4
Lithium	7430	70-130	30	3
Magnesium	6010	70-130	30	50
Manganese	6010	70-130	30	2
Manganese	6020	70-130	30	2
Mercury	7471	65-135	30	0.01
Molybdenum	6010	70-130	30	3
Molybdenum	6020	70-130	30	1
Nickel	6010	70-130	30	3
Nickel	6020	70-130	30	2
Phosphorous, Total	6010	65-135	30	50
Potassium	6010	70-130	30	50
Selenium	7740	65-135	30	3
Selenium	6020	65-135	30	4
Silver	6010	70-130	30	3
Silver	6020	70-130	30	1
Sodium	6010	70-130	30	50
Strontium	6010	65-135	30	3
Thallium	7841	65-135	30	3
Thallium	6020	65-135	30	1
Tin	6010	65-135	30	3
Titanium	6010	65-135	30	5
Uranium	6010	65-135	30	5
Vanadium	6010	70-130	30	1
Zinc	6010	70-130	30	3
Zinc	6020	70-130	30	10

Quality Assurance Objectives

TABLE 5-3 Quality Assurance Objectives for Solid Waste / Hazardous Waste Methods

<u>CONSTITUENT</u>	<u>Method</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>MDA</u> <u>pCi/Kg</u>
Radiochemistry				
Gamma Emitters	901.1	80-120	20	1
Gross Alpha	900.0	60-140	30	1
Gross Beta	900.0	60-140	30	1
Radon	913.0	N/A	20	10
Strontium 90	905.0	60-140	30	1
Total Radium	900.1	75-125	20	1
Radium 226	903.1	75-125	20	1
Radium 228	904.0	75-125	20	1
Tritium	906.0	75-125	20	300
Uranium	908.0	75-125	20	1

Quality Assurance Objectives

TABLE 5-4 Quality Assurance Objectives for Ambient Air / Air Pollution Methods

<u>CONSTITUENT</u>	<u>ACCURACY</u> <u>% REC-AR</u>	<u>PRECISION</u> <u>RPD-MAV</u>	<u>DLR</u> <u>ug/m³</u>
Method EPA TO-14			
Surrogates			
2-Bromochloropropane	70-130	N/A	N/A
Analytes			
Acetone	70-130	30	2
Benzene	70-130	30	0.5
Bromodichloromethane	70-130	30	1
Bromoform	70-130	30	1
Bromomethane	70-130	30	1
1,3-Butadiene	70-130	30	1
2-Butanone (MEK)	70-130	30	1
Carbon Disulfide	70-130	30	5
Carbon tetrachloride	70-130	30	1
Chlorobenzene	70-130	30	0.5
Chloroethane	70-130	30	0.5
2-Chloroethyl vinyl ether	70-130	30	5
Chloroform	70-130	30	3
Chloromethane	70-130	30	0.5
Dibromochloromethane	70-130	30	1
1,2-Dibromoethane (EDB)	70-130	30	2
1,3-Dichlorobenzene	70-130	30	1
1,4-Dichlorobenzene	70-130	30	1
1,2-Dichlorobenzene	70-130	30	1
1,1-Dichloroethane	70-130	30	0.5
1,2-Dichloroethane (EDC)	70-130	30	1
1,1-Dichloroethene	70-130	30	1
cis-1,2-Dichloroethene	70-130	30	1
trans-1,2-Dichloroethene	70-130	30	1
1,2-Dichloropropane	70-130	30	0.5
cis-1,3-Dichloropropene	70-130	30	0.5
trans-1,3-Dichloropropene	70-130	30	0.5
Ethyl Benzene	70-130	30	1
2-Hexanone	70-130	30	0.5
Methylene chloride	70-130	30	5
4-Methyl-2-pentanone (MIBK)	70-130	30	0.5
Styrene	70-130	30	1
1,1,2,2-Tetrachloroethane	70-130	30	1
Tetrachloroethylene (PCE)	70-130	30	1
Toluene	70-130	30	1
1,1,1-Trichloroethane (TCA)	70-130	30	1
1,1,2-Trichloroethane	70-130	30	1
Trichloroethene (TCE)	70-130	30	0.5
Trichlorofluoromethane F-11	70-130	30	1
Trichlorotrifluoroethane F-113	70-130	30	2
Vinyl Acetate	70-130	30	2
Vinyl chloride	70-130	30	0.5

Quality Assurance Objectives

TABLE 5-4 Quality Assurance Objectives for Ambient Air / Air Pollution Methods

<u>CONSTITUENT</u>	<u>ACCURACY % REC-AR</u>	<u>PRECISION RPD-MAV</u>	<u>DLR ug/m³</u>
Method EPA TO-14 continued			
Xylenes (Total)	70-130	30	1
Total Petroleum Hydrocarbon	70-130	30	4000
Hydrogen Sulfide (Gold Film)	N/A	30	0.2
<u>CONSTITUENT</u>	<u>ACCURACY % REC-AR</u>	<u>PRECISION RPD-MAV</u>	<u>DLR mg/m³</u>
Method EPA TO-3 (modified)			
Butanes	70-130	30	20
Ethane	70-130	30	10
Hexanes	70-130	30	40
Methane	70-130	30	10
Pentanes	70-130	30	30
Propane	70-130	30	20
<u>CONSTITUENT</u>	<u>ACCURACY % REC-AR</u>	<u>PRECISION RPD-MAV</u>	<u>DLR %</u>
Method ASTM 1945			
Carbon Dioxide	70-130	30	0.1
Carbon Monoxide	70-130	30	0.1
Methane	70-130	30	0.005
Nitrogen	70-130	30	0.02
Oxygen	70-130	30	0.01

100
100
100
100
100

100
100
100
100
100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

Sampling Procedures

Sample collection and sample handling techniques are important aspects of the overall sample analysis process and have a major impact on the quality and validity of the results. Specific containers and preservatives are used to ensure that sample integrity is not lost through volatility or degradation. In addition, contaminants that are likely to interfere or effect the quality of analytical data must be minimized or eliminated. If a client chooses to collect their own samples, experienced lab staff can brief clients by telephone on the proper methods of sample collection. Detailed procedures to ensure sampling consistency and compliance with method requirements are available. The correct container types, bottle sizes, preservatives, container closures, and holding times for sampling are shown in Table 6-1.

6.1 General Precautions

The result of any analytical determination can be no better than the sample on which it is performed. The objective is to obtain a sample that meets the requirements of the sampling program and manage it in such a way that it does not deteriorate or become contaminated before reaching the laboratory. This objective implies that the relative proportions or concentrations of all pertinent components will be the same in the samples as in the material being sampled, and that the sample will be processed in such a way that no significant changes in composition occur before the tests are made.

A sample may be presented to the laboratory for specific determinations with the collector taking responsibility for its validity. Often the laboratory conducts or prescribes the sampling program which is determined in consultation with the user of the test results. Such consultation is essential to ensure the selection of the appropriate sample and analytical methods that provide a true basis for answering the questions that prompted the sampling.

Before filling, rinse the sample bottle two or three times with the water being collected, unless the bottle contains a preservative. Depending on determinations to be performed, fill container full (most organics determinations) or leave space for aeration, mixing, etc. (microbiological analyses). For samples that will be shipped, preferably leave an air space of about one (1) percent of container capacity to allow for thermal expansion. Special precautions are necessary for samples containing organic compounds and trace metals. Because many constituents may be present at concentrations of micrograms per liter, they may be totally or partially lost if proper sampling and preservation procedures are not followed.

Representative samples of some sources can be obtained only by making composites of samples collected over a period of time or at many different sampling points. The details of collection vary so much with local conditions that no specific recommendations would be universally applicable. Sometimes it is more informative to analyze numerous separate samples instead of one composite so as not to obscure high and low results. Sample carefully to ensure that analytical results represent the actual sample composition. The following are several important factors affecting results:

- the presence of suspended matter or turbidity;
- the method chosen for its removal, and;
- the physical and chemical changes brought about by storage or aeration.

Particular care is required when processing (grinding, blending, sieving, filtering) samples to be analyzed for trace constituents, especially metals and organic compounds. Some determinations, particularly of lead, can be invalidated by contamination from such processing.

Sampling Procedures

6.1 General Precautions continued

Treat each sample individually with regard to the substances to be determined, the amount and nature of turbidity present, and other conditions that may influence the results.

It is impractical to give directions covering all conditions. The choice of technique for collecting a homogeneous sample must be left to the analyst's judgment. In general, separate any significant amount of suspended matter by decantation, centrifugation, or an appropriate filtration procedure. Often a slight turbidity can be tolerated if experience shows that it will cause no interference in gravimetric or volumetric tests. Its influence can be corrected in colorimetric tests, where it has potentially the greatest interfering effect. When relevant, state whether or not the sample has been filtered. To measure the total amount of a constituent, do not remove suspended solids, but treat them appropriately.

Make a record of every sample collected and identify every bottle, preferably by attaching an appropriately inscribed tag or label. Record sufficient information to provide positive sample identification at a later date. Include the name of the sample collector, the date, hour, and exact location, the water temperature, and any other data that may be needed for correlation, such as weather conditions, water level, stream flow, post-sampling handling, etc. Provide space on the label for the initials of those assuming sample custody and for the time and date of transfer. Identify sampling points by detailed description, by maps, or with the aid of stakes, buoys, or landmarks in a manner that will permit their identification by other persons without reliance on memory or personal guidance. When sample results are expected to be involved in litigation, it is recommended to use formal "chain-of-custody" procedures which trace sample history from collection to final reporting.

Hot samples collected under pressure should be cooled while still under pressure.

Before collecting samples from distribution systems, flush lines sufficiently to insure that the sample is representative of the supply, taking into account the diameter and length of the pipe to be flushed and the velocity of flow.

Collect samples from wells only after the well has been pumped sufficiently to insure that the sample represents the groundwater source. Sometimes it will be necessary to pump at a specified rate to achieve a characteristic drawdown, if this determines the zones from which the well is supplied. Record pumping rate and drawdown.

When samples are collected from a river or stream, observed results may vary with depth, stream flow, and distance from shore and from one shore to the other. If equipment is available, take an "integrated" sample from top to bottom in the middle of the stream or from side to side at mid-depth.

Lakes and reservoirs are subject to considerable variations from normal causes such as seasonal stratification, rainfall, runoff, and wind. Choose location, depth, and frequency of sampling to reflect local conditions and the purpose of the investigation. Avoid surface scum.

Sampling Procedures

6.1 General Precautions continued

For certain constituents, sampling location is extremely important. Avoid areas of excessive turbulence because of potential loss of volatile constituents and of potential presence of toxic vapors. Avoid sampling at weirs because such locations tend to favor retrieval of lighter-than-water, immiscible compounds. Generally, collect samples beneath the surface in quiescent areas. If composite samples are required, take care that sample constituents are not lost during compositing because of improper handling of the sample being pooled. For example, casual dumping together of portions rather than addition to the composite through a submerged siphon can cause unnecessary volatilization.

Use only representative samples (or those conforming to a sampling program) for examination. The great variety of conditions under which collections must be made makes it impossible to prescribe a fixed procedure. In general, take into account the tests or analyses to be made and the purpose for which the results are needed.

6.1.2 Field Notebook

The sampler or field investigator should keep a field notebook (preferably bound with pages numbered) to record sample collection procedures, dates, laboratory identification, sample collection location, and the name of the sampler. This is important for later recall or legal challenge.

6.2 Sample Collection

6.2.1 Water Sampling

6.2.1.1 Grab or Catch Samples

Strictly speaking, a sample collected at a particular time and place can represent only the composition of the source at that time and place. However, when a source is known to be fairly constant in composition over a considerable period of time or over substantial distances in all directions, then the sample may be said to represent a longer time period or a larger volume, or both, than the specific point at which it was collected. In such circumstances, some sources may be fairly represented by single grab samples. Examples are some water supplies, some surface waters, and rarely, some wastewater streams. When a source is known to vary with time, grab samples collected at suitable intervals and analyzed separately can document the extent, frequency, and duration of these variations. Choose sampling intervals on the basis of the frequency with which changes may be expected, which may vary from as little as five (5) minutes to as long as one (1) hour or more. Seasonal variations in natural systems may necessitate sampling over months. When the source composition varies in space rather than time, collect samples from appropriate locations.

Use great care in sampling wastewater, sludges, sludge banks, and muds. No definite procedure can be given, but take every possible precaution to obtain a representative sample or one conforming to a sampling program.

Sampling Procedures

6.2.1.2 Composite Samples

In most cases, the term "composite sample" refers to a mixture of grab samples collected at the same sampling point at different times. Sometimes the term "time-composite" is used to distinguish this type of sample from others. Time-composite samples are most useful for observing average concentrations that will be used, for example, in calculating the loading or the efficiency of a wastewater treatment plant. As an alternative to the separate analysis of a large number of samples and the computation of average and total results, composite samples represent a substantial saving in laboratory effort and expense. For these purposes, a composite sample representing a 24 hour period is considered standard for most determinations. Under certain circumstances, however, a composite sample representing one shift, or a shorter time period, or a complete cycle of a periodic operation, may be preferable. To evaluate the effects of special, variable, or irregular discharges and operations, collect composite samples representing the period during which such discharges occur.

For determining components or characteristics subject to significant and unavoidable changes on storage, do not use composite samples. Make such determinations on individual samples as soon as possible after collection and preferably at the sampling point. Analyses for all dissolved gases, residual chlorine, soluble sulfide, temperature, and pH are examples of this type of determination. Changes in such components as dissolved oxygen or carbon dioxide, pH, or temperature may produce secondary changes in certain inorganic constituents such as iron, manganese, alkalinity, or hardness. Use time-composite samples only for determining components that can be demonstrated to remain unchanged under the conditions of sample collection and preservation.

Take individual portions in a bottle having a diameter of at least 35 mm at the mouth and a capacity of at least 120 mL. Collect these portions every hour, in some cases every half hour or even every five (5) minutes, and mix at the end of the sampling period or combine in a single bottle as collected. If preservatives are used, add them to the sample bottle initially so that all portions of the composite are preserved as soon as collected. Analysis of individual samples sometimes may be necessary. It is desirable, and often essential, to combine individual samples in volumes proportional to flow. A final sample volume of 2 to 3 L is sufficient for sewage, effluents, and wastes.

Automatic sampling devices are available; however, do not use them unless the sample is preserved as described below. Clean sampling devices, including bottles, daily to eliminate biological growths and other deposits.

6.2.1.3 Integrated Samples

For certain purposes, the information needed is provided best by analyzing mixtures of grab samples collected from different points simultaneously, or as nearly so as possible. Such mixtures sometimes are called integrated samples. An example of the need for such sampling occurs in a river or stream that varies in composition across its width and depth. To evaluate average composition or total loading, use a mixture of samples representing various points in the cross-section, in proportion to their relative flows. The need for integrated samples also may exist if combined treatment is proposed for several separate wastewater streams, the interaction of which may have a significant effect on treatability or even on composition. Mathematical prediction of the interactions may be inaccurate or impossible and testing a suitable integrated sample may provide more useful information.

Sampling Procedures

6.2.1.3 Integrated Samples continued

Both natural and artificial lakes show variations of composition with both depth and horizontal location. However, under many conditions, neither total nor average results are especially significant; local variations are more important. In such cases, examine samples separately rather than integrate them.

Preparation of integrated samples usually requires special equipment to collect a sample from a known depth without contaminating it with overlying water. Knowledge of the volume, movement, and composition of the various parts of the water being sampled usually is required. Therefore, collecting integrated samples is a complicated and specialized process that cannot be described in detail.

6.2.2 Soil Sampling

Soil samples collected from a backhoe, the ground or a soil coring device, should be collected in a thin-walled stainless steel or brass cylinder at least three inches long by one inch in diameter that has been prepared by the laboratory doing the analysis or the project consultant (cylinders can be made to fit inside the preferred split-barrel core sampler). About one inch of soil should be removed from the immediate surface area where the sample is to be taken and the cylinder then pounded in to the soil with a mallet or hammer. No headspace should be present in the cylinder once the sample is collected. When the sample is collected, each end of the cylinder should be covered with teflon tape and then capped with a polyethylene lid, taped and labeled. The sample should be immediately placed in an ice chest and kept cool at 4 C for delivery to the laboratory. Care should be taken throughout, to avoid contamination of both the inside and outside of the cylinder and its contents.

In situations where the above procedure is inappropriate (i.e. semi-solid samples), glass vials with Teflon seal and screw cap should be used.

6.2.3 Special Sampling Considerations

6.2.3.1 Volatile Organics including Organic Lead

When collecting the samples, liquids and solids should be introduced into the vials gently to reduce agitation which might drive off volatile compounds. Liquid samples should be poured into the vial without introducing any air bubbles within the vial as it is being filled. Should bubbling occur as a result of violent pouring, the sample must be poured out and the vial refilled. Each VOA vial should be filled until there is a meniscus over the lip of the vial. The screw-top lid with the septum (Teflon side toward the sample) should then be tightened onto the vial. After tightening the lid, the vial should be inverted and tapped to check for air bubbles. If there are any air bubbles present the sample must be retaken. Two VOA vials should be filled per sample location.

VOA vials for samples with solid or semi-solid (sludges) matrices should be completely filled as best as possible. The vials should be tapped slightly as they are filled to eliminate as much free air space as possible. Two vials should also be filled per sample location.

Sampling Procedures

6.2.3.1 Volatile Organics including Organic Lead continued

VOA vials should be filled and labeled immediately at the point at which the sample is collected. They should NOT be filled near a running motor or any type of exhaust system because discharged fumes and vapors may contaminate the samples. The two vials from each sampling location should then be sealed in separate plastic bags to prevent cross-contamination between samples particularly if the sampled waste is suspected of containing high levels of volatile organics. (Activated carbon may also be included in the bags to prevent cross-contamination from highly contaminated samples). VOA samples may also be contaminated by diffusion of volatile organics through the septum during shipment and storage. To monitor possible contamination, a trip blank prepared from distilled deionized water should be carried throughout the sampling, storage, and shipping process.

6.2.3.2 Semivolatile Organics including Pesticides and Herbicides

Containers used to collect samples for the determination of semivolatile organic compounds should be soap and water washed followed by methanol (or isopropanol) rinsing. The sample containers should be of glass or Teflon and have screw-top covers with Teflon liners. In situations where Teflon is not available, samples may react with the aluminum foil, causing eventual contamination of the sample. Plastic containers or lids may NOT be used for the storage of samples due to the possibility of sample contamination from the phthalate esters and other hydrocarbons within the plastic. Sample containers should be filled with care so as to prevent any portion of the collected sample coming in contact with the field persons gloves, thus causing contamination. Samples should not be collected or stored in the presence of exhaust fumes. If the sample comes in contact with the an automatic sampler run reagent water through the sampler and use as a field blank.

6.2.3.3 Trace Metals

In the determination of trace metals, containers can introduce either positive or negative errors in the measurement of trace metals by (a) contributing contaminants through leaching or surface desorption, and (b) depleting concentrations through adsorption. Thus the collection and treatment of the sample prior to analysis require particular attention.

6.2.3.4 Radiochemistry

6.2.3.4.1 Radon

Sample by slowly running water into a 2 liter or greater bucket until it overflows for 5 minutes. The water entering the bucket should be as free as possible of bubbles. Fill duplicate 250 mL glass boston round bottles under water, taking care to release all of the air bubbles from inside the bottle. Cap each bottle tightly while still under water. Dry the bottles and place electrical tape around the cap. Record the date and time. Ship immediately to the laboratory and keep the samples cool at 4 C.

6.2.3.4.1 Radium

The sample should be acidified at the time of sampling.

Sampling Procedures

6.2.3.5 Air Toxics

In the determination of air toxics there are many ways in which to sample and handle samples. For specifics regarding air toxics sampling and handling please refer to the air toxics sampling standard operating procedure (Document ID S2AIR005.XXX).

6.2.3.6 Product Samples

Free Floating Product (from a well): Sampling of free floating product on the surface of ground water should not be performed until the well has been allowed to stabilize for at least 24 hours after development or other withdrawal procedure. A sample should be collected that is indicative of the thickness of floating product within the monitoring well. This may be accomplished by the use of a clear, acrylic bailer designed to collect a liquid sample where free product and ground water meet. A graduated scale on the bailer is helpful for determining the thickness of free product. Samples should be field-inspected for the presence of odor and/or sheen in addition to the above evaluation. Electronic measuring devices also are available for determining the thickness of the hydrocarbon layer floating on ground water.

6.2.3.7 Aqueous/Dissolved Product

If free product (from a well) is detected, analysis of water for dissolved product should be conducted after the free product has been substantially removed from the well. Before collecting a water sample a well should be purged until temperature, conductivity and pH stabilize. Often, this will require removal of four or more well volumes by bailing or pumping. Once well volumes are removed and well water is stabilized, a sample can be taken after the water level approaches 80 percent of its initial level. Where water level recovery is slow, the sample can be collected after stabilization is achieved.

Ground water samples should be collected in a manner which reduces or eliminates the possibility of loss of volatile constituents from the sample. For collecting samples, a gas-actuated positive displacement pump or a submersible pump is preferred. A Teflon or stainless steel bailer is acceptable. Peristaltic pumps or airlift pumps should not be used.

Cross-contamination from transferring pumps (or bailers) from well to well can occur and should be avoided by thorough cleaning between sampling episodes. Dedicated (i.e., permanent installation) well pumps, while expensive, are often cost effective in the long term and ensure data reliability relative to cross-contamination. If transfer of equipment is necessary, sampling should proceed from the least contaminated to the most contaminated well, if the latter information is available before sample collection.

Water samples should be collected in vials or containers specifically designed to prevent loss of volatile constituents from the sample. These vials should be provided by an analytical laboratory, and preferably, the laboratory conducting the analysis. No headspace should be present in the sample container once the container has been capped. This can be checked by inverting the bottle, once the sample is collected, and looking for bubbles. Sometimes it is not possible to collect a sample without air bubbles, particularly if water is aerated. In these cases, the investigator should record the problem and account for probable error. Cooling samples may also produce headspace (bubbles), but these will disappear once the sample is warmed for analysis.

6.2.3.7 Aqueous/Dissolved Product continued

Samples should be placed in an ice chest maintained at 4 C with blue ice (care should be taken to prevent freezing of the water and bursting of the glass vial). A thermometer with a protected bulb should be carried in each ice chest.

Sampling Procedures

6.3 Sample Handling Policy

Proper sample containers, sample volumes, preservatives, and holding times are essential to providing reliable data. Table 6-1 provides information for each of these items. FGL references the following sources for compiling Table 6-1.

- (1) Federal Register, Volume 49, No. 209, October 26, 1984 and subsequent updates.
- (2) "Handbook for Sampling and Sample Preservation of Water and Wastewater", EPA Method Book, EPA-600/4-82-029, September 1982.
- (3) "Methods for Chemical Analysis in Waters and Waste" (MCAWW) EPA-600/4-79-020
- (4) "Methods for Evaluating Solid Waste", EPA Method Book, SW- 846, rev. 3, and Proposed Revisions.
- (5) "Standard Methods for the Analysis of Water and Wastewater", 17th Edition, 1990.
- (6) "Methods for the Determination of Organic Compounds in Drinking Water", EPA Method Book, EPA-600/4-88-039, December 1988.
- (7) "Methods for the Determination of Organic Compounds in Drinking Water-Supplement I", EPA Method Book, EPA-600/4- 90-020, July 1990.
- (8) "Methods for the Determination of Organic Compounds in Drinking Water-Supplement II", EPA Method Book, EPA-600/4- 90-020, July 1990.
- (9) "Methods for Organic Chemical Analysis of Municipal and Industrial Wastewater", EPA Method Book, EPA 600/4-82-057, July 1982.
- (10) "Prescribed Procedures for Measurement of Radioactivity in Drinking Water", EPA Method Book, EPA-600/4-80-032, August 1980.

6.3.1 Container Check Policy

Sample bottles for most analyses, such as metals, and organics analyses, are purchased precleaned according to EPA Protocol specification from various vendors. Cases of sample bottles are logged in upon receipt. The log book contains the bottle type, lot number or manufacture date, receive date and number of cases. This information is also recorded on the document provided by the manufacturer and is retained in a file for that bottle type. Most containers are checked and documented by the manufacturer. Bacteriology and Santa Paula metals bottles must be checked in-house by lot or on a manufacture date basis. If neither of these are available then one container must be checked from every ten cases. The following files are to be maintained for storing certificates or in-house analysis data:

40 mL VOA - for all VOA styles
125 mL Boston Round (B.R.) - for all 125 mL B.R. bottle styles
250 mL Boston Round (B.R.) - for all 250 mL B.R. bottle styles
1 L Boston Round (B.R.)
250 mL Wide Mouth (W.M.)
1 Qt. Wide Mouth (W.M.)
4 oz. Bact
500 mL Plastic (SP only, for Al, Sb, As, Ba, Be, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Hg, Ni, K, Se, Ag, Na, Tl, V, Zn)

For those bottles not listed and not verified (such as 1 Qt plastic) it has been determined that the tests performed from those containers are not at risk from contamination by the container.

Sampling Procedures

6.3.1 Container Check Policy continued

When an in-house verification is required the sample is given a lab number, chain-of-custody and is treated as a regular sample. The results are formally reported but only the signature of the QA Director or Officer to verify cleanliness is required prior to filing.

Lots determined to be contaminated are returned and replaced.

6.3.2 Shipping Samples

Prior to shipment of samples, all documentation must be ready for proper chain of custody. The information necessary for documenting chain of custody is outlined in the following section of the quality assurance manual (section 7). After filling out the proper sample documentation, the samples and documents should be placed in an ice chest with adequate protection. Normally "Blue Ice" is used for keeping samples cool. However, dry ice may be used if approved by Department of Transportation (DOT).

6.3.3 Sample Kits

FGL Environmental supplies the appropriate sample containers, preservatives, chain-of-custody forms, coolers with blue ice, and packing materials to client upon request. There is no charge for these services as long as FGL is the laboratory receiving the samples for analysis. Arrangements for sample kits may be made through the client services department.

Sampling Procedures

TABLE 6-1 RECOMMENDED SAMPLE COLLECTION AND PRESERVATION

<u>Analysis</u>	<u>Container</u>	<u>Volume (mL)</u>	<u>Preservation</u>	<u>Holding Time</u>
General Inorganic Chemistry				
Acidity	P,G	250	Cool, 4 C	14 days
Alkalinity	P,G	250	Cool, 4 C	14 days
Asbestos	G	1000	Cool, 4 C	48 hr.
Bicarbonate	P	250	Cool, 4 C	14 days
Biochemical Oxygen Demand	P,G	1000	Cool, 4 C	48 hr.
Boron	P	250	Cool, 4 C	6 mo.
Bromide	P	250	Cool, 4 C	28 days
Carbonate	P	250	Cool, 4 C	14 days
Carbon Dioxide	P,G	250	Cool, 4 C	immed.
Chemical Oxygen Demand	P,G	250	H ₂ SO ₄ , pH<2; Cool, 4 C	28 days
Chloride	P,G	250	Cool, 4 C	28 days
Chlorine Residual	P,G	500	Cool, 4 C	2 hr.
Chlorine Demand	P,G	2000	Cool, 4 C	2 hr.
Color	P,G	250	Cool, 4 C	48 hr.
Cyanide, Total	P,G	1000	NaOH, pH>12; Cool, 4 C	14 days
Electrical Conductivity	P	250	Cool, 4 C	28 days
Fluoride	P,G	250	Cool, 4 C	28 days
Hardness, Total	P,G	250	HNO ₃ , pH<2; Cool, 4 C	6 mo.
Hydroxide	P,G	250	Cool, 4 C	14 days
Iodide	P,G	250	Cool, 4 C	24 hr.
Langelier Index	P,G	500	Cool, 4 C	2 hr.
MBAS	P,G	500	Cool, 4 C	48 hr.
Nitrogen,				
Ammonia	P,G	250	H ₂ SO ₄ , pH<2; Cool, 4 C	28 days
Nitrate+Nitrite	P,G	250	H ₂ SO ₄ , pH<2; Cool, 4 C	28 days
Nitrate	P,G	250	Cool, 4 C	48 hr.
Nitrite	P,G	250	Cool, 4 C	48 hr.
Organic	P,G	400	H ₂ SO ₄ , pH<2; Cool, 4 C	28 days
Total	P,G	250	H ₂ SO ₄ , pH<2; Cool, 4 C	28 days
Total Kjeldahl	P,G	250	H ₂ SO ₄ , pH<2; Cool, 4 C	28 days
Odor	G	500	Cool, 4 C	24 hr.
Oil and Grease	G	1000	H ₂ SO ₄ , pH<2; Cool, 4 C	28 days
Oxygen, Dissolved	G	250	Cool, 4 C	immed.
w/glass stopper				
pH	P,G	250	Cool, 4 C	2 hr.
Phenolics	G	500	H ₂ SO ₄ , pH <2; Cool, 4 C	28 days

P = plastic, G = glass

Note: All solid samples should be collected in stainless steel sleeves, brass sleeves or in glass jars all with teflon-lined caps and 4-8 oz. capacity. All solid samples should be kept cool at 4 C.

Sampling Procedures

TABLE 6-1 RECOMMENDED SAMPLE COLLECTION AND PRESERVATION

<u>Analysis</u>	<u>Container</u>	<u>Volume (mL)</u>	<u>Preservation</u>	<u>Holding Time</u>
General Inorganic Chemistry continued				
Phosphorus				
Ortho/dissolved	P,G	250	Cool, 4 C	48 hr.
Total	P,G	250	H ₂ SO ₄ , pH<2; Cool, 4 C	28 days
Resistivity	P	250	Cool, 4 C	28 days
Silica	P	250	Cool, 4 C	28 days
Sodium Absorption Ratio	P	250	HNO ₃ , pH<2	6 mo.
Solids,				
Filterable	P,G	250	Cool, 4 C	7 days
Non-filterable	P,G	250	Cool, 4 C	7 days
Total	P,G	250	Cool, 4 C	7 days
Volatile	P,G	250	Cool, 4 C	7 days
Settleable	P,G	1000	Cool, 4 C	48 hr.
Sulfate	P,G	250	Cool, 4 C	28 days
Sulfide				
Total	P,G	500	2 ml ZnAcetate+NaOH, pH>9	7 days
Dissolved	P,G	500	NaOH, pH>9	7 days
Tannin & Lignin	G	250		
Titration - pH adjustment	P,G	250	Cool, 4 C	14 days
Turbidity	P,G	250	Cool, 4 C	48 hr.
Trace Metals				
Chromium VI	P,G	500	Cool, 4 C	24 hr.
Mercury	P,G	500	HNO ₃ , pH<2	28 days
All other metals	P	500	HNO ₃ , pH<2	6 mo.
Radiochemistry				
Gross Alpha & Beta**	P	1000	HNO ₃ , pH <2	6 mo.
Total Radium	P	1000	HNO ₃ , pH <2	6 mo.
Total Uranium	P	1000	HCl, pH <2	6 mo.
Radon*	G	2x250	Cool, 4 C	4 days
Tritium	G	2x250	Cool, 4 C	6 mo.
Strontium 90	P	1000	HCl, pH <2	6 mo.

P = plastic, G = glass

* No headspace over sample

** For non-preserved samples, the holding time is 5 days. For preserved samples, please provide either a non-preserved sample (100 mL) or the electrical conductivity prior to acidification.

Note: All solid samples should be collected in stainless steel sleeves, brass sleeves or in glass jars all with teflon-lined caps and 4-8 oz. capacity. All solid samples should be kept cool at 4 C.

Sampling Procedures

TABLE 6-1 RECOMMENDED SAMPLE COLLECTION AND PRESERVATION

<u>Analysis</u>	<u>Container</u>	<u>Volume (mL)</u>	<u>Preservation</u>	<u>Holding Time</u>
All Bacteriological	P,G	100	0.008% Na ₂ S ₂ O ₃ ; Cool, 4 C, Sterile	30 hr.

<u>Analysis</u>	<u>Container</u>	<u>Volume (mL)</u>	<u>Preservation</u>	<u>Holding Time</u>
-----------------	------------------	--------------------	---------------------	---------------------

Organic Chemicals

Drinking Water

EPA 501*	G, VOA TFE-septa cap	2 x 40	Na ₂ S ₂ O ₃ , if chlorinated HCl, pH <2; Cool, 4 C	14 days
EPA 502.2*	G, VOA TFE-septa cap	2 x 40	Na ₂ S ₂ O ₃ , if chlorinated HCl pH <2; Cool, 4 C	14 days
EPA 504*	G TFE-septa cap	2 x 40	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	28 days
EPA 505**	G TFE-septa cap	2 x 40	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	7 days
EPA 507	G, amber TFE-lined cap	1 x 1000	Na ₂ S ₂ O ₃ , if chlorinated or HCl pH <2; Cool, 4 C	14 days
EPA 508**	G, amber TFE-lined cap	1 x 1000	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	7 days
EPA 510*	G, amber TFE-septa cap	1 x 250	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	14 days
EPA 515.1**	G, amber TFE-lined cap	1 x 1000	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	7 days
EPA 524.2*	G, VOA TFE-septa cap	2 x 40	Na ₂ S ₂ O ₃ , if chlorinated or HCl pH <2; Cool, 4 C	14 days
EPA 525**	G, amber TFE-lined cap	1 x 1000	Cool, 4 C	7 days

* No head space over sample.

** This is the maximum holding time prior to extraction. The extracted sample may be held up to 40 days before analysis.

Sampling Procedures

TABLE 6-1 RECOMMENDED SAMPLE COLLECTION AND PRESERVATION

<u>Analysis</u>	<u>Container</u>	<u>Volume (mL)</u>	<u>Preservation</u>	<u>Holding Time</u>
Organic Chemicals				
<u>Drinking Water</u>				
EPA 531	G, amber	1 x 250	Na ₂ S ₂ O ₃ , if chlorinated Monochloroacetic acid buffer	14 days
EPA 547	G, amber	1 x 125	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	6 mo.
EPA 548	G, amber	1 x 125	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	7 days
EPA 549	G, amber silanized	1 x 1000	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	7 days
EPA 550.1	G, amber	1 x 1000	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	7 days
EPA 551	G, amber	2 x 40	NH ₄ Cl, Cool, 4 C	28 days
EPA 552	G, amber	1 x 1000	NH ₄ Cl, Cool, 4 C	14 days
EPA 1613A	G, amber	1 x 1000	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	7 days
<u>Wastewater and Hazardous Waste</u>				
EPA 601/8010*	G, VOA TFE-septa cap	2 x 40	Na ₂ S ₂ O ₃ , if chlorinated HCl, pH <2; Cool, 4 C	14 days
EPA 8011	G, VOA TFE-septa cap	2 x 40	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	28 days
EPA 602/8020*	G, VOA TFE-septa cap	2 x 40	Na ₂ S ₂ O ₃ , if chlorinated HCl, pH <2; Cool, 4 C	14 days
EPA 603/8030*	G, VOA TFE-septa cap	2 x 40	Na ₂ S ₂ O ₃ , if chlorinated Adjust pH to 4-5; Cool, 4 C	14 days
EPA 604/8040**	G, amber TFE-lined cap	1 x 1000	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	7 days

* No head space over sample.

** This is the maximum holding time prior to extraction. The extracted sample may be held up to 40 days before analysis.

Sampling Procedures

TABLE 6-1 RECOMMENDED SAMPLE COLLECTION AND PRESERVATION

<u>Analysis</u>	<u>Container</u>	<u>Volume (mL)</u>	<u>Preservation</u>	<u>Holding Time</u>
Organic Chemicals				
<u>Wastewater and Hazardous Waste</u>				
EPA 608/8080**	G, amber TFE-lined cap	1 x 1000	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	7 days
EPA 610/8310	G, amber TFE-lined cap	1 x 1000	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	14 days
EPA 613**	G, amber TFE-lined cap	1 x 1000	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	7 days
EPA 614/8140**	G, amber TFE-lined cap	1 x 1000	Cool, 4 C	7 days
EPA 615/8150**	G, amber TFE-lined cap	1 x 1000	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	7 days
EPA 619	G, amber TFE-lined cap	1 x 1000	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	14 days
EPA 624/8240*	G, VOA TFE-septa cap	2 x 40	Na ₂ S ₂ O ₃ , if chlorinated HCl, pH <2; Cool, 4 C	14 days
EPA 625/8270**	G, amber TFE-lined cap	1 x 1000	Na ₂ S ₂ O ₃ , if chlorinated Cool, 4 C	7 days
EPA 632**	G, amber TFE-lined cap	1 x 1000	Cool, 4 C	7 days
EPA 9020* (TOX)***	G, amber TFE-lined cap	1 x 250	H ₂ SO ₄ , pH <2 Cool, 4 C	28 days*
EPA 415.1/9060 (TOC)	G, amber TFE-lined cap	1 x 250	HCl or H ₂ SO ₄ , pH <2 Cool, 4 C	28 days
Tributyltin	G, amber TFE-lined cap	2 x 1000	Cool, 4 C	28 days

* No head space over sample.

** This is the maximum holding time prior to extraction. The extracted sample may be held up to 40 days before analysis.

*** RCRA holding time is 7 days.

Note: All solid samples should be collected in stainless steel sleeves, brass sleeves or in glass jars all with teflon-lined caps and 4-8 oz. capacity. All solid samples should be kept cool at 4 C.

Sampling Procedures

TABLE 6-1 RECOMMENDED SAMPLE COLLECTION AND PRESERVATION

<u>Analysis</u>	<u>Container</u>	<u>Volume (mL)</u>	<u>Preservation</u>	<u>Holding Time</u>
Organic Chemicals				
<u>Underground Storage Tank Analyses</u>				
EPA 418.1	G, amber TFE-lined cap	1 x 1000	Cool, 4 C	28 days
EPA 8015,8015M*	G, VOA TFE-septa cap	2 x 40	HCl, pH <2 Cool, 4 C	14 days
EPA 601/8010*	G, VOA TFE-septa cap	2 x 40	Na ₂ S ₂ O ₃ , if chlorinated HCl, pH <2; Cool, 4 C	14 days
EPA 602/8020*	G, VOA TFE-septa cap	2 x 40	Na ₂ S ₂ O ₃ , if chlorinated HCl, pH <2; Cool, 4 C	14 days
Hazardous Waste Characterization				
Corrosivity	P,G	100	Cool, 4 C	7 days
Ignitability	G TFE-lined cap	100	Cool, 4 C	7 days
Reactivity/ Reactions	G TFE-lined cap	100	Cool, 4 C	7 days
Sulfide/Sulfide generation	G TFE-lined cap	100	Cool, 4 C	7 days

* No head space over sample.

Note: All solid samples should be collected in stainless steel sleeves, brass sleeves or in glass jars all with teflon-lined caps and 4-8 oz. capacity. All solid samples should be kept cool at 4 C.

Sampling Procedures

TABLE 6-1 RECOMMENDED SAMPLE COLLECTION AND PRESERVATION

<u>Analysis</u>	<u>Container</u>	<u>Volume (mL)</u>	<u>Preservation</u>	<u>Holding Time</u>
TTLIC, STLC, TCLP, and EP Toxicity				
Metals	G TFE-lined cap	500	Cool, 4 C	30 days
Pesticides	G, amber TFE-lined cap	1000	Cool, 4 C	7 days
Herbicides	G, amber TFE-lined cap	1000	Cool, 4 C	7 days
Bioassays				
Chronic	P,G	3x1000	Cool, 4 C	24 hr.
Acute	P,G	2x5 gal	Cool, 4 C	24 hr.

Note: All solid samples should be collected in stainless steel sleeves, brass sleeves or in glass jars all with teflon-lined caps and 4-8 oz. capacity. All solid samples should be kept cool at 4 C.

Sample Custody

7.1 Sample Custody

It is essential to ensure sample integrity from the time of collection through analysis and final disposition. This includes the ability to trace possession and handling of the samples. This is referred to as chain-of-custody and is important in the event of litigation involving the results. Where litigation is not involved, chain-of-custody procedures are useful for routine control of sample flow.

A sample is considered to be under a person's custody if it is in the individual's physical possession, in the individual's sight, secured in a tamper-proof manner by that individual, or is secured in an area restricted to authorized personnel. The following procedures summarize the major aspects of chain-of-custody.

7.1.1 Sample Labels

Use labels to prevent sample misidentification. Gummed paper labels or tags generally are adequate. Include at least the following information: sample number, name of collector, date and time of collection, and place of collection. Affix labels to sample containers before or at the time of sampling. Fill label out with waterproof ink at time of collection.

7.1.2 Custody Seals

Use sample seals to detect unauthorized tampering with samples up to the time of analysis. Plastic seals are normally used. Attach seal in such a way that it is necessary to break the seal to open the sample container. Affix seal to container before sample leaves custody of sampling personnel.

7.1.3 Field Log Book

Record all information pertinent to a field survey or sampling in a bound log book. As a minimum, include the following in the log book: purpose of sampling; location of sampling point; name and address of field contact; producer of material being sampled and address, if different from location; and type of sample. Because sampling situations vary widely, no general rule can be given as to the information to be entered in the log book. It is desirable to record sufficient information between the logbook and chain-of-custody so that one could reconstruct the sampling without reliance on the collector's memory. Protect the log book and keep it in a safe place.

7.1.4 Shipping Samples or Sample Delivery to Laboratory

Prior to shipping samples all documentation must be ready for proper chain of custody. The information necessary for documenting chain of custody is outlined section 7.3. After filling out the proper sample documentation, the samples and documents should be placed in an ice chest with adequate protection. Normally "Blue Ice" is used for keeping samples cool. However, dry ice may be used if approved by Department of Transportation (DOT).

If client provides direct delivery of sample to laboratory, samples should be delivered as soon as practical. Documentation must be ready for proper chain of custody. Again, all information necessary for documenting chain of custody is outlined section 7.3. Accompany sample with chain- of-custody record and a sample analysis request sheet. Deliver sample to sample custodian.

Sample Custody

7.1.6 Receipt and Logging of Sample

In the laboratory, the sample custodian receives the sample and inspects its condition and seal, reconciles label information and seal against the chain-of-custody record, assigns a laboratory number, logs sample in the laboratory computer, and stores it in a secured storage room or cabinet until it is assigned to an analyst.

7.1.7 Assignment of Sample for Analysis

The laboratory supervisor usually assigns the sample for analysis. Once in the laboratory, the supervisor or analyst is responsible for the sample's care and custody.

7.1.8 Safety Considerations

Because sample constituents can be toxic, take adequate precautions during sampling and sample handling. Toxic substances can enter through the skin and, in the case of vapors, through the lungs. Inadvertent ingestion can occur via direct contact with foods or by adsorption of vapors onto foods. Precautions may be limited to wearing gloves or may include coveralls, aprons, or other protective apparel. Always wear eye protection. When toxic vapors might be present, sample only in well-ventilated areas or use a respirator or self-contained breathing apparatus. In a laboratory, open sample containers in a fume hood. Never have food near samples or sampling locations; always wash hands thoroughly before handling food.

If there is any possibility that flammable organic compounds may be present, take adequate precautions. Prohibit smoking near samples, sampling locations, and in the laboratory. Keep sparks, flames, and excessive heat sources away from samples, and sampling locations.

Radioactivity is screened at the time of sample receipt. Consult the radiation safety SOP and Radiation Safety Officer for proper handling of samples.

7.2 Laboratory Sample Control and Tracking

FGL's sample control objectives are achieved through the use of a Laboratory Information Management System (LIMS). LIMS is a computer software system specifically designed by FGL for tracking and handling of the large amount of information required to efficiently manage an analytical chemistry laboratory. The system provides a versatile, easy-to-use vehicle for the laboratory managers and chemists to perform sample tracking and status checks.

7.3 Sample Receiving Policy

Obtain a chain-of-custody record accompanying each sample or group of samples. The chain-of-custody is usually prepared in the field.

Sample Custody

7.3.1 Obtain the following client information and record on chain of custody:

Reporting -

Address
Phone Number
Fax Number
Person to Contact

Billing -

Address
Phone Number
Fax Number
P.O. or contract Number
Person to Contact

7.3.2 Obtain the following project and sample information and record on chain of custody:

Project description
Sample descriptions
Sample type
Sampling date and time
Sample containers, preservatives
EPA Method Numbers or method descriptions
Report form required: ____ State ____ FGL
Determine turn-around-time requirement:
Rush _____ Number of Days _____

7.3.3 Inspect the sample for the following:

Have holding times been observed and determine if it is possible for FGL to meet holding times?

Has the correct preservative been used?

Is the sample size adequate?

Is the sample container satisfactory?

Note sample condition :

Broken/leaking container

Temperature _____ Ambient _____ Chilled

Record Actual Temperature

Check for headspace when appropriate

Also note on the chain of custody any problems with sample condition, the person notified, time and date notified, and customers response, if any.

Screen all samples for radio chemical hazard using the Geiger counter kept in the sample receiving area. Consult the radiation safety SOP and Radiation Safety Officer for proper handling of samples.

7.3.4 Log the sample information into the LIMS under one of the following divisions:

Inorganic
Organic
Radiochemistry
Bacteriology
Agronomics

Sample Custody

7.3.5 Transfer samples and analyses worksheets to the proper refrigerator or lab work distribution area.

7.4 Sample Storage

All samples are retained for a minimum of 30 days except for microbiological samples which are held for a shorter time. A longer storage period can be arranged at the request of the client.

7.5 Sample Disposal

All samples which are considered to be potentially hazardous based upon analytical results or matrix, will be disposed of by lab packing. Extremely hazardous samples may be returned to the client for disposal. All disposal arrangements should be made with a project manager.

7.6 Subcontracted Lab Work

On occasion, laboratory work may need to be subcontracted to certified labs approved by FGL Environmental. Prior to subcontracting the client will be notified. Under no circumstances will work be subcontracted without client requirements being met. When work is subcontracted, it is done so under chain of custody, and the proper records are included with the data package. When work is subcontracted between the FGL laboratories the original chain of custody is carried forward with the samples. When work is subcontracted to an outside laboratory a separate chain of custody is prepared.

Sample Custody

Figure 7-1 Chain of Custody

This page intentionally left blank for the figure on the next 2 pages.



CHAIN OF CUSTODY AND ANALYSIS REQUEST DOCUMENT

Information and directions for completion

The attached document (Chain of Custody) is designed to encompass all the pertinent information pertaining to the sample(s) to be collected/received and the subsequent analysis(es).

Please note that all sampling and analyses conducted by this laboratory are subject to the terms and conditions on the reverse side of the Chain of Custody.

SECTION I This section should be fully completed and clearly printed. If the billing address differs from the regular address, this should be especially noted. For routine sampling, please indicate if pre log program is required.

SECTION II If the sample is to be taken by you, please clearly print the name of the sampler, the date and time. If the sample is to be taken by FGL, our certificated sampler will be responsible for this information.

SECTION III Please indicate if a rush analysis is requested. If so, please circle the appropriate rush period required. When the chain is received at the lab, you will be notified if this rush is not available. Please indicate if a QA/QC report or a state form is required. The laboratory number and location will be assigned by FGL when the sample(s) are received at the laboratory.

SECTION IV Please number by sample and not by individual test. Each test required (from the numbered sample), should be entered in the diagonal spaces provided to the right. In addition, please ensure that all information is entered in the appropriate boxes, on the same line as the numbered sample.

SECTION V Please use this section to make specific notes; i.e. special sampling, reporting instructions, etc.

SECTION VI requires a signature by a person authorized to relinquish the sample to an FGL representative. If a sample is being shipped, a relinquishing signature is required prior to releasing the sample (properly packaged) to the shipping agent. The receipt of a copy of the shipping document, maintains the integrity of the Chain of Custody.

The correct container(s) to be used for individual tests, with appropriate preservatives can be obtained from FGL. When calling the laboratory for containers, please be specific about the analyses required and if applicable, the number of locations. Samples must be kept cool. Coolers will be provided if requested.

Color Coding of Containers All containers which contain a preservative are marked with a Color Printed Label. The color scheme conforms to industry standards where applicable, and is provided as a quick reference for locating the correct container. Preservative and corresponding labels colors are set out hereunder:

Blue	HCL pH < 2	Black	Monochloroacetic Buffer
Gold	H2SO4 pH < 2	Green	NaOH pH > 12 or NaOH + Zinc Acetate
Red	HNO3 pH < 2	Black	Na2S2O3
		White	Other

WE ARE PLEASED TO HAVE THIS OPPORTUNITY TO SERVE YOU

If you have any questions or need sampling assistance, do not hesitate to call us at:

Santa Paula (805) 659 0910

Stockton (209) 942 0181

SECTION I

Customer Number: _____

```

Pre Log Required: yes _____ no _____

```

SECTION IV

[illegible]

SECTION II

Time: _____ Mileage: _____

SECTION III

Lab Loc: SP ☐ STK ☐ VI ☐ _____ ☐[illegible]

SECTION V

SECTION VI

Received by: _____ Date _____ Time _____

FIELD OFFICE
Visalia, California
Tel: (209) 734-9473
Mobile: (209) 737-2394
FAX (209) 734-8435

100

Calibration Procedures and Frequency

The production of analytical data of known, defensible and documented quality requires adherence to standardized procedures which cover all aspects of laboratory operation. The following sections provide details of the standardized procedures relating to instrumentation calibration.

8.1 Instrument Calibration

Prior to use, every instrument must be calibrated according to the procedure found in the method specific Standard Operating Procedure (SOP). A list of all laboratory equipment may be found in section 17. Tables 8-1 and 8-2 list the organic mass spectrometer calibration ion abundance criteria which must be met.

The analytical balances are certified once a year by a certified specialist. All balances are labelled as certified. All balances are checked monthly using NIST traceable S weights which are calibrated annually.

All refrigerator, oven, and incubator temperatures are monitored daily, and all oven and incubator thermometers are checked for accuracy on a quarterly basis.

8.2 Calibration Standards

All chemicals used by FGL Environmental are ACS reagent grade, or better. Wherever possible, standards are from sources that are traceable to the National Institute of Standards and Technology. A log book is maintained for all working standards. Each log contains the standard ID or code, date of working standard preparation, analyst initials who prepared the standard, the manufacturers lot number, stock solution expiration date, stock analyte concentration(s), analyte concentration(s), and initial and final volumes used in dilutions. The working standard container is also labeled with ID or code, date of standard preparation, analyst initials who prepared the standard, expiration date, analytes and analyte concentration. The standards are tracked from the logbook to the analysis in the following manner:

- 1) Working standards and spiking concentrates are labeled and coded. Stock standards should also be labeled and coded if they are used directly for calibration or spiking purposes.
- 2) The standard code is the date the standard was made, the analyst's initials, and the number referring to the first, second, third etc. standard of the day (i.e. 020395KW1).
- 3) The calibration and spiking standard codes should all be recorded with the analytical results. This can be done in several fashions:
 - a. If the test is performed manually the codes should be recorded on the batch sheet.
 - b. If the test is automated the codes can usually be recorded as part of the sample description which is printed by the instrument..
 - c. If the test is calibrated periodically then the original calibration information should have the codes recorded with it (i.e. cyanide, IC, 418.1). The daily calibration CCV's and spike codes should be recorded with each run.

Calibration Procedures and Frequency

8.3 Calibration Policy

8.3.1 Applicability

This policy is designed to be a guideline to ensure that all data are treated alike, and thus ensuring that data generated on any particular day of analysis are representative of the norm. However, the policies are not intended to be absolute criteria for the acceptance or rejection of any analytical data. In cases where the acceptance criteria outlined in policy or SOPs cannot be achieved then the analyst uses a non-conformance report form to document the difficulty. More than one continuing difficulty will result in a Corrective Action Report (CAR, see section 15). These are on record and will be included in a project data package if that is required by the project plan. An example of a CAR form is shown in figure 15-1.

8.3.2 Linearity

All calibrations should be linear unless otherwise defined in the specific SOP. FGL's definition of linearity is a calibration curve that has a linear regression equal to or greater than 0.995. For organics, if a linear regression is used, a single average response factor may be used if acceptance criteria pass. Specific protocols outlined in a given SOP will take precedence over these generic policies.

8.3.3 Selection of Quantitation Technique (Organics)

For organic analysis, a decision must be made during the validation process (and detailed in the SOP) as to whether an internal or external quantitation technique will be routinely employed.

The internal standard method of quantitation cannot be employed unless all of the following conditions are met:

- (1) The internal standard must be added post-extraction.**
- (2) The internal standard must be added quantitatively.**
- (3) Any analyte that is a target analyte in the method of interest may not be selected for use as an internal standard.**
- (4) The concentration of the internal standard(s) must not exceed the calibration range of the method target analyte. In cases where the target analytes are associated with more than one calibration range (i.e. analytes "1-4" are calibrated from 1 to 10 ppb, while analyte "5" is calibrated from 10 to 100 ppb, all target analytes should be prepared at a level between the highest and lowest calibration standard (e.g. approximately 50 ppb in the example given).**

The use of internal standard quantitation is of greatest benefit in those methods subject to injection variability, and thus, variability in the absolute mass injected onto the column(s) employed. The drawback to this technique, for GC methods, is that any compound which exhibits a similar retention time as the compound used for the internal standard will be identified as the internal standard, leading to erroneous quantitation. For this reason, the internal standard technique is most useful for GC/MS where deuterated analytes not naturally occurring can be detected and quantified.

Calibration Procedures and Frequency

8.3.4 Selection of Calibration Method

As part of the validation process, the specific calibration range and calibration method must be determined and documented in the SOP. Once determined in this manner, the same protocols must be followed each time the method is employed. This will ensure that data reduction is not performed differently on separate data sets by different analysts. The calibration acceptance criteria are listed in section 8.3.8. A least squares (linear) regression is initially tried as a calibration method. For organics, if a linear regression is used, a single average response factor may be used. For inorganics, if the acceptance criteria cannot be met using a linear regression, then a second order polynomial can be used to fit the data, with the same acceptance criteria being applied. In the event that neither a simple linear regression nor a second order polynomial fit result in an equation which meets the calibration acceptance criteria, then the calibration range must be reduced.

8.3.5 Minimum Number of Calibration Levels

Most calibrations include a minimum of three or five initial calibration standards plus a blank. Specific SOPs may have other requirements.

8.3.6 Selection of Calibration Levels

Two standards should be included per order of magnitude of concentration of the calibration curve. For example 0.1, 1.0, 10.0 has 2 standards per order magnitude (0.1 and 1.0; 1.0 and 10.0). In cases where instrumentation spans several orders of magnitude, the SOP for that method may not require this policy. The lowest calibration level should be within a factor of 10 of the detection limit for reporting (DLR) for each target compound unless otherwise specified in the SOP.

8.3.7 Calibration Analysis Sequence

The calibration must progress from the analysis of the lowest to highest standard unless the instrumentation does not permit it. A blank must be analyzed after the highest calibration standard.

If the analysis requires an initial high standard to set the gain, a blank must be run before starting with the low calibration standard unless the instrumentation does not permit it.

8.3.8 Calibration Acceptance Criteria

In general, for inorganics, the calculated value for standards must be within 10% of the expected value. However, the value determined by the calibration curve for the lowest standard must be within +/- 50% of the true value and if the calibration is linear through the origin (at less than +/- 1/2 the detection limit). For organics, if a linear regression is used, a single average response factor may be used. The percent relative standard deviation for the individual standard response factors must be less than the maximum value listed for the method in the SOP.

Calibration Procedures and Frequency

8.3.9 Calibration Check Compounds (CCC) and Initial Calibration Verifications (ICV's)

The CCC or ICV is used to check the validity of the initial calibration. This standard is composed of some or all of the same analytes used for calibration but from a different source than the calibration standard. The standard should be at a concentration near the midpoint of the curve. In many cases FGL uses a Laboratory Control Sample (LCS) as an ICV. In this case the LCS verifies both the calibration and sample preparation. FGL uses control charts for LCS's and acceptance ranges for many analytes have been statistically derived. Please see table 5-1 for acceptance limits. If calculated acceptance criteria are not listed, the general acceptance range is $\pm 25\%$ of the true value for organics and $\pm 10\%$ for inorganics.

8.3.10 Continuing Calibration Verifications (CCV)

The CCV is used to verify continuing calibration validity without having to completely restandardize the instrument. Refer to specific EPA methods or SOPs to determine whether this is required. The continuing calibration standard should be near the mid-point of the calibration curve. If calculated acceptance criteria are not listed, the general acceptance range is $\pm 25\%$ of the true value for organics and $\pm 10\%$ for inorganics.

8.3.11 Organic Mass Spectrometry Tuning Criteria

In addition to the above calibration criteria, GC/MS methods require mass spectrometer tuning. The acceptance criteria for volatile organics using bromofluorobenzene (BFB) are listed in table 8-1. The acceptance criteria for semivolatile organics using decafluorotriphenylphosphene (DFTPP) are listed in table 8-2.

Table 8-1

GC/MS Volatile Organic and Air Toxics Key Ion Abundance Tuning Criteria, using BFB

<u>Mass</u>	<u>Ion Abundance Criteria</u>
50	15 to 40% of mass 95
75	30 to 60% of mass 95
95	base peak, 100% relative abundance
96	5 to 9% of mass 95
173	less than 2% of mass 174
174	greater than 50% of mass 95
175	5 to 9% of mass 174
176	greater than 95% but less than 101% of mass 174
177	5 to 9% of mass 176

Calibration Procedures and Frequency

Table 8-2

GC/MS Semivolatile Organic Key Ion Abundance Tuning Criteria, using DFTPP

<u>Mass</u>	<u>Ion Abundance Criteria</u>
51	30 to 60% of mass 198
68	less than 2% of mass 69
70	less than 2% of mass 69
127	40 to 60% of mass 198
197	less than 1% of mass 198
198	base peak, 100% relative abundance
199	5 to 9% of mass 198
275	10 to 30% of mass 198
365	greater than 1% of mass 198
441	present but less than mass 443
442	greater than 40% of mass 198
443	17 to 23% of mass 442

Calibration Procedures and Frequency

8.3.12 Calibration Frequency

8.3.12.1 Inorganics

For trace metals analyses calibrations are performed initially for each analytical run. After initial calibration verification (ICV) recalibration or continuing calibration checks are used every ten analyses. For wet chem analyses, a new curve is generated every six months. To verify daily calibration of wet chem methods a continuing calibration verifications (CCV) is used. Exceptions may exist for method specific SOPs.

8.3.12.2 Organics

GC and GC/MS methods are calibrated initially for all analytes. For each additional day of operation, a calibration check standard is analyzed and evaluated. If the calibration is deemed valid the analysis may be performed. Otherwise, the system is recalibrated. Exceptions may exist for method specific SOPs.

8.3.12.3 Radiochemistry

All methods utilize recalibration or continuing calibration verifications every ten samples. EPA check samples are performed quarterly. DOE check sample are performed on a semiannual basis. The results must be acceptable to maintain certification. Exceptions may exist for certain method specific SOP's

8.3.12.3.1 Gas Proportional Counters

Gas proportional counters are calibrated for each matrix and sample size. For most liquid samples an efficiency vs. mg chart for each instrument is fit to a polynomial equation, which is stored in the computer for automated calculation.

8.3.12.3.2 Liquid Scintillation

Liquid Scintillation analyzers are calibrate for each matrix and sample size. Standards are initially run in duplicate with calibration verifications performed on each analytical run.

8.3.12.3.3 Gamma Spectroscopy

Gamma spectroscopy analyses are calibrated for both energy and efficiency. The calibration range is from 20 keV to 1350 keV with a minimum of 7 strong peaks per calibration for each geometry and matrix.

Analytical Procedures

9.1 Method Sources

FGL uses EPA or standard methods for most analyses. The following method manuals are used as references:

Drinking Water Methods -

- 1) "Methods for Chemical Analysis in Waters and Waste," (MCAWW) EPA-600/4-79-020
- 2) "Standard Methods for the Analysis of Water and Wastewater," 17th Edition, 1990.
- 3) "Methods for the Determination of Organic Compounds in Drinking Water," EPA Method Book, EPA-600/4-88-039, December 1988.
- 4) "Methods for the Determination of Organic Compounds in Drinking Water-Supplement I," EPA Method Book, EPA-600/4-90-020, July 1990.
- 5) "Methods for the Determination of Organic Compounds in Drinking Water-Supplement II," EPA Method Book, EPA-600/4-90-020, July 1990.
- 6) "Eastern Environmental Radiation Facility Radiochemistry Procedures Manual," EPA Method Book, EPA 520/5-84-006, August 1984.
- 7) "Environmental Measurements Laboratory Procedures," HASL-300, 27th Edition, February 1992.

Wastewater Methods -

- 1) "Methods for Chemical Analysis in Waters and Waste," (MCAWW) EPA-600/4-79-020
- 2) "Standard Methods for the Analysis of Water and Wastewater," 17th Edition, 1990.
- 3) "Methods for Organic Chemical Analysis of Municipal and Industrial Wastewater," EPA Method Book, EPA 600/4-82-057, July 1982.
- 4) "Eastern Environmental Radiation Facility Radiochemistry Procedures Manual," EPA Method Book, EPA 520/5-84-006, August 1984.
- 5) "Environmental Measurements Laboratory Procedures," HASL-300, 27th Edition, February 1992.

Solid Waste / Hazardous Waste Methods -

- 1) "Methods for Evaluating Solid Waste," EPA Method Book, SW- 846, revision 3, and proposed revisions.
- 2) "Eastern Environmental Radiation Facility Radiochemistry Procedures Manual," EPA Method Book, EPA 520/5-84-006, August 1984.
- 3) "Environmental Measurements Laboratory Procedures," HASL-300, 27th Edition, February 1992.

Ambient Air / Air Pollution Methods -

- 1) "Compendium of Methods for the Determination of Toxic Organic Compounds in Ambient Air," EPA Method Book, EPA-600/4-, June 1988.
- 2) "Technical Assistance Document for Sampling and Analysis of Toxic Organic Compounds in Ambient Air," EMSL, EPA Method Book, EPA-600/4-83-027, 1983

9.2 Standard Operating Procedures (SOPs)

FGL has specific standard operating procedures (SOPs) for each analytical test we perform. The specific format and use for these procedures is given in SOP S0QA010.XXX.

9.3 Specific Methods Used for Analysis

The analytical methods performed at FGL fall into three general categories: drinking waters, wastewaters, solid waste / hazardous waste and ambient air / air pollution methods. These methods are listed in Tables 9-1 - 9-4.

Analytical Procedures

TABLE 9-1 Specific Analytical Drinking Water Methods

Parameter	Method	Description
Organic Chemicals		
Trihalomethanes	EPA 501.2	GC/ECD, micro extraction
Volatile Organics	EPA 502.2	GC/PID/Hall, purge & trap
Dibromochloropropane (DBCP) and Ethylene dibromide (EDB)	EPA 504	GC/ECD, micro extraction
Chlorinated Pesticides	EPA 505	GC/ECD, micro extraction
Nitrogen/phosphorus Pesticides	EPA 507	GC/NPD, liquid-liquid
Chlorothalonil	EPA 508	GC/ECD, liquid-liquid
PCB's as Decachlorobiphenyl	EPA 508A	GC/ECD, liquid-liquid
Trihalomethane Form. Potential	EPA 510	GC/ECD, micro extraction
Herbicides	EPA 515.1	GC/ECD, liquid-liquid
Volatile Organics	EPA 524.2	GC/MS, purge & trap
Diethylhexylphthalate	EPA 525	GC/MS, SPE
Carbamates	EPA 531	HPLC, post column derivatization
Glyphosate (Roundup)	EPA 547	HPLC, post column derivatization
Endothall	EPA 548	HPLC, post column derivatization
Paraquat and Diquat	EPA 549	HPLC, post column derivatization
Polynuclear Aromatic Hydrocarbons	EPA 550.1	HPLC, post column derivatization
Haloacetic Acids	EPA 552.1	HPLC, post column derivatization, SPE
General Inorganic Analyses		
Acidity	EPA 305.1	Titration
Aggressive Index	N/A	Calculation
Alkalinity (CaCO ₃)	EPA 310.1	Titration
Bicarbonate (HCO ₃)	EPA 310.1	Titration
Biochemical Oxygen Demand (BOD ₅)	EPA 405.1	ISE
Bromide (Br)	EPA 300.0	IC
Carbon Dioxide (CO ₂)	SM 4500CO ₂	Titration
Carbonate (CO ₃)	EPA 310.1	Titration
Chemical Oxygen Demand (COD)	EPA 410.2	Colorimetric
Chloride (Cl)	EPA 300.0	IC
Chlorine Residual (Cl ₂)	EPA 330.2	Titration
Chlorine Residual (Cl ₂)	EPA 330.5	Colorimetric
Chlorine Demand	SM 409A	Colorimetric
Color	EPA 110.3	Observation
Cyanide, Total (CN)	EPA 335.2	Colorimetric
Electrical Conductivity (EC)	EPA 120.1	Conductivity Bridge
Fluoride (F)	EPA 340.2	ISE
Hardness, total (as CaCO ₃)	EPA 130.2	Titration
Hardness, total (as CaCO ₃)	SM 2340B	Calculation
Hydroxide (OH)	EPA 310.1	Titration
Langelier Index (corrosivity)	SM 2330B	Calculation
MBAS	EPA 425.1	Colorimetric

Analytical Procedures

TABLE 9-1 Specific Analytical Drinking Water Methods

Parameter	Method	Description
General Inorganic Analyses continued		
Nitrogen		
Ammonia (NH ₃ -N)	EPA 350.1	Colorimetric
Nitrate (NO ₃ -N)	EPA 300.0	IC
Nitrite (NO ₂ -N)	EPA 300.0	IC
Nitrate (NO ₃ -N)	EPA 353.2	Colorimetric
Nitrite (NO ₂ -N)	EPA 353.2	Colorimetric
Organic (TKN-NH ₃ -N)	N/A	Calculation
Total (TKN+NO ₃ -N+NO ₂ -N)	N/A	Calculation
Total Kjeldahl	EPA 351.2	Colorimetric
Odor	EPA 140.1	Observation
Oil and Grease	EPA 413.1	Gravimetric
Oxygen, Dissolved (DO)	EPA 360.1	ISE
pH	EPA 150.1	ISE
Phenols	EPA 420.1	Colorimetric
Phosphorous		
Phosphate (PO ₄ -P)	EPA 300.0	IC
Phosphate-dissolved (PO ₄ -P)	EPA 300.0	IC
Total (P)	EPA 365.2	Colorimetric
Total-dissolved (P)	EPA 365.2	Colorimetric
Resistivity	N/A	Calculation
Sodium Percent	N/A	Calculation
Sodium Absorption Ratio (SAR)	EPA 200.7	ICP
Solids/Residue		
Filterable (TDS)	EPA 160.1	Gravimetric
Non-filterable (TSS)	EPA 160.2	Gravimetric
Total	EPA 160.3	Gravimetric
Volatile	EPA 160.4	Gravimetric
Settleable	EPA 160.5	Gravimetric
Sulfate (SO ₄)	EPA 300.0	IC
Sulfide (H ₂ S)		
Total	EPA 376.2	Methylene Blue
Dissolved	EPA 376.2	Methylene Blue
Sulfite (SO ₂)	EPA 377.1	Titrimetric
Tannin & Lignin	SM 5500B	Colorimetric
Titration - pH adjustment	N/A	Titration
Turbidity	EPA 180.1	Nephelometric
Trace Metals Analyses		
Aluminum (Al)	EPA 200.9	Furnace Atomic Absorption
Aluminum (Al)	EPA 200.8	ICP/MS
Antimony (Sb)	EPA 200.9	Furnace Atomic Absorption
Antimony (Sb)	EPA 200.8	ICP/MS
Arsenic (As)	EPA 200.9	Furnace Atomic Absorption
Arsenic (As)	EPA 200.8	ICP/MS
Barium (Ba)	EPA 200.7	ICP
Barium (Ba)	EPA 200.8	ICP/MS

Analytical Procedures

TABLE 9-1 Specific Analytical Drinking Water Methods

Parameter	Method	Description
Trace Metals Analyses continued		
Beryllium (Be)	EPA 200.7	ICP
Beryllium (Be)	EPA 200.8	ICP/MS
Boron (B)	EPA 200.7	ICP
Boron (B)	EPA 200.8	ICP/MS
Cadmium (Cd)	EPA 200.9	Furnace Atomic Absorption
Cadmium (Cd)	EPA 200.8	ICP/MS
Calcium (Ca)	EPA 200.7	ICP
Chromium (Cr)	EPA 200.9	Furnace Atomic Absorption
Chromium (Cr)	EPA 200.8	ICP/MS
Chromium VI (Cr+6)	EPA 7196	Colorimetric
Cobalt (Co)	EPA 200.7	ICP
Cobalt (Co)	EPA 200.8	ICP/MS
Copper (Cu)	EPA 200.7	ICP
Copper (Cu)	EPA 200.8	ICP/MS
Iron (Fe)	EPA 200.7	ICP
Lead (Pb)	EPA 200.9	Furnace Atomic Absorption
Lead (Pb)	EPA 200.8	ICP/MS
Lithium (Li)	SM 3500LiB	Flame Atomic Absorption
Magnesium (Mg)	EPA 200.7	ICP
Manganese (Mn)	EPA 200.7	ICP
Manganese (Mn)	EPA 200.8	ICP/MS
Mercury (Hg)	EPA 245.1	Cold Vapor Atomic Absorption
Mercury (Hg)	EPA 245.2	Cold Vapor Atomic Absorption
Molybdenum (Mo)	EPA 200.7	ICP
Molybdenum (Mo)	EPA 200.8	ICP/MS
Nickel (Ni)	EPA 200.7	ICP
Nickel (Ni)	EPA 200.8	ICP/MS
Potassium (K)	EPA 200.7	ICP
Selenium (Se)	EPA 200.9	Furnace Atomic Absorption
Selenium (Se)	EPA 200.8	ICP/MS
Silica (SiO ₂)	EPA 200.7	ICP
Silver (Ag)	EPA 200.9	Furnace Atomic Absorption
Silver (Ag)	EPA 200.8	ICP/MS
Sodium (Na)	EPA 200.7	ICP
Thallium (Tl)	EPA 200.9	Furnace Atomic Absorption
Thallium (Tl)	EPA 200.8	ICP/MS
Tin (Sn)	EPA 200.9	Furnace Atomic Absorption
Vanadium (V)	EPA 200.7	ICP
Vanadium (V)	EPA 200.8	ICP/MS
Zinc (Zn)	EPA 200.7	ICP
Zinc (Zn)	EPA 200.7	ICP/MS

Analytical Procedures

TABLE 9-1 Specific Analytical Drinking Water Methods

Parameter	Method	Description
Radiochemical Analyses		
Gross Alpha	EPA 900.0	Proportional Counter
Gross Beta	EPA 900.0	Proportional Counter
Gross Alpha & Beta	EPA 900.0	Proportional Counter
Gamma Emitters	EPA 901.1	HPGe, gamma spectroscope
Total Radium*	EPA 900.1	Isolation, Proportional Counter
Radium 226	EPA 903.1	Radon bubbler, Lucas cell scintillation
Radium 228	EPA 904.0	Isolation, Proportional Counter
Uranium	EPA 908.0	Isolation, Proportional Counter
Tritium	EPA 906.0	Distillation, Liquid Scintillation
Radon	EPA 913.0	Liquid Scintillation
Bacteriological Analyses		
Total & Fecal Coliform	SM9221E	Fermentation, MPN, 10 tube
Total Coliform-Colilert	SM9221D	Presence-Absence
Standard Plate Count	SM9215B	Incubation, visual count

* Can be reported as Radium 226 if less than 3 pCi/liter.

Analytical Procedures

TABLE 9-2 Specific Analytical Wastewater / Hazardous Waste Liquid Methods

Parameter	Method	Description
Organic Chemical Analyses		
Sample Preparation	EPA 3510	Liquid-Liquid extraction
Sample Preparation	EPA 3520	Continuous Liquid- Liquid Extraction
Sample Preparation	EPA 3580	Solvent Dilution
Purgeable Halocarbons	EPA 601/8010	GC/PID/Hall, purge & trap
EDB and DBCP	EPA 8011	GC/ECD, micro extraction
Non-Halogenated Volatile Organics	EPA 8015	GC/FID, purge & trap
Total Petroleum Hydrocarbons	EPA 8015M	GC/FID, purge & trap
Purgeable		
Non-Halogenated Volatile Organics	EPA 8015M	GC/FID, micro extraction
Extractable		
Aromatic Volatile Organics	EPA 602/8020	GC/FID, purge & trap
Phenols	EPA 604/8040	GC/ECD, liquid- liquid
Chlorinated Pesticides & PCB's	EPA 608/8080	GC/ECD, liquid- liquid
Polynuclear Aromatic Hydrocarbons	EPA 610/8310	HPLC/UV, liquid- liquid
Organophosphorus Pesticides	EPA 614/8140	GC/FPD, liquid- liquid
Chlorinated Herbicides	EPA 615/8150	GC/ECD, liquid- liquid
Volatile Organics	EPA 624/8240	GC/MS, purge & trap
Semi-volatile Organics	EPA 625/8270	GC/MS, liquid- liquid
Carbamates	EPA 632	HPLC/UV, liquid- liquid
Total Organic Carbon (TOC)	EPA 415.1/9060	IR, combustion
Total Organic Halogens (TOX)	EPA 9020	Coulometric, Pyrolysis
Total Recov. Pet. Hydrocarbons	EPA 418.1	IR, liquid-liquid
General Inorganic Analyses		
Acidity	EPA 305.1	Titration
Aggressive Index	N/A	Calculation
Alkalinity (CaCO ₃)	EPA 310.1	Titration
Bicarbonate (HCO ₃)	EPA 310.1	Colorimetric
Biochemical Oxygen Demand (BOD ₅)	EPA 405.1	ISE
Bromide (Br)	EPA 300.0	IC
Carbonate (CO ₃)	EPA 310.1	Titration
Carbon Dioxide (CO ₂)	SM 4500CO ₂	Titration
Chemical Oxygen Demand (COD)	EPA 410.2	Colorimetric
Chloride (Cl)	EPA 300.0	IC
Chlorine Residual (Cl ₂)	EPA 330.2	Titration
Chlorine Residual (Cl ₂)	EPA 330.5	Colorimetric
Chlorine Demand	SM 409A	Titration
Color	EPA 110.3	Visual
Cyanide, Total (CN)	EPA 335.2	Colorimetric
Electrical Conductivity (EC)	EPA 120.1	Conductivity Bridge
Fluoride (F)	EPA 340.2	ISE
Hardness, total (as CaCO ₃)	EPA 130.2	Titration
Hydroxide (OH)	EPA 310.1	Titration
Langelier Index (corrosivity)	SM 2330B	Calculation
MBAS	EPA 425.1	Colorimetric

Analytical Procedures

TABLE 9-2 Specific Analytical Wastewater / Hazardous Waste Liquid Methods

Parameter	Method	Description
General Inorganic Analyses continued		
Nitrogen		
Ammonia (NH ₃ -N)	EPA 350.1	Colorimetric
Nitrate (NO ₃ -N)	EPA 300.0	IC
Nitrite (NO ₂ -N)	EPA 300.0	IC
Organic (TKN-NH ₃ -N)	Calculation	
Total (TKN+NO ₃ -N+NO ₂ -N)	Calculation	
Total Kjeldahl	EPA 351.2	Colorimetric
Odor	EPA 140.1	Observation
Oil and Grease	EPA 413.1	Gravimetric
Oxygen, Dissolved (DO)	EPA 360.1	ISE
pH	EPA 150.1	ISE
Phenols	EPA 420.1	Colorimetric
Phosphorous		
Phosphate (PO ₄ -P)	EPA 300.0	IC
Phosphate-dissolved (PO ₄ -P)	EPA 300.0	IC
Total (P)	EPA 365.2	Colorimetric
Total-dissolved (P)	EPA 365.2	Colorimetric
Resistivity	N/A	Calculation
Sodium Percent	N/A	Calculation
Sodium Absorption Ratio (SAR)	EPA 200.7	ICP
Solids/Residue		
Filterable (TDS)	EPA 160.1	Gravimetric
Non-filterable (TSS)	EPA 160.2	Gravimetric
Total	EPA 160.3	Gravimetric
Volatile	EPA 160.4	Gravimetric
Settleable	EPA 160.5	Gravimetric
Sulfate (SO ₄)	EPA 300.0	IC
Sulfide (H ₂ S)		
Total	EPA 376.2	Methylene Blue
Dissolved	EPA 376.2	Methylene Blue
Sulfite (SO ₂)	EPA 377.1	Titrimetric
Tannin & Lignin	SM 513	Colorimetric
Titration - pH adjustment	N/A	Titration
Turbidity	EPA 180.1	Nephelometric
Trace Metals Analyses		
Sample Preparation	EPA 3015	Digestion
Aluminum (Al)	EPA 200.9	Furnace Atomic Absorption
Aluminum (Al)	EPA 200.8	ICP/MS
Antimony (Sb)	EPA 200.9	Furnace Atomic Absorption
Antimony (Sb)	EPA 200.8	ICP/MS
Arsenic (As)	EPA 200.9	Furnace Atomic Absorption
Arsenic (As)	EPA 200.8	ICP/MS
Barium (Ba)	EPA 200.7	ICP
Barium (Ba)	EPA 200.8	ICP/MS
Beryllium (Be)	EPA 200.7	ICP
Beryllium (Be)	EPA 200.8	ICP/MS

Analytical Procedures

TABLE 9-2 Specific Analytical Wastewater / Hazardous Waste Liquid Methods

Parameter	Method	Description
Trace Metals Analyses continued		
Boron (B)	EPA 200.7	ICP
Boron (B)	EPA 200.8	ICP/MS
Cadmium (Cd)	EPA 200.9	Furnace Atomic Absorption
Cadmium (Cd)	EPA 200.8	ICP/MS
Calcium (Ca)	EPA 200.7	ICP
Chromium (Cr)	EPA 200.9	Furnace Atomic Absorption
Chromium (Cr)	EPA 200.8	ICP/MS
Chromium VI (Cr+6)	EPA 7196	Colorimetric
Cobalt (Co)	EPA 200.7	ICP
Cobalt (Co)	EPA 200.8	ICP/MS
Copper (Cu)	EPA 200.7	ICP
Copper (Cu)	EPA 200.8	ICP/MS
Gold (Au)	EPA 231.1	Flame Atomic Absorption
Iron (Fe)	EPA 200.7	ICP
Lead (Pb)	EPA 200.9	Furnace Atomic Absorption
Lead (Pb)	EPA 200.8	ICP/MS
Lithium (Li)	SM 3500LiB	Flame Atomic Absorption
Magnesium (Mg)	EPA 200.7	ICP
Manganese (Mn)	EPA 200.7	ICP
Manganese (Mn)	EPA 200.8	ICP/MS
Mercury (Hg)	EPA 245.1	Cold Vapor Atomic Absorption
Mercury (Hg)	EPA 245.2	Cold Vapor Atomic Absorption
Molybdenum (Mo)	EPA 200.7	ICP
Molybdenum (Mo)	EPA 200.8	ICP/MS
Nickel (Ni)	EPA 200.7	ICP
Nickel (Ni)	EPA 200.8	ICP/MS
Potassium (K)	EPA 200.7	ICP
Selenium (Se)	EPA 200.9	Furnace Atomic Absorption
Selenium (Se)	EPA 200.8	ICP/MS
Silica (SiO ₂)	EPA 200.7	ICP
Silver (Ag)	EPA 200.9	Furnace Atomic Absorption
Silver (Ag)	EPA 200.8	ICP/MS
Sodium (Na)	EPA 200.7	ICP
Strontium (Sr)	EPA 200.7	ICP
Thallium (Tl)	EPA 200.9	Furnace Atomic Absorption
Thallium (Tl)	EPA 200.8	ICP/MS
Tin (Sn)	EPA 200.9	Furnace Atomic Absorption
Titanium (Ti)	EPA 200.7	ICP
Uranium (U)	EPA 200.7	ICP
Vanadium (V)	EPA 200.7	ICP
Zinc (Zn)	EPA 200.7	ICP
Zinc (Zn)	EPA 200.7	ICP/MS

Analytical Procedures

TABLE 9-2 Specific Analytical Wastewater / Hazardous Waste Liquid Methods

Parameter	Method	Description
Radio Chemical Analyses		
Gross Alpha	EPA 900.0	Proportional counter
Gross Beta	EPA 900.0	Proportional counter
Gross Alpha & Beta	EPA 900.0	Proportional counter
Gamma Emitters	EPA 901.1	HPGe, gamma spectroscopy
Total Radium*	EPA 900.1	Isolation, Proportional Counter
Radium 226	EPA 903.1	Radon bubbler, Lucas cell scintillation
Radium 228	EPA 904.0	Isolation, Proportional Counter
Uranium	EPA 908.0	Isolation, proportional counter
Tritium	EPA 906.0	Distillation, liquid scintillation
Radon	EPA 913.0	Liquid scintillation
Bacteriological Analyses		
Total Coliform	SM9221E	Fermentation, MPN, 15 tube
Total & Fecal Coliform	SM9221E	Fermentation, MPN, 15 tube
Standard Plate Count	SM9215B	Incubation, visual count

* Can be reported as Radium 226 if less than 3 pCi/liter.

Analytical Procedures

TABLE 9-3 Specific Analytical Solid Waste / Hazardous Waste Methods

Parameter	Method	Description
Organic Chemical Analyses		
Sample Preparation - STLC	Title 22	Extraction
Sample Preparation - EP TOX	EPA 1310	Extraction
Sample Preparation - TCLP	EPA 1311	Extraction
Sample Preparation	EPA 3510	Liquid-Liquid extraction
Sample Preparation	EPA 3520	Continuous Liquid- Liquid Extraction
Sample Preparation	EPA 3540	Soxhlet Extraction
Sample Preparation	EPA 3550	Sonication Extraction
Sample Preparation	EPA 3580	Solvent Dilution
Purgeable Halocarbons	EPA 8010	GC/PID/Hall, purge & trap
EDB and DBCP	EPA 8011	GC/ECD, micro extraction
Non-Halogenated Volatile Organics	EPA 8015	GC/FID, purge & trap
Total Petroleum Hydrocarbons	EPA 8015M	GC/FID, purge & trap
Purgeable		
Total Petroleum Hydrocarbons	EPA 8015M	GC/FID, micro extraction
Extractable		
Aromatic Volatile Organics	EPA 8020	GC/FID, purge & trap
Phenols	EPA 8040	GC/CED, soxhlet or sonication
Chlorinated Pesticides & PCB's	EPA 8080	GC/ECD, soxhlet or sonication
Polynuclear Aromatic Hydrocarbons	EPA 8100	GC/PID, soxhlet or sonication
Organophosphorus Pesticides	EPA 8141	GC/FPD, soxhlet or sonication
Chlorinated Phenoxy Herbicides	EPA 8150	GC/ECD, soxhlet or sonication
Volatile Organics	EPA 8240	GC/MS, purge & trap
Semi-volatile Organics	EPA 8270	GC/MS, soxhlet or sonication
Polynuclear Aromatic Hydrocarbons	EPA 8310	HPLC/UV, liquid- liquid
Carbamates	EPA 632	HPLC/UV, liquid- liquid
Total Organic Carbon (TOC)	EPA 9060	IR, combustion
Total Organic Halogens (TOX)	EPA 9020	Coulometric, Pyrolysis
Total Recov. Pet. Hydrocarbons	EPA 418.1	IR, liquid-liquid
General Inorganic Analyses		
Chloride (Cl)	EPA 9056	IC
Electrical Conductivity	EPA 120.1	Conductivity bridge
Cyanide, total (CN)	EPA 335.2	Distillation- Colorimetric
Fluoride (F)	EPA 340.1	Distillation-ISE
Moisture	ASA/UL	Gravimetric
Nitrogen		
Ammonia (NH ₃ -N)	EPA 350.1	Colorimetric
Nitrate (NO ₃ -N)	EPA 9056	IC
Nitrite (NO ₂ -N)	EPA 9056	IC
Organic (TKN-NH ₃ -N)	N/A	Calculation
Total (TKN+NO ₃ -N+NO ₂ -N)	N/A	Calculation
Total Kjeldahl	EPA 351.1	Colorimetric
Oil and grease		
Soxhlet	EPA 413.1M	Gravimetric

Analytical Procedures

TABLE 9-3 Specific Analytical Solid Waste / Hazardous Waste Methods

Parameter	Method	Description
General Inorganic Analyses continued		
pH	EPA 9045	ISE
Phosphorous		
Phosphate (PO ₄)	EPA 9056	IC
Total (P)	See Trace Metals	
Sulfate (SO ₄)	EPA 9056	IC
Sulfide (H ₂ S)	EPA 376.2	Colorimetric
Hazardous Waste Characterization Analyses		
Corrosivity (pH)		
Aqueous sample	EPA 9040	ISE
Nonaqueous sample	EPA 9045	ISE
Ignitability		
Aqueous (Flashpoint)	EPA 1010	Flashpoint
Nonaqueous (Flammability)	EPA 1020	Flashpoint
Reactivity	SW-846 Ch 8	Observations
Reaction with water		
Reaction with dilute acid		
Reaction with dilute base		
Reaction with oxidizing agent		
Reaction with reducing agent		
Generation	SW-846 Ch 7	Screens
Sulfide		
Cyanide		
Trace Metals		
Sample Preparation - TTLC	EPA 3050	Digestion
Sample Preparation - STLC	Title 22	Extraction
Sample Preparation - EP TOX	EPA 1310	Extraction
Sample Preparation - TCLP	EPA 1311	Extraction
Aluminum (Al)	EPA 6010	ICP
Aluminum (Al)	EPA 6020	ICP/MS
Antimony (Sb)	EPA 7041	Furnace Atomic Absorption
Antimony (Sb)	EPA 6020	ICP/MS
Arsenic (As)	EPA 7060	Furnace Atomic Absorption
Arsenic (As)	EPA 6020	ICP/MS
Barium (Ba)	EPA 6010	ICP
Barium (Ba)	EPA 6020	ICP/MS
Beryllium (Be)	EPA 6010	ICP
Beryllium (Be)	EPA 6020	ICP/MS
Boron (B)	EPA 6010	ICP
Boron (B)	EPA 6020	ICP/MS
Cadmium (Cd)	EPA 6010	ICP
Cadmium (Cd)	EPA 6020	ICP/MS
Calcium (Ca)	EPA 6010	ICP
Chromium (Cr)	EPA 6010	ICP
Chromium (Cr)	EPA 6010	ICP/MS
Chromium VI (Cr+6)	EPA 7196	Colorimetric

Analytical Procedures

TABLE 9-3 Specific Analytical Solid Waste / Hazardous Waste Methods

Parameter	Method	Description
Trace Metals Analyses continued		
Cobalt (Co)	EPA 6010	ICP
Cobalt (Co)	EPA 6020	ICP/MS
Copper (Cu)	EPA 6010	ICP
Copper (Cu)	EPA 6020	ICP/MS
Gold (Au)	EPA 231.1	Flame Atomic Absorption
Iron (Fe)	EPA 6010	ICP
Lead (Pb)	EPA 7420	Flame Atomic Absorption
Lead (Pb)	EPA 6020	ICP/MS
Lithium (Li)	EPA 7430	Flame Atomic Absorption
Magnesium (Mg)	EPA 6010	ICP
Manganese (Mn)	EPA 6010	ICP
Manganese (Mn)	EPA 6020	ICP/MS
Mercury (Hg)	EPA 7470	Cold Vapor Atomic Absorption
Molybdenum (Mo)	EPA 6010	ICP
Molybdenum (Mo)	EPA 6020	ICP/MS
Nickel (Ni)	EPA 6010	ICP
Nickel (Ni)	EPA 6020	ICP/MS
Phosphorous (P)	EPA 6010	ICP
Potassium (K)	EPA 6010	ICP
Selenium (Se)	EPA 7741	Furnace Atomic Absorption
Selenium (Se)	EPA 6020	ICP/MS
Silver (Ag)	EPA 6010	ICP
Silver (Ag)	EPA 6020	ICP/MS
Sodium (Na)	EPA 6010	ICP
Strontium (Sr)	EPA 6010	ICP
Thallium (Tl)	EPA 7841	Furnace Atomic Absorption
Thallium (Tl)	EPA 6020	ICP/MS
Tin (Sn)	EPA 6010	ICP
Titanium (Ti)	EPA 6010	ICP
Uranium (U)	EPA 6010	ICP
Vanadium (V)	EPA 6010	ICP
Zinc (Zn)	EPA 6010	ICP
Zinc (Zn)	EPA 6020	ICP/MS

Analytical Procedures

TABLE 9-3 Specific Analytical Solid Waste / Hazardous Waste Methods

Parameter	Method	Description
Radio Chemical Analyses		
Gross Alpha	EPA 900.0	Proportional counter
Gross Beta	EPA 900.0	Proportional counter
Gross Alpha & Beta	EPA 900.0	Proportional counter
Gamma Emitters	EPA 901.1	HPGe, gamma spectroscopy
Total Radium*	EPA 900.1	Isolation, Proportional Counter
Radium 226	EPA 903.1	Radon bubbler, Lucas cell scintillation
Radium 228	EPA 904.0	Isolation, Proportional Counter
Uranium	EPA 908.0	Isolation, proportional counter
Tritium	EPA 906.0	Distillation, liquid scintillation
Radon	EPA 913.0	Liquid scintillation

* Can be reported as Radium 226 if less than 3 pCi/liter.

Analytical Procedures

TABLE 9-4 Specific Analytical Ambient Air / Air Pollution Methods

Parameter	Method	Description
Volatile Organics	TO-14	GC/MS
BTEX/TPH	TO-14 (mod)	GC/MS
Total Non-methane hydrocarbons	TO-14 (mod)	GC/MS
Sulfur compounds	TO-14 (mod)	GC/MS
Light Hydrocarbons (C1-C6)	TO-3 (mod)	GC/FID
Methane	3810/5020	GC/FID
Fixed Gases	ASTM 1945	GC/TCD
Hydrogen Sulfide	-	Gold Film

Data Reduction, Validation, and Reporting

The process of transforming raw analytical data into a finished report involves steps which are generally grouped into the categories of data reduction, data validation, and reporting. It involves mathematical modeling of the standard calibration curves, statistical analysis of the acquired data, calculations to account for preparation steps and dilutions, verification of adherence to quality assurance procedures, and the generation of hardcopy output.

10.1 Data Reduction

At FGL Environmental the analyst has the primary responsibility for reducing raw data. This process consists primarily of converting raw data into final reportable values by comparing individual sample results against those obtained for calibration purposes then accounting for any dilutions or concentration.

For each method, all raw data results are recorded on method specific forms or in a standardized output from each of the various instruments. Details on procedures for data reduction may be found in the laboratory SOP for each method.

10.2 Data Validation

Upon completion of each analytical run, the analyst enters or transfers the data to LIMS. The analytical raw data and LIMS generated QC summary sheets are validated by the laboratory supervisor or a backup peer analyst. They verify that all quality control parameters meet the data quality objectives and also review the analytical data for calculation errors and inconsistencies. When data quality objectives are not met the deficiency is investigated and the samples are rerun or an explanation is provided.

10.3 Data Review and Reporting Policy

The raw data review includes all documentation associated with the samples, including chromatograms, instrument run logs, digestion logs, and other instrument printouts. Upon approval by the analyst or supervisor, the analytical results for the run are transferred to a results database for compiling with other data for that sample. When all results for a sample have been entered, an on screen report is generated for review and validation by the supervisor. Upon approval by the supervisor sample results are then released for final hardcopy reporting, which is forwarded to the client. Quality assurance reports are also generated at this step. The final reports are reviewed before signing by both the department supervisor and laboratory director. Quality assurance reports are reviewed by the quality assurance director or officer. Invoices are also reviewed and initialed by the project manager or department supervisor.

Data review steps include the following:

- 1) All data packages are reviewed by a second analyst or the supervisor. The QC batch report and analytical run sheets (if applicable) must be initialed by the reviewer.
- 2) All supervisors must review the data released for reporting.
- 3) Analysis reports are printed and again reviewed by the supervisor and lab director and signed by each upon approval.
- 4) Quality Control reports are printed and are reviewed and signed by the quality assurance director or officer.
- 5) Invoices are reviewed and initialed by the project manager or department supervisor.

Data Reduction, Validation and Reporting

10.4 Data Storage

FGL Environmental maintains report files and the supporting raw data for the current and previous year on the premises. Reports and raw data are maintained for a total of ten years in the secured data storage facility.

Internal Quality Control Checks

An internal quality control program requires a set of routine internal procedures for assuring that the data generated from a measurement system meets prescribed criteria for data quality. An effective internal QC program must be capable of measuring and controlling the quality of the data, in terms of precision, accuracy, and completeness (see sections 5 and 14 for these details).

This section identifies QC protocols associated with analytical procedures. Tables 11-1 - 11-4 are general outlines of quality control parameters monitored for each procedure. Included are general quality control measures as well as specific quality control checks which provide continual control and assessment of data quality. Figures 11-1 through 11-3 are examples of FGL Control Charts. FGL uses continuing calibration verifications (CCV) and initial calibration verification (ICV) for instrument quality control. The laboratory control sample (LCS) is used for sample preparation quality control. The CCV standard only verifies continuing calibration. The ICV standard is used to independently verify the calibration and may take the place of CCV when used on a continuing basis during analysis. The LCS may take the place of both ICV and CCV when prepared independently and used on a continuing basis during analysis.

11.1 Quality Control Parameters

11.1.1 Initial Demonstration of Capability

Before analyzing samples, the laboratory must prove proficiency in the method by preparing a data package for certification. The laboratory normally provides the following information:

- 1) calibration data
- 2) calibration verification from an independent source
- 3) method detection limit data
- 4) detection limit verification data
- 5) accuracy and precision data

These must all be acceptable under the method QC criteria or, when requirements are not specified, reasonably meet good laboratory practices and Department of Health Services requirements.

11.1.2 Analysis Quality Controls

11.1.2.1 Instrument Blank

The instrument or calibration blank is used to calibrate the instrument. This blank contains the same reagents used in the standards and samples. However, the blank is prepared under controlled conditions and is not processed like all samples.

11.1.2.2 Initial Calibration Verification (ICV)

ICV is used as an independent verification of the calibration. EPA protocol recommends analysis of ICV for each analytical calibration. ICV samples are manufacturer or laboratory prepared from independent suitable reference standards. The ICV usually contains the analytes of interest at a concentration in the mid-calibration range. Method specific acceptance criteria are used when possible. When method specific criteria are unavailable, the recoveries are control charted to obtain acceptance limits.

Internal Quality Control Checks

11.1.2.3 Continuing Calibration Verification (CCV)

CCV is used to verify continuing calibration. Many EPA methods require analysis of CCV's on a per batch or per day basis. CCV samples are manufacturer or laboratory prepared from suitable reference standards. This standard may or may not be independent of the calibration stock standards. The CCV usually contains the analytes of interest at a concentration in the mid-calibration range. Method specific acceptance criteria are used when possible. When method specific criteria are unavailable the recoveries are control charted to obtain acceptance limits.

11.1.2.4 Internal Standards (IS)

An IS is a synthetic compound not occurring in an environmental sample but has chemical behavior similar to that of the target analytes. EPA protocol requires IS for specific methods on a per sample basis (including QC samples). The IS serves as a check on the analysis and corrects for instrumental drift or matrix effects. Method specific acceptance criteria are used when possible. When method specific criteria are unavailable the recoveries are control charted to obtain acceptance limits.

11.1.3 Method Quality Controls

11.1.3.1 Method Blank

The method blank is used to ensure that any positive results were not because of reagent or labware contamination. Before analyzing any samples, the analyst must demonstrate through the analysis of a method blank, that all glassware and reagents are free of contaminants. Each time a set of samples is extracted, a method blank must be processed to check for laboratory contamination. The blank samples should be carried through all stages of the sample preparation and analysis. Lack of contamination is demonstrated if all target analytes with the exception of common laboratory reagents are below their DLRs.

11.1.3.2 Field Blank

The field blank is used to ensure that any positive results were not because of contamination occurring during sampling. The field blank samples should be carried through all stages of the sample preparation and analysis. Lack of contamination is demonstrated if all target analytes with the exception of common laboratory reagents are below their DLRs.

11.1.3.3 Travel Blank

The travel blank is used to ensure that any positive results were not because of contamination occurring during shipping and handling of the samples. The travel blank samples should be carried through all stages of the sample preparation and analysis. Lack of contamination is demonstrated if all target analytes with the exception of common laboratory reagents are below their DLRs.

11.1.3.4 Laboratory Control Sample (LCS)

The LCS is used to verify overall accuracy of the method. EPA protocol requires analysis of an LCS for each analytical batch when appropriate. The LCS consists of either a control matrix spiked with analytes representative of the target analytes or a certified reference material. Whenever possible, the LCS contains the analyte of interest at a concentration in the mid-calibration range. This standard may or may not be independent of the calibration stock standards. Initially method specific acceptance criteria are used. Eventually, or when method specific criteria are unavailable, the recoveries are control charted to obtain acceptance limits.

Internal Quality Control Checks

11.1.3.5 Surrogate Spikes

Surrogate spikes serve as a check on the extraction process where extraction is a necessary part of the analytical procedure. When surrogate recovery is within limits it indicates that the extraction was complete. A surrogate is a compound not expected to occur in an environmental sample but has chemical behavior similar to that of the target analytes. EPA protocol requires surrogate spikes for specific methods on a per sample basis (including QC samples). Initially method specific acceptance criteria are used. Eventually, or when method specific criteria are unavailable, the recoveries are control charted to obtain acceptance limits.

11.1.3.6 Matrix Spike/Matrix Spike Duplicates (MS/MSD)

The MS/MSD is used to verify matrix specific precision and accuracy. EPA protocol normally requires analysis of MS/MSD samples for each analytical batch or matrix type. The MS/MSD spikes are manufacturer or laboratory prepared from suitable reference standards. This standard may or may not be independent of the calibration stock standards. The matrix spike recovery and relative percent difference (RPD) acceptance criteria are shown in Section 5. When matrix spike results fall outside limits published in the respective methods, The LCS is used to verify method control. If spike recoveries are outside normal limits due to matrix problems, the data should be reported noting matrix interference. The spike recovery and RPD acceptance limits are test specific and are control charted.

11.1.3.7 Duplicates

Duplicates are used to verify matrix specific precision. EPA protocol normally requires analysis of duplicate samples for each analytical batch or matrix type. The relative percent difference (RPD) calculated from duplicate analyses provide an assessment of precision. The RPD acceptance limits are test specific and are control charted.

11.1.4 Radiochemical Specific Quality Controls

11.1.4.1 Efficiency vs. Dissolved Solids Chart

Dissolved solids (TDS) mask or decrease the radiation picked in the proportional counters. For each instrument an efficiency vs. solids chart must be generated as part of the initial demonstration of capability. In addition, whenever an instrument is maintained or repaired (i.e. a counting wire replaced) a new efficiency vs. TDS chart must be generated. Samples containing solids such that the efficiency of a counter could drop below ten percent must be reprepared using a smaller aliquot so that the solids give acceptable counting efficiency. Whenever possible an electrical conductivity measurement is used to estimate TDS and sample aliquots.

11.1.4.2 Background

Background samples are run daily, prior to sample analysis. However, monthly average may be used for calculation purposes. If a run background is used for sample calculation the background must be within 2 standard deviations of the monthly average to be acceptable.

11.1.4.3 Minimum Detectable Activity (MDA)

MDA's are calculated every six months. This data is used to determine if a sample is not detectable. EPA guidelines for sensitivity are followed for each isotope. MDA's can be calculated on per sample basis. Background samples are run daily, prior to sample analysis. However, monthly average may be used for calculation purposes.

Internal Quality Control

Table 11-1 Quality Controls for Drinking Water Methods

TEST	INST BLANK	METHOD BLANK	CCV	ICV	LCS	BS/BSD	MS/MSD	DUP	SURR	I.S.
Semivolatile Organics										
EPA 501.2	Batch	Batch		Batch	Batch					
EPA 504	Batch	Batch		Batch	Batch					
EPA 505	Batch	Batch		Batch	Batch					
EPA 507	Batch	Batch		Batch	Batch		Sample			
EPA 508	Batch	Batch		Batch	Batch		Sample			
EPA 508A	Batch	Batch		Batch	Batch					
EPA 510	Batch	Batch		Batch	Batch					
EPA 515.1	Batch	Batch		Batch	Batch		Sample			
EPA 525	Batch	Batch		Batch	Batch		Sample	Sample		
EPA 531	Batch	Batch		Batch	Batch		Sample			
EPA 547	Batch	Batch		Batch	Batch					
EPA 548	Batch	Batch		Batch	Batch		Sample			
EPA 549	Batch	Batch		Batch	Batch					
EPA 550.1	Batch	Batch		Batch	Batch		Sample			
EPA 552	Batch	Batch		Batch	Batch		Sample			
TOC	Batch		Batch		Batch					
TOX	Batch		Batch		Batch					
Volatile Organics										
EPA 502.2	Batch		Batch		Batch		Sample	Sample		
EPA 524.2	Batch		Batch		Batch		Sample	Sample		
Inorganic Chemicals										
Alkalinity			Batch			Batch				
Ammonia	Batch		Batch		Batch					
BOD	Batch			Batch		Batch				
Carbon Dioxide						Batch				
COD	Daily			Batch	Batch					
COD, % Transmittance	Daily			Batch	Batch					
Cl Res., colorimetric	Daily	Batch		Batch			Batch			
Cl Res., titrimetric				Batch			Batch			

Internal Quality Control

Table 11-1 Quality Controls for Drinking Water Methods

TEST	INST BLANK	METHOD BLANK	CCV	ICV	LCS	BS/BSD	MS/MSD	DUP	SURR	I.S.
Inorganic Chemical continued										
Cyanide, Free	Batch		Batch		Batch					
Cyanide, Total	Batch	Batch	Batch		Batch	Batch				
E.C.			Batch			Batch				
Fluoride (Distillation)		Batch	Batch		Batch	Batch				
Fluoride	Batch		Batch		Batch					
General Physical										
Ignitability			Batch			Batch				
Ion Chromatography	Batch		Batch		Batch					
MBAS Extraction	Batch			Batch	Batch					
MBAS Screen							Batch			
Moisture, percent							Batch			
Oxygen, Dissolved							Batch			
Nitrate - Technicon	Batch		Batch		Batch					
Nitrite - Technicon	Batch		Batch		Batch					
Oil & Grease, Pet	Batch			Batch	Batch					
Oil & Grease, Soxhlet	Batch			Batch	Batch					
Oil & Grease	Batch			Batch	Batch					
pH					Batch					
pH, Adjustment							Batch	Batch		
Phenols	Batch	Batch		Batch	Batch					
Phosphorous, Total	Batch	Batch		Batch	Batch					
Reactivity, Generation							Batch			
Reactivity							Batch			
Solids, Fixed	Batch			Batch		Batch				
Solids, Settleable										
Solids, Total	Batch			Batch		Batch				
Solids, T. Dissolved	Batch			Batch		Batch				
Solids, T. Suspended	Batch			Batch		Batch				
Solids, Volatile	Batch				Batch					
Solids, V. Suspended	Batch				Batch					
Sulfide, Dissolved							Batch			

Internal Quality Control

Table 11-1 Quality Controls for Drinking Water Methods

TEST	INST BLANK	METHOD BLANK	CCV	ICV	LCS	BS/BSD	MS/MSD	DUP	SURR	I.S.
Inorganic Chemical continued										
Sulfide, Total								Batch		
Sulfite								Batch		
TKN	Batch				Batch		Batch			
Tannin & Lignin	Batch				Batch		Batch			
Trace Metals										
Cr VI	Batch		Batch		Batch		Batch			
FAA	Batch		Batch				Batch			
GFAA	Batch		Batch				Batch			
ICP	Batch		Batch				Batch			
ICP/MS	Batch		Batch				Batch			Sample
Hg - CVAA	Batch		Batch		Batch		Batch			
Radiochemistry										
Gross A & B		Batch						Batch		
Gamma		Batch						Batch		
Nuclide Screen		Batch				Batch				
Radium 226		Batch					Batch			
Radium 228		Batch					Batch			
Radium 226 & 228		Batch				Batch				
Radon		Batch						Batch		
Strontium 90		Batch					Batch			
Tritium		Batch				Batch				
Uranium		Batch					Batch			

Internal Quality Control

Table 11-2 Quality Controls for Wastewater / Hazardous Waste Liquid Methods

TEST	INST BLANK	METHOD BLANK	CCV	ICV	LCS	BS/BSD	MS/MSD	DUP	SURR	I.S.
Semivolatile Organics										
EPA 3510				Batch			Batch	Batch		
EPA 3520				Batch			Batch	Batch		
EPA 3540				Batch			Batch	Batch		
EPA 3550				Batch			Batch	Batch		
EPA 3580				Batch			Batch			Batch
TCLP				Batch						Batch
EPA 8015	Batch			Batch						
EPA 8015M (Purgeable)	Batch			Batch						
EPA 8015M (Extract)	Batch			Batch						
EPA 604/8040	Batch			Batch						Sample
EPA 608/8080	Batch			Batch					Sample	
EPA 610/8310	Batch			Batch						
EPA 614/8140	Batch			Batch						Sample
EPA 615/8150	Batch			Batch						
EPA 625/8270	Batch			Batch						Sample
EPA 632	Batch			Batch						
TOC	Batch			Batch			Batch			
TOX	Batch			Batch			Batch			
TPH by IR	Batch	Batch			Batch	Batch				
Volatile Organics										
EPA 601/8010	Batch			Batch			Batch		Sample	Sample
EPA 602/8020	Batch			Batch			Batch		Sample	
EPA 624/8240	Batch			Batch			Batch		Sample	Sample
Inorganic Chemicals										
Alkalinity			Batch				Batch			
Ammonia	Batch			Batch			Batch			
BOD	Batch				Batch			Batch		
Carbon Dioxide										Batch
COD		Daily				Batch	Batch			

Internal Quality Control

Table 11-2 Quality Controls for Wastewater / Hazardous Waste Liquid Methods

TEST	INST BLANK	METHOD BLANK	CCV	ICV	LCS	BS/BSD	MS/MSD	DUP	SURR	I.S.
Inorganic Chemicals continued										
COD, % Transmittance	Daily				Batch	Batch				
Cl Res., colorimetric	Batch			Batch				Batch		
Cl Res., titrimetric					Batch				Batch	
Cyanide, Free	Batch			Batch			Batch			
Cyanide, Total	Batch	Batch	Batch		Batch	Batch				
E.C.			Batch				Batch			
Fluoride (Distillation)			Batch	Batch			Batch	Batch		
Fluoride	Batch			Batch			Batch			
Gen. Physical										Batch
Ignitability					Batch					Batch
Ion Chromatography	Batch			Batch			Batch			
MBAS Extraction	Batch				Batch	Batch				
MBAS Screen									Batch	
Moisture, percent										Batch
Oxygen, Dissolved									Batch	
Nitrate - Technicon	Batch			Batch			Batch			
Nitrite - Technicon	Batch			Batch			Batch			
Oil & Grease, Pet	Batch				Batch	Batch				
Oil & Grease, Sox	Batch				Batch	Batch				
Oil & Grease	Batch				Batch	Batch				
pH						Batch				Batch
pH, Adjustment										Batch
Phenols	Batch	Batch			Batch	Batch				
Phosphorus, Total	Batch	Batch			Batch	Batch				
Reactivity, Generation									Batch	
Reactivity										Batch
Solids, Fixed	Batch				Batch			Batch		
Solids, Settleable										
Solids, Total	Batch				Batch			Batch		
Solids, T. Dissolved	Batch				Batch			Batch		
Solids, T. Suspended	Batch				Batch			Batch		

Internal Quality Control

Table 11-2 Quality Controls for Wastewater / Hazardous Waste Liquid Methods

TEST	INST BLANK	METHOD BLANK	CCV	ICV	LCS	BS/BSD	MS/MSD	DUP	SURR	I.S.
Inorganic Chemicals continued										
Solids, Volatile	Batch						Batch			
Solids, V. Suspended	Batch						Batch			
Sulfide, Diss										Batch
Sulfide, Total										Batch
Sulfite										Batch
TKN	Batch				Batch	Batch				
Tannin & Lignin	Batch				Batch	Batch				
Trace Metals										
3015			Batch			Batch	Batch			
STLC				Batch						Batch
TCLP				Batch			Batch	Batch		
Cr VI	Batch	Batch			Batch		Batch			
FAA	Batch			Batch						
GFAA	Batch			Batch						
ICP	Batch			Batch						
ICP/MS	Batch			Batch						Sample
Hg - CVAA	Batch			Batch						
Radiochemistry										
Gross A & B	Batch					Batch				
Gamma		Batch						Batch		
Nuclide Screen		Batch				Batch				
Radium 226		Batch					Batch			
Radium 228		Batch					Batch			
Radon		Batch						Batch		
Radium 226 & 228			Batch				Batch			
Strontium 90		Batch				Batch				
Tritium		Batch				Batch				
Uranium		Batch				Batch				

Internal Quality Control

Table 11-3 Quality Controls for Solid Waste / Hazardous Waste Methods

TEST	INST BLANK	METHOD BLANK	CCV	ICV	LCS	BS/BSD	MS/MSD	DUP	SURR	I.S.
Semivolatile Organics										
EPA 3510				Batch			Batch	Batch		
EPA 3520				Batch			Batch	Batch		
EPA 3540				Batch			Batch	Batch		
EPA 3550				Batch			Batch	Batch		
EPA 3580				Batch			Batch			Batch
TCLP				Batch						Batch
EPA 8015	Batch			Batch						
EPA 8015M (Diesel)	Batch			Batch						
EPA 8015M (Gas)	Batch			Batch						Sample
EPA 8040	Batch			Batch						Sample
EPA 8080	Batch			Batch						
EPA 8140	Batch			Batch						Sample
EPA 8150	Batch			Batch						
EPA 8310	Batch			Batch						
EPA 632	Batch			Batch						
EPA 8270	Batch			Batch						
TOC	Batch			Batch			Batch			
TOX	Batch			Batch			Batch			
TPH by IR	Batch	Batch		Batch		Batch				
Volatile Organics										
TCLP				Batch						Batch
EPA 601/8010	Batch			Batch			Batch		Sample	Sample
EPA 602/8020	Batch			Batch			Batch		Sample	
EPA 624/8240	Batch			Batch			Batch		Sample	Sample
EPA 8260	Batch			Batch			Batch		Sample	Sample

Internal Quality Control

Table 11-3 Quality Controls for Solid Waste / Hazardous Waste Methods

TEST	INST BLANK	METHOD BLANK	CCV	ICV	LCS	BS/BSD	MS/MSD	DUP	SURR	I.S.
Solids Inorganic Chemicals										
Ammonia	Batch				Batch	Batch				
Corrosivity (pH)					Batch				Batch	
Cyanide, Total	Batch	Batch	Batch		Batch		Batch			
E.C.			Batch				Batch			
Fluoride (Distillation)			Batch	Batch			Batch	Batch		
Ignitability					Batch					Batch
Ion Chromatography	Batch				Batch	Batch				
Moisture, percent										Batch
Nitrate - Technicon	Batch				Batch	Batch				
Nitrite - Technicon	Batch				Batch	Batch				
Oil & Grease, Sox	Batch				Batch	Batch				
Oil & Grease	Batch				Batch	Batch				
pH					Batch					Batch
Phenols	Batch	Batch			Batch	Batch				
Phosphorus (See Trace metals - ICP)										
Reactivity, Generation									Batch	
Reactivity									Batch	Batch
Solids, Percent										
Sulfide, Total										Batch
TKN	Batch				Batch	Batch	Batch			
Trace Metals										
3050			Batch			Batch	Batch			
STLC				Batch						Batch
TCLP				Batch				Batch		
Cr VI	Batch	Batch			Batch		Batch			
FAA	Batch			Batch						
GFAA	Batch			Batch						
ICP	Batch			Batch						
ICP/MS	Batch			Batch						Sample
Hg - CVAA	Batch			Batch						

Internal Quality Control

Table 11-3 Quality Controls for Solid Waste / Hazardous Waste Methods

TEST	INST BLANK	METHOD BLANK	CCV	ICV	LCS	BS/BSD	MS/MSD	DUP	SURR	I.S.
Radiochemistry										
Gross A & B		Batch			Batch					
Gamma		Batch				Batch				
Nuclide Screen		Batch			Batch					
Radium 226		Batch			Batch					
Radium 228		Batch			Batch					
Radium 226 & 228		Batch			Batch					
Radon		Batch				Batch				
Strontium 90		Batch			Batch					
Tritium		Batch			Batch					
Uranium		Batch			Batch					

Internal Quality Control

Table 11-4 Quality Controls for Ambient Air / Air Pollution Methods

TEST	INST BLANK	METHOD BLANK	CCV	ICV	LCS	BS/BSD	MS/MSD	DUP	SURR	I.S.
TO-14	Batch		Batch		Batch			Batch	Sample	Sample
TO-3 (modified)			Batch		Batch			Batch		
Fixed Gases			Batch		Batch			Batch		
Total Pet. Hydrocarbons	Batch		Batch		Batch			Batch	Sample	Sample
Hydrogen Sulfide	Batch							Batch		

Internal Quality Control Checks

Figure 11-1 FGL Control Chart for LCS


This page intentionally left blank for figures on the next 2 pages.

QALCS-LBW

FGL ENVIRONMENTAL TREND CONTROL CHART

300.0 Anions for CL

09/23/93



△/■ => Matrix Spike / Dup

Reporting Limits : AR % 98 - 115 MAV %

on 9/23/93 by: Q / 10/18/93 EA

Handwritten signature: KRW

QALCS-LBW

FGL ENVIRONMENTAL TREND CONTROL CHART

300.0 Anions for CL

09/23/93

BATCH ID	DATE COMPLETED	Theo. Conc.	MS %	MSD %	AR %	See Notes
09/17/93:B	09/17/93	213	105	75-125		
09/17/93:A	09/17/93	213	101	75-125		
09/16/93:C	09/16/93	213	110	75-125		
09/16/93:B	09/16/93	213	109	75-125		
09/16/93:A	09/16/93	213	105	75-125	1	
09/15/93:B	09/15/93	213	108	75-125		
09/15/93:A	09/15/93	213	105	75-125		
09/13/93:B	09/13/93	213	104	75-125		
09/13/93:A	09/13/93	213	106	75-125		
09/10/93:D	09/10/93	213	110	75-125		
09/10/93:C	09/10/93	213	108	75-125		
09/10/93:B	09/10/93	213	107	75-125		
09/10/93:A	09/10/93	213	106	75-125		
09/08/93:C	09/08/93	213	108	75-125		
09/08/93:B	09/08/93	213	106	75-125		
09/08/93:A	09/08/93	213	105	75-125		
09/03/93:C	09/03/93	213	105	75-125		
09/03/93:A	09/03/93	213	102	75-125		
09/02/93:B	09/02/93	213	105	75-125		
09/02/93:A	09/02/93	213	104	75-125		
09/01/93:C	09/01/93	213	110	75-125		
09/01/93:B	09/01/93	213	107	75-125		
09/01/93:A	09/01/93	213	95.2	75-125		
08/30/93:B	08/30/93	213	112	75-125		
08/30/93:A	08/30/93	213	109	75-125		
08/27/93:F	08/27/93	213	121	75-125		
08/27/93:C	08/27/93	213	109	75-125		
08/27/93:B	08/27/93	213	108	75-125		
08/27/93:A	08/27/93	213	106	75-125		
08/26/93:E	08/26/93	213	108	75-125		

Internal Quality Control Checks

Figure 11-2 FGL Control Chart for MS/MSD and RPD


This page intentionally left blank for figures on the next 2 pages.

QAMS-WW

FGL ENVIRONMENTAL TREND CONTROL CHART

300.0 Anions for CL

09/23/93



△/■ => Matrix Spike / Dup

↔ => % Difference

Reporting Limits : AR % MAV %
54 - 150 7.9 on 9/23/93 by: CS / 10/18/93 JA

OK
KRW

QAMS-WW

FGL ENVIRONMENTAL TREND CONTROL CHART

300.0 Anions for CL

09/23/93

BATCH ID	DATE COMPLETED	Theo. Conc.	MS %	AR %	DIFF. %	MAV %	See Notes
09/17/93:B	09/17/93	100	98.9	101	75-125	0.6	20.0 10
09/16/93:C	09/16/93	40.0	96.9	99.3	75-125	0.5	20.0
09/16/93:B	09/16/93	100	154	151	75-125	1.2	20.0 *
09/15/93:B	09/15/93	145	180	180	75-125	0.1	20.0 *
09/13/93:B	09/13/93	100	92.0	120	75-125	13.4	20.0 *
09/10/93:D	09/10/93	100	110	116	75-125	2.4	20.0
09/10/93:C	09/10/93	200	98.9	103	75-125	1.6	20.0
09/10/93:B	09/10/93	100	106	109	75-125	1.6	20.0
09/08/93:C	09/08/93	100	110	118	75-125	2.4	20.0 10
09/08/93:B	09/08/93	200	124	113	75-125	2.1	20.0
09/03/93:C	09/03/93	100	95.7	95.8	75-125	0.1	20.0
09/02/93:B	09/02/93	100	95.0	102	75-125	4.5	20.0
09/02/93:A	09/02/93	100	68.6	46.0	75-125	14.1	20.0 10
09/01/93:C	09/01/93	200	85.7	82.0	75-125	3.3	20.0 13
09/01/93:B	09/01/93	200	84.5	89.7	75-125	2.8	20.0
08/30/93:B	08/30/93	100	98.5	103	75-125	1.3	20.0
08/30/93:A	08/30/93	100	103	100	75-125	1.7	20.0
08/27/93:F	08/27/93	4000	45.7	38.0	75-125	2.0	20.0 10
08/27/93:C	08/27/93	100	107	106	75-125	0.4	20.0 10
08/26/93:E	08/26/93	200	112	104	75-125	3.2	20.0 10
08/26/93:C	08/26/93	40.0	98.9	100	75-125	0.8	20.0
08/24/93:E	08/24/93	50.0	109	111	75-125	1.3	20.0
08/24/93:D	08/24/93	625	97.2	95.3	75-125	1.9	20.0
08/24/93:C	08/24/93	250	106	106	75-125	0.6	20.0 13
08/24/93:B	08/24/93	250	109	107	75-125	1.2	20.0
08/20/93:F	08/20/93	50.0	77.9	80.3	75-125	1.0	20.0
08/18/93:E	08/18/93	250	83.8	86.4	75-125	1.5	20.0 13
08/18/93:D	08/18/93	100	99.5	99.7	75-125	0.1	20.0 10
08/18/93:C	08/18/93	100	101	94.7	75-125	3.0	20.0 10
08/18/93:B	08/18/93	40.0	102	103	75-125	0.5	20.0 13

1000

1000

1000

1000

Performance and System Audits

The Quality Assurance Director or Officer is responsible for internal system audits, coordinating all external audits and performance evaluation (PE) samples. In addition, the QA Director or Officer is responsible for maintaining state and agency certification.

12.1 System Audits

System audits are performed both by external agencies, and by the laboratory Quality Assurance officers. These audits check the overall laboratory "system", from login to delivery of the finished reports. The purpose of the audit is to verify and document compliance with the regulatory methods, our Standard Operating Procedures (SOPs) and client specific needs.

12.1.1 Internal System Audit Program

Internal system audits are conducted on a monthly basis. Several analytical methods are selected each month for vertical slice audits. Compliance with all the required QC is evaluated and indicated on the QA Audit form (document ID F2QA040.XXX for Santa Paula, figure 12-1, and F3QA040.XXX for Stockton). The findings from the audit are compiled in the monthly QA non-conformance summary report.

12.1.2 External System Audits

System audits are performed by outside government agencies such as the California Department of Health Services, Lawrence Livermore National Laboratory and the Army Corp of Engineers. Audits are also performed by private agencies such as Chemical Waste Management, Inc.

12.2 Performance Evaluation Samples

Performance evaluation audits are used to provide a direct evaluation of the ability of the analytical systems to generate data that is consistent with the laboratory's stated objectives for accuracy and precision. External PE samples are analyzed as part of the certification and approval process for various state and federal agencies, as well as for other organizations.

12.2.1 External Performance Evaluation Samples

Performance evaluation samples are analyzed for a number of outside agencies including:

- (1) USEPA semi-annual drinking water check samples (WS series)
- (2) USEPA semi-annual wastewater check samples (WP series)
- (3) USEPA annual wastewater check samples (DMR studies)
- (4) CA-DHS-ELAP semi-annual hazardouswaste check samples (HW studies)
- (5) EMSL, Las Vegas, radiochemistry check samples
- (6) DOE, Environmental Measurements Laboratory QA Program
- (7) DOE, Mixed Analyte Performance Evaluation Program (MAPEP)

12.3 Certifications, Accreditations and Agency Approvals

FGL Environmental participates in laboratory certification programs with California, and other states. A copy of the California Environmental Laboratory Accreditation Program (ELAP) certified analysis list may be found in Figures 12-2 and 12-3 for Santa Paula and Stockton Laboratories respectively. A copy of the Utah and Hawaii Department of Health certified analysis lists may be found in Figures 12-4 and 12-5 (respectively) for Santa Paula.

Performance and System Audits

Figure 12-1 FGL QA Audit Form

This page intentionally left blank for figures on the next 7 pages.

FGL - Santa Paula QA Audit Form

Date: _____

Inspector: _____

<u>Item</u>	<u>In Compliance?</u>	<u>Corrective Action</u>
Overall -		
Oven Temps	_____	_____
Ref. Temps	_____	_____
Balance Checks	_____	_____
Container Checks	_____	_____
QC SOPs	_____	_____

Comments: _____

Front Office Login -

Sample #s - _____

LIMS Logbook	_____	_____
File Tracking	_____	_____
Completeness	_____	_____
Chain of Custody	_____	_____
Report	_____	_____
Bill	_____	_____
Training	_____	_____
SOPs	_____	_____

Comments: _____

Bacteriology -

MUG Log (colilert)	_____	_____
MTF Log (D.W.)	_____	_____
Series Log (W.W.)	_____	_____
Plate Count Log	_____	_____
Client Notifications	_____	_____
Media Prep Log	_____	_____
Autoclave Temps	_____	_____
Water Suitability	_____	_____
Corrective Actions	_____	_____

Method Check

Method: _____ Sample #: _____ Date Started: _____
SOP _____
Analyst Training _____

Comments: _____

<u>Item</u>	<u>In Compliance?</u>	<u>Corrective Action</u>
Inorganic Wet Chemistry -		
Instrument Maintenance:		
Dionex DX-100	_____	_____
Dionex DX-300	_____	_____
P.E. Lambda 3	_____	_____
Turner Nepth.	_____	_____
Fisher pH/ISE	_____	_____
Orion E.C.	_____	_____
Orion BOD	_____	_____
Skalar BOD	_____	_____
Corrective Actions	_____	_____

Method Checks

Method: _____ Sample #: _____ Date Started: _____

Data Package		
Batch QC Report	_____	_____
Reviewed Report	_____	_____
Batch Sheet	_____	_____
Inst. Printout	_____	_____
SOP	_____	_____
Control Charts	_____	_____
MDL Study	_____	_____
Standard Tracking	_____	_____
Analyst Training	_____	_____

Method: _____ Sample #: _____ Date Started: _____

Data Package		
Batch QC Report	_____	_____
Reviewed Report	_____	_____
Batch Sheet	_____	_____
Inst. Printout	_____	_____
SOP	_____	_____
Control Charts	_____	_____
MDL Study	_____	_____
Standard Tracking	_____	_____
Analyst Training	_____	_____

Comments: _____

<u>Item</u>	<u>In Compliance?</u>	<u>Corrective Action</u>
-------------	-----------------------	--------------------------

Inorganic Trace Metals -

Instrument Maintenance:

P.E. 5000		
P.E. 5100		
TJA Atomscan 16		
TJA Trace Anal.		
Fisons PQ-II		
Leeman PS200		
HP-4500 ICP-MS		
Corrective Actions		

Method: _____ Sample #: _____ Date Started: _____

Data Package		
Batch QC Report		
Reviewed Report		
Batch Sheet		
Inst. Printout		
SOP		
Control Charts		
MDL Study		
Standard Tracking		
Analyst Training		

Comments: _____

Organics -

GC Lab -

Instrument Maintenance:

GC 2		
GC 3		
GC 4		
GC 5		
GC 7		
GC 8		
Hitachi HPLC		
HP HPLC		
IR		
Corrective Actions		

Comments: _____

<u>Item</u>	<u>In Compliance?</u>	<u>Corrective Action</u>
-------------	-----------------------	--------------------------

Method Check

Method: _____ Sample #: _____ Date Started: _____

Data Package

Batch QC Report

Reviewed Report

Batch Sheet

Inst. Printout

SOP

Control Charts

MDL Study

Standard Tracking

Analyst Training

Comments: _____

GC/MS Lab:

Instrument Maintenance:

GC 9

GC/MS 1

GC/MS 2

GC/MS 3

GC/MS 4

GC/MS 5

MCI TOX

Astro TOC

Corrective Actions

Method Check

Method: _____ Sample #: _____ Date Started: _____

Data Package

Batch QC Report

Reviewed Report

Batch Sheet

Inst. Printout

SOP

Control Charts

MDL Study

Standard Tracking

Analyst Training

Comments: _____

<u>Item</u>	<u>In Compliance?</u>	<u>Corrective Action</u>
Radiochemistry -		
Instrument Maintenance:		
Alpha 1	_____	_____
Alpha 2	_____	_____
Alpha 5	_____	_____
Alpha 6	_____	_____
Alpha 7	_____	_____
Alpha/Beta 3	_____	_____
Alpha/Beta 4	_____	_____
Alpha/Beta 8	_____	_____
Liquid Scintillation	_____	_____
Gamma Spec.	_____	_____
Alpha Spec.	_____	_____
Random Scint. Cntr	_____	_____
Corrective Actions	_____	_____
Method Check		
Method: _____	Sample #: _____	Date Started: _____
Data Package		
Batch QC Report	_____	_____
Reviewed Report	_____	_____
Batch Sheet	_____	_____
Inst. Printout	_____	_____
SOP	_____	_____
Control Charts	_____	_____
MDL Study	_____	_____
Standard Tracking	_____	_____
Analyst Training	_____	_____
Comments: _____		

<u>Item</u>	<u>In Compliance?</u>	<u>Corrective Action</u>
Agronomics Lab -		
Instrument Maintenance:		
Technicon - nitrate	_____	_____
Technicon - TKN	_____	_____
LECO	_____	_____
pH meter	_____	_____
E.C. meter	_____	_____
ARL 3410	_____	_____
Corrective Actions	_____	_____

Method Check

Method: _____	Sample #: _____	Date Started: _____
Data Package		
Batch QC Report	_____	_____
Reviewed Report	_____	_____
Batch Sheet	_____	_____
Inst. Printout	_____	_____
SOP	_____	_____
Control Charts	_____	_____
MDL Study	_____	_____
Standard Tracking	_____	_____
Analyst Training	_____	_____

Comments: _____

<u>Item</u>	<u>In Compliance?</u>	<u>Corrective Action</u>
Air Analysis Lab -		
Instrument Maintenance:		
SRI GC/TCD	_____	_____
SRI GC/FID	_____	_____
HP 5890 GC/FID	_____	_____
HP GC/MS #1	_____	_____
HP GC/MS #2	_____	_____
H ₂ S Analyzer	_____	_____
Corrective Actions	_____	_____

Method Check

Method: _____	Sample #: _____	Date Started: _____
Data Package		
Batch QC Report	_____	_____
Reviewed Report	_____	_____
Batch Sheet	_____	_____
Inst. Printout	_____	_____
SOP	_____	_____
Control Charts	_____	_____
MDL Study	_____	_____
Standard Tracking	_____	_____
Analyst Training	_____	_____

Comments: _____

Performance and System Audits

Figure 12-2 FGL Santa Paula - California ELAP Certification

This page intentionally left blank for figures on the next 5 pages.

ENVIRONMENTAL LABORATORY ACCREDITATION/REGISTRATION
List of Approved Fields of Testing and Analytes

FGL Environmental Laboratory
853 Corporation Street
Santa Paula, CA

TELEPHONE No: (805) 659-0910
CALIFORNIA COUNTY: Ventura

CERTIFICATE NUMBER: 1573
EXPIRATION DATE: 7/31/97

=====

1 Microbiology of Drinking Water and Wastewater (07-15-91)

1.1	Total Coliforms in Drinking Water by Multiple Tube Fermentation	Y
1.2	Fecal Coliforms/E. Coli in Drinking Water by MTF	Y
1.3	Total Coliforms in Drinking Water by Membrane Filter Technics	N
1.4	Fecal Coliforms/E. Coli in Drinking Water by Membrane Filter Technics	N
1.5	Total Coliforms and E. Coli in Drinking Water by MMO-MUG	Y
1.6	Total Coliforms in Drinking Water by Clark's Presence/Absence	N
1.7	Fecal Coliforms/E. Coli in Drinking Water by Clark's Presence/Absence	N
1.8	Heterotrophic Plate Count	Y
1.9	Total Coliforms in Wastewater by Multiple Tube Fermentation	Y
1.10	Fecal Coliforms in Wastewater by MTF	Y
1.11	Total Coliforms in Wastewater by Membrane Filter Technics	N
1.12	Fecal Coliforms in Wastewater by Membrane Filter Technics	N
1.13	Fecal Streptococci or Enterococci by Multiple Tube Technics	N
1.14	Fecal Streptococci or Enterococci by Membrane Filter Technics	N

2 Inorganic Chemistry and Physical Properties of Drinking Water excluding Toxic Chemical Elements (07-15-91)

2.1	Alkalinity	Y	2.12	Sulfate	Y
2.2	Calcium	Y	2.13	Total Filterable Residue	
2.3	Chloride	Y		and Conductivity	Y
2.4	Corrosivity	Y	2.14	Iron (Colorimetric Methods Only)	N
2.5	Fluoride	Y	2.15	Manganese (Colorimetric Methods Only)	N
2.6	Hardness	Y	2.16	Phosphate, ortho	Y
2.7	Magnesium	Y	2.17	Silica (Colorimetric Methods Only)	N
2.8	MBAS	Y	2.18	Cyanide	Y
2.9	Nitrate	Y			
2.10	Nitrite	Y			
2.11	Sodium	Y			

3 Analysis of Toxic Chemical Elements in Drinking Water (07-15-91)

3.1	Arsenic	Y	3.11	Silver	Y
3.2	Barium	Y	3.12	Zinc	Y
3.3	Cadmium	Y	3.13	Aluminum	Y
3.4	Chromium, total	Y	3.14	Asbestos	N
3.5	Copper	Y	3.15	EPA Method 200.7	Y
3.6	Iron	Y	3.16	EPA Method 200.8 (Unregulated Elements	
3.7	Lead	Y		and Lead Only)	Y
3.8	Manganese	Y	3.17	Antimony	Y
3.9	Mercury	Y	3.18	Beryllium	Y
3.10	Selenium	Y	3.19	Nickel	Y
			3.20	Thallium	Y

4 Organic Chemistry of Drinking Water (measurement by GC/MS combination) (07-15-91)

4.1	EPA Method 501.3	N
4.2	EPA Method 524.2	Y
4.3	EPA Method 525	Y
4.4	EPA Method 513	N

5 Organic Chemistry of Drinking Water (excluding measurements by GC/MS combination) (07-15-91)

5.1	EPA Method 501.1	N	5.16	EPA Method 548	Y
5.2	EPA Method 501.2	Y	5.17	EPA Method 549	Y
5.3	EPA Method 502.1	N	5.18	EPA Method 550	N
5.4	EPA Method 502.2	Y	5.19	EPA Method 550.1	N
5.5	EPA Method 503.1	N	5.20	EPA Method 551	Y
5.6	EPA Method 504	Y	5.21	EPA Method 552	Y
5.7	EPA Method 505	Y			
5.8	EPA Method 506	N			
5.9	EPA Method 507	Y			
5.10	EPA Method 508	Y			
5.11	EPA Method 508A	Y			
5.12	EPA Method 510.1	N			
5.13	EPA Method 515.1	Y			
5.14	EPA Method 531.1	Y			
5.15	EPA Method 547	Y			

CERTIFICATE NUMBER: 1573
EXPIRATION DATE: 7/31/97

6 Radiochemistry (07-15-91)

6.1	Gross Alpha and Beta Radiation -----	Y	6.11	Gross Alpha by Co-precipitation -----	Y
6.2	Total Radium -----	Y	6.12	Radium 228 -----	Y
6.3	Radium 226 -----	Y	6.13	Radioactive Iodine -----	N
6.4	Uranium -----	Y	6.14	Gross Alpha & Beta in Hazardous Wastes --	Y
6.5	Radon 222 -----	Y	6.15	Alpha Emitting Radium Isotopes in Haz. Wastes -----	Y
6.6	Radioactive Cesium -----	N	6.16	Radium 228 in Hazardous Wastes -----	Y
6.7	Iodine 131 -----	N			
6.8	Radioactive Strontium -----	Y			
6.9	Tritium -----	Y			
6.10	Gamma and Photon Emitters -----	Y			

7 Shellfish Sanitation (-----)

7.1	Shellfish meat Microbiology -----	N
7.2	Paralytic Shellfish Poison -----	N
7.3	Domoic Acid -----	N

8 Aquatic Toxicity Bioassays (-----)

8.1	Hazardous Waste Aquatic Toxicity Bioassay (Title 22, CCR, 66261.24(a)(6)) -----	N
8.2	Wastewater Testing According to Kopperdahl (1976) using Freshwater Fish. -----	N
8.3	Wastewater Testing According to EPA/600/4-85/013 using Freshwater and/or Marine Organisms -----	N
8.4	Wastewater Testing by EPA Method 1000.0 -----	N
8.5	Wastewater Testing by EPA Method 1002.0 -----	N
8.6	Wastewater Testing by EPA Method 1003.0 -----	N
8.7	Wastewater Testing by EPA Method 1006 -----	N
8.8	Wastewater Testing by EPA Method 1007 -----	N
8.9	Wastewater Testing by EPA Method 1009 -----	N
8.10	Wastewater Testing According to Anderson, et. al. (1990) using Giant Kelp (<i>Macrocystis pyrifera</i>) --	N
8.11	Wastewater Testing According to Anderson, et. al. (1990) using Red Abalone (<i>Haliotis rufescens</i>) ---	N
8.12	Wastewater Testing According to Dinnel and Stober (1987) using Purple Sea Urchin (<i>Strongylocentrotus purpuratus</i>) -----	N
8.13	Wastewater Testing According to Dinnel and Stober (1987) using Red Sea Urchin (<i>Strongylocentrotus franciscanus</i>) -----	N
8.14	Wastewater Testing According to Dinnel and Stober (1987) using Sand Dollar (<i>Pendraster excentricus</i>) -----	N
8.15	Wastewater Testing According to procedure E 724-89 (ASTM, 1989) using Pacific Oyster (<i>Crassostrea gigas</i>) -----	N
8.16	Wastewater Testing According to procedure E 724-89 (ASTM, 1989) using California Bay Mussel (<i>Mytilus edulis</i>) -----	N
8.17	Wastewater Testing According to Standard Methods (APHA, 1989) using an alga (<i>Skeletonema costatum</i>) -----	N
8.18	Wastewater Testing According to EPA/600/4-90/027 using Freshwater and/or Marine Organisms -----	N

9 Physical Properties Testing of Hazardous Waste (07-15-91)

9.1	Ignitability by Flashpoint determination (Title 22, CCR, 66261.21) -----	Y
9.2	Corrosivity - pH determination (Title 22, CCR, 66261.22) -----	Y
9.3	Corrosivity - Corrosivity towards steel (Title 22, CCR, 66261.22) -----	N
9.4	Reactivity (Title 22, CCR, 66261.23) -----	Y

10 Inorganic Chemistry and Toxic Chemical Elements of Hazardous Waste

10.1	Antimony 7040(-----) -----	N	10.7	Cobalt 7200(-----) -----	N
	7041(06-06-86) -----	Y		7201(-----) -----	N
10.2	Arsenic 7060(06-06-86) -----	Y	10.8	Copper 7210(-----) -----	N
	7061(-----) -----	N		7211(-----) -----	N
10.3	Barium 7080(-----) -----	N	10.9	Lead 7420(06-06-86) -----	Y
	7081(-----) -----	N		7421(-----) -----	N
10.4	Beryllium 7090(-----) -----	N	10.10	Mercury 7470(-----) -----	N
	7091(-----) -----	N		7471(11-30-93) -----	Y
10.5	Cadmium 7130(-----) -----	N	10.11	Molybdenum 7480(-----) -----	N
	7131(-----) -----	N		7481(-----) -----	N
10.6	Chromium, total 7190(-----) -----	N	10.12	Nickel 7520(-----) -----	N
	7191(-----) -----	N			

CERTIFICATE NUMBER: 1573
EXPIRATION DATE: 7/31/97

10.13	Selenium		
	7740(06-06-86)	-----	Y
	7741(-----)	-----	N
10.14	Silver		
	7760(06-06-86)	-----	Y
	7761(-----)	-----	N
10.15	Thallium		
	7840(-----)	-----	N
	7841(06-06-86)	-----	Y
10.16	Vanadium		
	7910(-----)	-----	N
	7911(-----)	-----	N
10.17	Zinc		
	7950(-----)	-----	N
	7951(-----)	-----	N
10.18	Chromium (VI)		
	7195(-----)	-----	N
	7196(06-06-86)	-----	Y
	7197(-----)	-----	N
	7198(-----)	-----	N
11	<u>Extraction Tests of Hazardous Waste (06-06-86)</u>		
11.1	California Waste Extraction Test (WET) (Title 22, CCR, 66261.100, Appendix 11)	-----	Y
11.2	Extraction Procedure Toxicity	-----	Y
11.3	Toxicity Characteristic Leaching Procedure (TCLP) All Classes	-----	Y
11.4	Toxicity Characteristic Leaching Procedure (TCLP) Inorganics Only	-----	N
11.5	Toxicity Characteristic Leaching Procedure (TCLP) Extractables Only	-----	N
11.6	Toxicity Characteristic Leaching Procedure (TCLP) Volatiles Only	-----	N
12	<u>Organic Chemistry of Hazardous Waste (measurement by GC/MS combination)</u>		
12.1	EPA Method 8240(02-05-87)	-----	Y
12.2	EPA Method 8250(-----)	-----	N
12.3	EPA method 8270(02-05-87)	-----	Y
12.4	EPA Method 8280(-----)	-----	N
12.5	EPA Method 8290(-----)	-----	N
12.6	EPA Method 8260(11-30-93)	-----	Y
13	<u>Organic Chemistry of Hazardous Waste (excluding measurements by GC/MS combination)</u>		
13.1	EPA Method 8010(01-24-96)	-----	Y
13.2	EPA Method 8015(01-09-90)	-----	Y
13.3	EPA Method 8020(06-06-86)	-----	Y
13.4	EPA Method 8030(-----)	-----	N
13.5	EPA Method 8040(-----)	-----	N
13.6	EPA Method 8060(08-31-95)	-----	Y
13.7	EPA Method 8080(06-06-86)	-----	Y
13.8	EPA Method 8090(-----)	-----	N
13.9	EPA Method 8100(-----)	-----	N
13.10	EPA Method 8120(-----)	-----	N
13.11	EPA Method 8140(06-06-86)	-----	Y
13.12	EPA Method 8150(06-06-86)	-----	Y
13.13	EPA Method 8310(05-27-92)	-----	Y
13.14	EPA Method 632 (07-15-91)	-----	Y
13.15	Total Petroleum Hydrocarbons (LUFT Manual) (06-06-86)	-----	Y
13.16	EPA Method 8011(11-08-87)	-----	Y
13.17	EPA Method 8021(-1-24-96)	-----	Y
13.18	EPA Method 8070(-----)	-----	N
13.19	EPA Method 8110(-----)	-----	N
13.20	EPA Method 8141(11-30-93)	-----	Y
13.21	EPA Method 8330(-----)	-----	N
14	<u>Bulk Asbestos Analysis (-----)</u>		
14.1	1% or Greater Asbestos Concentrations (Title 22, CCR, 66261.24(a)(2)(A))	-----	N
15	<u>Substances Regulated Under the California Safe Drinking Water and Toxic Enforcement Act (Proposition 65) and Not Included in Other Listed Groups.</u>		
16	<u>Wastewater Inorganic Chemistry, Nutrients and Demand (07-15-91)</u>		
16.1	Acidity	-----	Y
16.2	Alkalinity	-----	Y
16.3	Ammonia	-----	Y
16.4	Biochemical Oxygen Demand	-----	Y
16.5	Boron	-----	Y
16.6	Bromide	-----	Y
16.7	Calcium	-----	Y
16.8	cBOD	-----	N
16.9	Chemical Oxygen Demand	-----	Y
16.10	Chloride	-----	Y
16.11	Chlorine Residual, total	-----	Y
16.12	Cyanide	-----	Y
16.13	Cyanide amenable to Chlorination	-----	Y
16.14	Fluoride	-----	Y
16.15	Hardness	-----	Y
16.16	Kjeldahl Nitrogen	-----	Y
16.17	Magnesium	-----	Y
16.18	Nitrate	-----	Y
16.19	Nitrite	-----	Y
16.20	Oil and Grease	-----	Y
16.21	Organic Carbon	-----	Y
16.22	Oxygen, Dissolved	-----	Y

CERTIFICATE NUMBER: 1573
EXPIRATION DATE: 7/31/97

16.23	pH	Y	16.39	Surfactants (MBAS)	Y
16.24	Phenols	Y	16.40	Tannin and Lignin	Y
16.25	Phosphate, ortho-	Y	16.41	Turbidity	Y
16.26	Phosphorus, total	Y	16.42	Iron (Colorimetric Only)	N
16.27	Potassium	Y	16.43	Manganese (Colorimetric Only)	N
16.28	Residue, Total	Y	16.44	Total Recoverable	
16.29	Residue, Filterable (TDS)	Y		Petroleum Hydrocarbons	Y
16.30	Residue, Nonfilterable (TSS)	Y	16.45	Total Organic Halides	Y
16.31	Residue, Settleable (SS)	Y			
16.32	Residue, Volatile	Y			
16.33	Silica	Y			
16.34	Sodium	Y			
16.35	Specific Conductance	Y			
16.36	Sulfate	Y			
16.37	Sulfide (includes total & soluble)	Y			
16.38	Sulfite	Y			

17 Toxic Chemical Elements in Wastewater (07-15-91)

17.1	Aluminum	Y	17.18	Nickel	Y
17.2	Antimony	Y	17.19	Osmium	N
17.3	Arsenic	Y	17.20	Palladium	N
17.4	Barium	Y	17.21	Platinum	N
17.5	Beryllium	Y	17.22	Rhodium	N
17.6	Cadmium	Y	17.23	Ruthenium	N
17.7	Chromium (VI)	Y	17.24	Selenium	Y
17.8	Chromium, total	Y	17.25	Silver	Y
17.9	Cobalt	Y	17.26	Strontium	Y
17.10	Copper	Y	17.27	Thallium	Y
17.11	Gold	Y	17.28	Tin	Y
17.12	Iridium	N	17.29	Titanium	Y
17.13	Iron	Y	17.30	Vanadium	Y
17.14	Lead	Y	17.31	Zinc	Y
17.15	Manganese	Y	17.32	EPA Method 200.7	Y
17.16	Mercury	Y	17.33	EPA Method 200.8	Y
17.17	Molybdenum	Y	17.34	DCP	N
			17.35	Asbestos	N

18 Organic Chemistry of Wastewater (measurements by GC/MS combination (07-15-91))

18.1	EPA Method 624	Y
18.2	EPA Method 625	Y
18.3	EPA Method 1613	N
18.4	EPA Method 1625	N
18.5	EPA Method 613	N

19 Organic Chemistry of Wastewater (excluding measurements by GC/MS combination) (07-15-91)

19.1	EPA Method 601	Y	19.8	EPA Method 608	Y
19.2	EPA Method 602	Y	19.9	EPA Method 609	N
19.3	EPA Method 603	N	19.10	EPA Method 610	Y
19.4	EPA Method 604	N	19.11	EPA Method 611	N
19.5	EPA Method 605	N	19.12	EPA Method 632	Y
19.6	EPA Method 606	Y	19.13	EPA Method 619	N
19.7	EPA Method 607	N			

20 Inorganic Chemistry and Toxic Chemical Elements of Pesticide Residues in Food (-----)

20.1	Processed Foods by One of the Following Methods	
	Atomic Absorption Spectrophotometry	N
	Inductively Coupled Plasma Atomic Emission Spectrophotometry	N
	Inductively Coupled Plasma/Mass Spectrometry	N
	Colorimetry	N
20.2	Raw Commodities by One of the Following Methods	
	Atomic Absorption Spectrophotometry	N
	Inductively Coupled Plasma Atomic Emission Spectrophotometry	N
	Inductively Coupled Plasma/Mass Spectrometry	N
	Colorimetric	N
20.3	Dairy Products by One of the Following Methods	
	Atomic Absorption Spectrophotometry	N
	Inductively Coupled Plasma Atomic Emission Spectrophotometry	N
	Inductively Coupled Plasma/Mass Spectrometry	N
	Colorimetry	N

CERTIFICATE NUMBER: 1573
EXPIRATION DATE: 7/31/97

20.4	Feed Products by One of the Following Methods	
	Atomic Absorption Spectrophotometry	N
	Inductively Coupled Plasma Atomic Emission Spectrophotometry	N
	Inductively Coupled Plasma/Mass Spectrometry	N
	Colorimetry	N
21	<u>Organic Chemistry of Pesticide Residues in Food (measurements by GC/MS) (-----)</u>	
21.1	Gas Chromatographic/Mass Spectrometric Methods in Processed Foods	N
21.2	Gas Chromatographic/Mass Spectrometric Methods in Raw Commodities	N
21.3	Gas Chromatographic/Mass Spectrometric Methods in Dairy Products	N
21.4	Gas Chromatographic/Mass Spectrometric Methods in Feed Products	N
22	<u>Organic Chemistry of Pesticide Residues in Food (Excluding Measurement by GC/MS Combination) (-----)</u>	
22.1	Halogenated Compounds in Processed Foods by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.2	Organophosphorous Compounds in Processed Foods by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.3	Carbamates in Processed Foods by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.4	Halogenated Compounds in Raw Commodities by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.5	Organophosphorous Compounds in Raw Commodities by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.6	Carbamates in Raw Commodities by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.7	Halogenated Compounds in Dairy Products by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.8	Organophosphorous Compounds in Dairy Products by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.9	Carbamates in Dairy Products by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.10	Halogenated Compounds in Feed Products by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.11	Organophosphorous Compounds in Feed Products by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.12	Carbamates in Feed Products by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N

Performance and System Audits

Figure 12-3 FGL Stockton - California ELAP Certification

This page intentionally left blank for figures on the next 5 pages.

ENVIRONMENTAL LABORATORY ACCREDITATION/REGISTRATION
List of Approved Fields of Testing and Analytes

FGL Environmental
2500 Stagecoach Road
Stockton, CA

TELEPHONE No: (209) 942-0181
CALIFORNIA COUNTY: San Joaquin

CERTIFICATE NUMBER: 1563
EXPIRATION DATE: 07/31/97

<u>1 Microbiology of Drinking Water and Wastewater (07-03-91)</u>		
1.1	Total Coliforms in Drinking Water by Multiple Tube Fermentation	Y
1.2	Fecal Coliforms/E. Coli in Drinking Water by MTF	Y
1.3	Total Coliforms in Drinking Water by Membrane Filter Technics	N
1.4	Fecal Coliforms/E. Coli in Drinking Water by Membrane Filter Technics	N
1.5	Total Coliforms and E. Coli in Drinking Water by MMO-MUG	Y
1.6	Total Coliforms in Drinking Water by Clark's Presence/Absence	Y
1.7	Fecal Coliforms/E. Coli in Drinking Water by Clark's Presence/Absence	Y
1.8	Heterotrophic Plate Count	Y
1.9	Total Coliforms in Wastewater by Multiple Tube Fermentation	Y
1.10	Fecal Coliforms in Wastewater by MTF	Y
1.11	Total Coliforms in Wastewater by Membrane Filter Technics	N
1.12	Fecal Coliforms in Wastewater by Membrane Filter Technics	N
1.13	Fecal Streptococci or Enterococci by Multiple Tube Technics	N
1.14	Fecal Streptococci or Enterococci by Membrane Filter Technics	N
<u>2 Inorganic Chemistry and Physical Properties of Drinking Water excluding Toxic Chemical Elements (07-03-91)</u>		
2.1	Alkalinity	Y
2.2	Calcium	Y
2.3	Chloride	Y
2.4	Corrosivity	Y
2.5	Fluoride	Y
2.6	Hardness	Y
2.7	Magnesium	Y
2.8	MBAS	Y
2.9	Nitrate	Y
2.10	Nitrite	Y
2.11	Sodium	Y
2.12	Sulfate	Y
2.13	Total Filterable Residue and Conductivity	Y
2.14	Iron (Colorimetric Methods Only)	N
2.15	Manganese (Colorimetric Methods Only)	N
2.16	Phosphate, ortho	Y
2.17	Silica (Colorimetric Methods Only)	Y
2.18	Cyanide	Y
<u>3 Analysis of Toxic Chemical Elements in Drinking Water (07-03-91)</u>		
3.1	Arsenic	Y
3.2	Barium	Y
3.3	Cadmium	Y
3.4	Chromium, total	Y
3.5	Copper	Y
3.6	Iron	Y
3.7	Lead	Y
3.8	Manganese	Y
3.9	Mercury	Y
3.10	Selenium	Y
3.11	Silver	Y
3.12	Zinc	Y
3.13	Aluminum	Y
3.14	Asbestos	N
3.15	EPA Method 200.7	Y
3.16	EPA Method 200.8 (Unregulated Elements and Lead Only)	N
3.17	Antimony	Y
3.18	Beryllium	Y
3.19	Nickel	Y
3.20	Thallium	Y
<u>4 Organic Chemistry of Drinking Water (measurement by GC/MS combination) (07-03-91)</u>		
4.1	EPA Method 501.3	Y
4.2	EPA Method 524.2	Y
4.3	EPA Method 525	N
4.4	EPA Method 513	N
<u>5 Organic Chemistry of Drinking Water (excluding measurements by GC/MS combination) (07-03-91)</u>		
5.1	EPA Method 501.1	N
5.2	EPA Method 501.2	Y
5.3	EPA Method 502.1	N
5.4	EPA Method 502.2	Y
5.5	EPA Method 503.1	Y
5.6	EPA Method 504	Y
5.7	EPA Method 505	Y
5.8	EPA Method 506	N
5.9	EPA Method 507	N
5.10	EPA Method 508	N
5.11	EPA Method 508A	N
5.12	EPA Method 510.1	Y
5.13	EPA Method 515.1	Y
5.14	EPA Method 531.1	N
5.15	EPA Method 547	N
5.16	EPA Method 548	N
5.17	EPA Method 549	N
5.18	EPA Method 550	N
5.19	EPA Method 550.1	N
5.20	EPA Method 551	N
5.21	EPA Method 552	Y

CERTIFICATE NUMBER: 1563
EXPIRATION DATE: 07-31-97

6 Radiochemistry (-----)

6.1	Gross Alpha and Beta Radiation -----	N	6.11	Gross Alpha by Co-precipitation -----	N
6.2	Total Radium -----	N	6.12	Radium 228 -----	N
6.3	Radium 226 -----	N	6.13	Radioactive Iodine -----	N
6.4	Uranium -----	N	6.14	Gross Alpha & Beta in Hazardous Wastes --	N
6.5	Radon 222 -----	N	6.15	Alpha Emitting Radium Isotopes	
6.6	Radioactive Cesium -----	N		in Haz. Wastes -----	N
6.7	Iodine 131 -----	N	6.16	Radium 228 in Hazardous Wastes -----	N
6.8	Radioactive Strontium -----	N			
6.9	Tritium -----	N			
6.10	Gamma and Photon Emitters -----	N			

7 Shellfish Sanitation (-----)

7.1	Shellfish meat Microbiology -----	N
7.2	Paralytic Shellfish Poison -----	N
7.3	Domoic Acid -----	N

8 Aquatic Toxicity Bioassays (-----)

8.1	Hazardous Waste Aquatic Toxicity Bioassay (Title 22, CCR, 66261.24(a)(6)) -----	N
8.2	Wastewater Testing According to Kopperdahl (1976) using Freshwater Fish. -----	N
8.3	Wastewater Testing According to EPA/600/4-85/013 using Freshwater and/or Marine Organisms -----	N
8.4	Wastewater Testing by EPA Method 1000.0 -----	N
8.5	Wastewater Testing by EPA Method 1002.0 -----	N
8.6	Wastewater Testing by EPA Method 1003.0 -----	N
8.7	Wastewater Testing by EPA Method 1006 -----	N
8.8	Wastewater Testing by EPA Method 1007 -----	N
8.9	Wastewater Testing by EPA Method 1009 -----	N
8.10	Wastewater Testing According to Anderson, et. al. (1990) using Giant Kelp (<i>Macrocystis pyrifera</i>) --	N
8.11	Wastewater Testing According to Anderson, et. al. (1990) using Red Abalone (<i>Haliotis rufescens</i>) ---	N
8.12	Wastewater Testing According to Dinnel and Stober (1987) using Purple Sea Urchin (<i>Strongylocentrotus purpuratus</i>) -----	N
8.13	Wastewater Testing According to Dinnel and Stober (1987) using Red Sea Urchin (<i>Strongylocentrotus franciscanus</i>) -----	N
8.14	Wastewater Testing According to Dinnel and Stober (1987) using Sand Dollar (<i>Dendraster excentricus</i>) -----	N
8.15	Wastewater Testing According to procedure E 724-89 (ASTM, 1989) using Pacific Oyster (<i>Crassostrea gigas</i>) -----	N
8.16	Wastewater Testing According to procedure E 724-89 (ASTM, 1989) using California Bay Mussel (<i>Mytilus edulis</i>) -----	N
8.17	Wastewater Testing According to Standard Methods (APHA, 1989) using an alga (<i>Skeletonema costatum</i>) -----	N
8.18	Wastewater Testing According to EPA/600/4-90/027 using Freshwater and/or Marine Organisms -----	N

9 Physical Properties Testing of Hazardous Waste (11-09-93)

9.1	Ignitability by Flashpoint determination (Title 22, CCR, 66261.21) -----	N
9.2	Corrosivity - pH determination (Title 22, CCR, 66261.22) -----	Y
9.3	Corrosivity - Corrosivity towards steel (Title 22, CCR, 66261.22) -----	N
9.4	Reactivity (Title 22, CCR, 66261.23) -----	N

10 Inorganic Chemistry and Toxic Chemical Elements of Hazardous Waste

10.1	Antimony		10.7	Cobalt	
	7040(-----) -----	N		7200(-----) -----	N
	7041(07-03-91) -----	Y		7201(-----) -----	N
10.2	Arsenic		10.8	Copper	
	7060(07-03-91) -----	Y		7210(-----) -----	N
	7061(-----) -----	N		7211(-----) -----	N
10.3	Barium		10.9	Lead	
	7080(-----) -----	N		7420(07-03-91) -----	Y
	7081(-----) -----	N		7421(-----) -----	N
10.4	Beryllium		10.10	Mercury	
	7090(-----) -----	N		7470(07-03-91) -----	Y
	7091(-----) -----	N		7471(07-03-91) -----	Y
10.5	Cadmium		10.11	Molybdenum	
	7130(-----) -----	N		7480(-----) -----	N
	7131(-----) -----	N		7481(-----) -----	N
10.6	Chromium, total		10.12	Nickel	
	7190(-----) -----	N		7520(-----) -----	N
	7191(-----) -----	N			

CERTIFICATE NUMBER: 1563
EXPIRATION DATE: 07-31-97

10.13	Selenium				
	7740(07-03-91)	-----	Y		
	7741(-----)	-----	N		
10.14	Silver				
	7760(07-03-91)	-----	Y		
	7761(-----)	-----	N		
10.15	Thallium				
	7840(-----)	-----	N		
	7841(07-03-91)	-----	Y		
10.16	Vanadium				
	7910(-----)	-----	N		
	7911(-----)	-----	N		
10.17	Zinc				
	7950(-----)	-----	N		
	7951(-----)	-----	N		
10.18	Chromium (VI)				
	7195(-----)	-----	N		
	7196(07-03-91)	-----	Y		
	7197(-----)	-----	N		
	7198(-----)	-----	N		
10.19	Cyanide				
	9010(-----)	-----	N		
10.20	Fluoride				
	300.0(11-09-93)	-----	Y		
	340.1(-----)	-----	N		
	340.2(07-03-91)	-----	Y		
	340.3(-----)	-----	N		
10.21	Sulfide				
	9030(-----)	-----	N		
10.22	Total Organic Lead				
	(07-03-91)	-----	Y		
10.23	EPA Method 6010(11-09-93)	-----	Y		
10.24	EPA Method 6020(-----)	-----	N		
11	<u>Extraction Tests of Hazardous Waste (07-03-91)</u>				
11.1	California Waste Extraction Test (WET) (Title 22, CCR, 66261.100, Appendix II)	-----	Y		
11.2	Extraction Procedure Toxicity	-----	N		
11.3	Toxicity Characteristic Leaching Procedure (TCLP) All Classes	-----	N		
11.4	Toxicity Characteristic Leaching Procedure (TCLP) Inorganics Only	-----	N		
11.5	Toxicity Characteristic Leaching Procedure (TCLP) Extractables Only	-----	N		
11.6	Toxicity Characteristic Leaching Procedure (TCLP) Volatiles Only	-----	N		
12	<u>Organic Chemistry of Hazardous Waste (measurement by GC/MS combination)</u>				
12.1	EPA Method 8240(11-09-91)	-----	Y		
12.2	EPA Method 8250(-----)	-----	N		
12.3	EPA method 8270(-----)	-----	N		
12.4	EPA Method 8280(-----)	-----	N		
12.5	EPA Method 8290(-----)	-----	N		
12.6	EPA Method 8260(11-09-93)	-----	Y		
13	<u>Organic Chemistry of Hazardous Waste (excluding measurements by GC/MS combination)</u>				
13.1	EPA Method 8010(07-03-91)	-----	Y		
13.2	EPA Method 8015(07-03-91)	-----	Y		
13.3	EPA Method 8020(07-03-91)	-----	Y		
13.4	EPA Method 8030(-----)	-----	N		
13.5	EPA Method 8040(07-03-91)	-----	Y		
13.6	EPA Method 8060(-----)	-----	N		
13.7	EPA Method 8080(07-03-91)	-----	Y		
13.8	EPA Method 8090(-----)	-----	N		
13.9	EPA Method 8100(-----)	-----	N		
13.10	EPA Method 8120(-----)	-----	N		
13.11	EPA Method 8140(-----)	-----	N		
13.12	EPA Method 8150(07-03-91)	-----	Y		
13.13	EPA Method 8310(-----)	-----	N		
13.14	EPA Method 632 (-----)	-----	N		
13.15	Total Petroleum Hydrocarbons				
	(LUFT Manual) (07-31-93)	-----	Y		
13.16	EPA Method 8011(11-09-93)	-----	Y		
13.17	EPA Method 8021(01-25-96)	-----	Y		
13.18	EPA Method 8070(-----)	-----	N		
13.19	EPA Method 8110(-----)	-----	N		
13.20	EPA Method 8141(-----)	-----	N		
13.21	EPA Method 8330(-----)	-----	N		
14	<u>Bulk Asbestos Analysis (-----)</u>				
14.1	1% or Greater Asbestos Concentrations (Title 22, CCR, 66261.24(a)(2)(A))	-----	N		
15	<u>Substances Regulated Under the California Safe Drinking Water and Toxic Enforcement Act (Proposition 65) and Not Included in Other Listed Groups.</u>				
16	<u>Wastewater Inorganic Chemistry, Nutrients and Demand (07-03-91)</u>				
16.1	Acidity	-----	Y		
16.2	Alkalinity	-----	Y		
16.3	Ammonia	-----	Y		
16.4	Biochemical Oxygen Demand	-----	Y		
16.5	Boron	-----	Y		
16.6	Bromide	-----	Y		
16.7	Calcium	-----	Y		
16.8	cBOD	-----	Y		
16.9	Chemical Oxygen Demand	-----	Y		
16.10	Chloride	-----	Y		
16.11	Chlorine Residual, total	-----	Y		
16.12	Cyanide	-----	Y		
16.13	Cyanide amenable to Chlorination	-----	Y		
16.14	Fluoride	-----	Y		
16.15	Hardness	-----	Y		
16.16	Kjeldahl Nitrogen	-----	Y		
16.17	Magnesium	-----	Y		
16.18	Nitrate	-----	Y		
16.19	Nitrite	-----	Y		
16.20	Oil and Grease	-----	Y		
16.21	Organic Carbon	-----	N		
16.22	Oxygen, Dissolved	-----	Y		

CERTIFICATE NUMBER: 1563
EXPIRATION DATE: 07-31-97

16.23	pH -----	Y	16.39	Surfactants (MBAS) -----	Y
16.24	Phenols -----	Y	16.40	Tannin and Lignin -----	N
16.25	Phosphate, ortho- -----	Y	16.41	Turbidity -----	Y
16.26	Phosphorus, total -----	Y	16.42	Iron (Colorimetric Only) -----	N
16.27	Potassium -----	Y	16.43	Manganese (Colorimetric Only) -----	N
16.28	Residue, Total -----	Y	16.44	Total Recoverable -----	
16.29	Residue, Filterable (TDS) -----	Y		Petroleum Hydrocarbons -----	Y
16.30	Residue, Nonfilterable (TSS) -----	Y	16.45	Total Organic Halides -----	N
16.31	Residue, Settleable (SS) -----	Y			
16.32	Residue, Volatile -----	Y			
16.33	Silica -----	Y			
16.34	Sodium -----	Y			
16.35	Specific Conductance -----	Y			
16.36	Sulfate -----	Y			
16.37	Sulfide (includes total & soluble) -----	Y			
16.38	Sulfite -----	Y			

17 Toxic Chemical Elements in Wastewater (07-03-91)

17.1	Aluminum -----	Y	17.18	Nickel -----	N
17.2	Antimony -----	Y	17.19	Osmium -----	Y
17.3	Arsenic -----	Y	17.20	Palladium -----	N
17.4	Barium -----	N	17.21	Platinum -----	N
17.5	Beryllium -----	N	17.22	Rhodium -----	N
17.6	Cadmium -----	Y	17.23	Ruthenium -----	N
17.7	Chromium (VI) -----	Y	17.24	Selenium -----	Y
17.8	Chromium, total -----	Y	17.25	Silver -----	Y
17.9	Cobalt -----	N	17.26	Strontium -----	N
17.10	Copper -----	N	17.27	Thallium -----	Y
17.11	Gold -----	N	17.28	Tin -----	Y
17.12	Iridium -----	N	17.29	Titanium -----	N
17.13	Iron -----	N	17.30	Vanadium -----	N
17.14	Lead -----	Y	17.31	Zinc -----	N
17.15	Manganese -----	N	17.32	EPA Method 200.7 -----	Y
17.16	Mercury -----	Y	17.33	EPA Method 200.8 -----	N
17.17	Molybdenum -----	N	17.34	DCP -----	N
			17.35	Asbestos -----	N

18 Organic Chemistry of Wastewater (measurements by GC/MS combination (07-03-91)

18.1	EPA Method 624 -----	Y
18.2	EPA Method 625 -----	N
18.3	EPA Method 1613 -----	N
18.4	EPA Method 1625 -----	N
18.5	EPA Method 613 -----	N

19 Organic Chemistry of Wastewater (excluding measurements by GC/MS combination) (07-03-91)

19.1	EPA Method 601 -----	Y	19.8	EPA Method 608 -----	Y
19.2	EPA Method 602 -----	Y	19.9	EPA Method 609 -----	N
19.3	EPA Method 603 -----	N	19.10	EPA Method 610 -----	N
19.4	EPA Method 604 -----	Y	19.11	EPA Method 611 -----	N
19.5	EPA Method 605 -----	N	19.12	EPA Method 632 -----	N
19.6	EPA Method 606 -----	N	19.13	EPA Method 619 -----	N
19.7	EPA Method 607 -----	N			

20 Inorganic Chemistry and Toxic Chemical Elements of Pesticide Residues in Food (-----)

20.1	Processed Foods by One of the Following Methods -----	
	Atomic Absorption Spectrophotometry -----	N
	Inductively Coupled Plasma Atomic Emission Spectrophotometry -----	N
	Inductively Coupled Plasma/Mass Spectrometry -----	N
	Colorimetry -----	N
20.2	Raw Commodities by One of the Following Methods -----	
	Atomic Absorption Spectrophotometry -----	N
	Inductively Coupled Plasma Atomic Emission Spectrophotometry -----	N
	Inductively Coupled Plasma/Mass Spectrometry -----	N
	Colorimetric -----	N
20.3	Dairy Products by One of the Following Methods -----	
	Atomic Absorption Spectrophotometry -----	N
	Inductively Coupled Plasma Atomic Emission Spectrophotometry -----	N
	Inductively Coupled Plasma/Mass Spectrometry -----	N
	Colorimetry -----	N

CERTIFICATE NUMBER: 1563
EXPIRATION DATE: 07-31-97

20.4	Feed Products by One of the Following Methods	
	Atomic Absorption Spectrophotometry	N
	Inductively Coupled Plasma Atomic Emission Spectrophotometry	N
	Inductively Coupled Plasma/Mass Spectrometry	N
	Colorimetry	N
21	<u>Organic Chemistry of Pesticide Residues in Food (measurements by GC/MS) (-----)</u>	
21.1	Gas Chromatographic/Mass Spectrometric Methods in Processed Foods	N
21.2	Gas Chromatographic/Mass Spectrometric Methods in Raw Commodities	N
21.3	Gas Chromatographic/Mass Spectrometric Methods in Dairy Products	N
21.4	Gas Chromatographic/Mass Spectrometric Methods in Feed Products	N
22	<u>Organic Chemistry of Pesticide Residues in Food (Excluding Measurement by GC/MS Combination)</u> <u>(-----)</u>	
22.1	Halogenated Compounds in Processed Foods by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.2	Organophosphorous Compounds in Processed Foods by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.3	Carbamates in Processed Foods by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.4	Halogenated Compounds in Raw Commodities by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.5	Organophosphorous Compounds in Raw Commodities by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.6	Carbamates in Raw Commodities by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.7	Halogenated Compounds in Dairy Products by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.8	Organophosphorous Compounds in Dairy Products by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.9	Carbamates in Dairy Products by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.10	Halogenated Compounds in Feed Products by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.11	Organophosphorous Compounds in Feed Products by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N
22.12	Carbamates in Feed Products by One of the Following Methods	
	Gas Chromatography	N
	High Pressure Liquid Chromatography	N
	Liquid Chromatography/Mass Spectrometry	N

Performance and System Audits

Figure 12-4 FGL Santa Paula - Utah Department of Health Certification

This page intentionally left blank for figures on the next 7 pages.



State of Utah

Michael O. Leavitt
Governor

Rod L. Erté
Executive Director

Charles D. Brokopp, Dr. PH.
Director

Bureau of Laboratory Improvement
100 North Medical Drive
Salt Lake City, Utah 84143-1105
Telephone 801-584-8409
Fax 801-584-8500

JAN 05 1996

DARRELL H NELSON
FGL ENVIRONMENTAL
PO BOX 272
SANTA PAULA CA 93061-0272

Certificate No.: E-278
Account No: 8056590910

On the basis of your most recent audit results, the laboratory listed is hereby certified for environmental monitoring under the Resource Conservation and Recovery Act and authorized to perform the following analytes, or groups of analytes by method:

METALS

ALUMINUM 6020
ANTIMONY 6020
ANTIMONY 7041
ARSENIC 6020
ARSENIC 7060
BARIUM 6010
BARIUM 6020
BERYLLIUM 6010
BERYLLIUM 6020
CADMIUM 6010
CADMIUM 6020
CHROMIUM 6010
CHROMIUM 6020
CHROMIUM, HEXAVALENT 7196
COBALT 6010
COBALT 6020
COPPER 6010
COPPER 6020
LEAD 6020
LEAD 7420
MANGANESE 6020
MERCURY 7470
MERCURY 7471
MOLYBDENUM 6010
NICKEL 6010
NICKEL 6020
SELENIUM 7741
SILVER 6010

SILVER 6020
THALLIUM 6020
THALLIUM 7841
VANADIUM 6010
ZINC 6010
ZINC 6020

MISCELLANEOUS

CYANIDE TOTAL/AMENABLE 9010
IGNITABILITY 1020
ORGANOCHL PEST 8080
ORGANOPHOSPHORUS PEST 8140
ORGANOPHOSPHORUS PEST 8141
PAH 8310
PAINT FILTER LIQUID TST 9095
PCB 8080
PH 9045
REACTIVITY SEC 2.1.3
REACTIVITY SEC 8.3
SEMIVOLATILES 8270
TCLP METAL 1311
TCLP VOLATILE 1311
TOTAL ORGANIC HALIDES 9020
VOLATILES 8240
VOLATILES 8260

RADIOLOGICS

GROSS ALPHA & BETA 9310
RADIUM 228 - 9320



State of Utah

Michael O. Leavitt
Governor

Rod L. Betit
Executive Director

Charles D. Brokopp, Dr. P.H.
Director

Bureau of Laboratory Improvement
46 North Medical Drive
Salt Lake City, Utah 84143-1105
Telephone: 801-584-8469
Fax: 801-584-8501

JAN 05 1996

DARRELL H NELSON
FGL ENVIRONMENTAL
PO BOX 272
SANTA PAULA CA 93061-0272

Certificate No.: E-278
Account No: 8056590910

On the basis of your most recent audit results, the laboratory listed is hereby certified for environmental monitoring under the Safe Drinking Water Act and authorized to perform the following analytes, or groups of analytes by method:

RADIOLOGICS

CESIUM-134
GROSS ALPHA
GROSS BETA
RADIUM - 226

RADIUM-228

STRONTIUM - 89/90
TOTAL RADIUM
TRITIUM
URANIUM

This laboratory's certification is effective NOV 30 1995 through NOV 30 1997.

The analytes for which a laboratory is authorized to perform at any given time will be those indicated in the most recent certificate letter. Please review for completeness and accuracy. Any discrepancies must be documented and notice received by this Bureau within 15 days of receipt. Copies of this letter will be on file in (1) the Bureau of Laboratory Improvement, Division of Laboratory Services and (2) in the Department of Environmental Quality. The certification will be recalled in the event that your Laboratory's certification is revoked.

Respectfully,


Charles Brokopp, Dr. P.H.
Director

cc. Richard Denton - DEQ (cc. electronic)
Kenneth Bousfield - DEQ (cc. electronic)
U.S. EPA Region VIII QAO
Management Services Coordinator (cc. electronic)

This laboratory's certification is effective JAN 23 1996 through NOV 30 1997.

The analytes for which a laboratory is authorized to perform at any given time will be those indicated in the most recent certificate letter. Please review for completeness and accuracy. Any discrepancies must be documented and notice received by this bureau within 15 days of receipt. Copies of this letter will be on file in (1) the Bureau of Laboratory Improvement, Division of Laboratory Services and (2) in the Department of Environmental Quality. The certification will be recalled in the event that your Laboratory's certification is revoked.

Respectfully,



Charles Brokopp, Dr. P.H.
Director

cc. Richard Denton - DEQ (cc. electronic)
Dennis Downs - DEQ (cc. electronic)
U.S. EPA Region VIII QAO
Management Services Coordinator (cc. electronic)

Performance and System Audits

Figure 12-4 FGL Santa Paula - Hawaii Department of Health Certification

This page intentionally left blank for the figure on the next page.

BENJAMIN J. CAYETANO
GOVERNOR



LAWRENCE MIIKE
DIRECTOR OF HEALTH

STATE OF HAWAII
DEPARTMENT OF HEALTH
2725 WAIMANO HOME ROAD
PEARL CITY, HAWAII 96782-1496

In reply, please refer to:
File: SLD

It is recommended that data from the following laboratory be accepted for drinking water analyses for regulatory purposes for the contaminants listed until February 28, 1997.

FGL ENVIRONMENTAL
853 Corporation Street
Santa Paula, California 93061

Denis D. Barry, Marketing Director
(805) 659-0910

INORGANICS

Antimony
Arsenic
Barium
Beryllium
Cadmium
Chromium
Copper
Lead
Mercury
Nickel
Selenium
Thallium

Nitrate
Fluoride

ORGANICS

Endothall
Glyphosate
Diquat
Bis-2-ethylhexyl Adipate
Bis-2-ethylhexyl Phthalate
Benzo(a)pyrene

PCB as decachlorobiphenyl

ORGANICS

Alachlor
Atrazine
Chlordane
Endrin
Heptachlor
Heptachlor Epoxide
Hexachlorobenzene
Hexachlorocyclopentadiene
Lindane
Methoxychlor
Simazine
Toxaphene

Aldicarb
Aldicarb Sulfone
Aldicarb Sulfoxide
Carbofuran
Oxamyl

2,4-D
Silverx
Pentachlorophenol
Dalapon
Dinoseb
Picloram

VOLATILES


THM
VOC
Vinyl Chloride

EDB
DBCP


OTHER

Residual Chlorine
TDS
Calcium
pH
Alkalinity
Corrosivity
Sodium
Sulfate

RECOMMENDED:

 2/13/96
Jodi Nakanura Date
Certification Officer

APPROVED:

 2/15/96
Vernon K. Miyamoto, Ph.D. Date
Chief, State Laboratories Division

1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525

Preventive Maintenance

13.1 Maintenance and Repair of Instruments

Routine maintenance of equipment is performed by the analyst when appropriate. The department supervisor must be notified immediately if any sign of serious malfunction occurs in any instrument so that he can decide if a qualified serviceman should be consulted. If warranted, instrument repair and calibration is performed by qualified service technicians (usually service representatives of the instrument manufacturer). A record containing the date, the analyst or service engineer, symptoms of the problem, description of the repair, and comments concerning the repair is also kept. Figures 13-1 and 13-2 give examples of the logbook cover and logbook record.

13.2 Refrigerator and Oven Temperature Monitoring

All refrigerators and ovens are monitored daily to confirm proper operation. Refrigerators and ovens which do not have an NIST certified thermometer are checked for accuracy using an NIST reference thermometer.

13.3 Balance Monitoring

All balances are monitored on a monthly basis to verify proper operation and accuracy. The weights used for verification are calibrated to class M2 tolerances. The weights are certified on an annual basis.

13.4 Good Laboratory Practices

Good laboratory practices are followed to prevent contamination of samples and standards. This includes the careful cleaning of glassware, and the use of disposable labware and containers when practical. Sample containers are monitored for contamination when received, according to lot number and proposed use.

The bacteriology water is monitored for suitability annually. Standard plate count, electrical conductivity and residual chlorine are checked monthly. Heavy metals (including lead, cadmium, chromium, copper, nickel and zinc) are checked annually.

Figure 13-1 Repair/Maintenance Logbook Cover

This page intentionally left blank for figure on next page.



ENVIRONMENTAL

Analytical Chemists

**Repair/Maintenance
Log Book**

Manufacturer:.....

Model No.....

Serial No.....

Instrument ID:.....

Section No: 13
Page: 3 of 5
Revision No: 2.2
Date: May 9, 1995

Figure 13-1 Repair/Maintenance Logbook Record

This page intentionally left blank for figure on next page.

Activities Log

Date:

Analyst/Service Eng.:

Symptoms: _____

Repair/Maintenance: _____

Comments: _____

Section No: 13
Page: 5 of 5
Revision No: 2.2
Date: May 9, 1995

Specific Routine Procedures used to assess Data Precision, Accuracy, and Completeness

Before analytical data can be used, it is necessary to determine the suitability of the data for a given purpose. The characteristics used to determine data suitability are precision, accuracy, and completeness. FGL Environmental determines these characteristics by using specific procedures, which are detailed in the following sections.

14.1 Precision

Precision is the measure of how closely replicate analyses agree. FGL Environmental uses Relative Percent Difference (RPD) to measure between duplicate analyses.

Precision is monitored for nearly all methods by RPD's plotted on control charts. The mean RPD ± 2 standard deviations are the warning limits, and the mean RPD ± 3 standard deviation are the control limits. To assess precision, FGL Environmental uses the following on a regular basis:

- (1) Duplicate samples
- (2) Duplicate Matrix Spikes
- (3) Control Charts

14.1.1 Precision Calculation

The RPD of duplicate samples is an absolute value from the following calculation:

$$\frac{(\text{First Sample Value} - \text{Second Sample Value}) \times 100}{(\text{First Sample Value} + \text{Second Sample Value}) / 2}$$

14.2 Accuracy

Accuracy measures the deviation of the analytical value from the "true" or known value. The true value for field samples are never known, so accuracy measurements are made on the analysis of QC samples analyzed with field samples.

Accuracy is monitored for nearly all methods by percent recoveries plotted on control charts. The mean recovery ± 2 standard deviation are the warning limits, and the mean recovery ± 3 standard deviation are the control limits. To assess accuracy, FGL Environmental uses the following on a regular basis:

- (1) Initial Calibration Verification (ICV)
- (2) Continuing Calibration Verification (CCV)
- (3) Laboratory Control Samples (LCS)

FGL uses ICV and CCV to verify control for those analyses without significant sample preparation and a combination of ICV, CCV and LCS to verify control for those analyses which require significant sample preparation.

Specific Routine Procedures used to assess Data Precision, Accuracy, and Completeness

14.2.1 Accuracy Calculations

Percent recoveries are calculated as follows (identical units would be used through each calculation):

ICV, CCV and LCS percent recoveries:

$$\frac{\text{value found} \times 100}{\text{true value}}$$

14.3 Sample Matrix Effects

Sample matrix effect calculations measure the impact of the matrix on the analytical results. Matrix effects are control charted for the major matrix groups such as potable water, wastewater, solids, filters etc. However, FGL does not use the results for verifying analytical control.

Matrix spike and matrix spike duplicate results are monitored for nearly all methods and surrogate spike results are monitored for most organic methods by percent recoveries plotted on control charts. The mean recovery +/- 2 standard deviation are the warning limits, and the mean recovery +/- 3 standard deviation are the control limits.

14.3.1 Sample Matrix Effect Calculations

Percent recoveries are calculated as follows (identical units would be used through each calculation):

Spike percent recoveries:

$$\frac{(\text{spiked sample result} - \text{sample result}) \times 100}{\text{spike amount added}}$$

14.4 Completeness

Completeness is defined by QAMS-005/80 as - a measure of the amount of valid data obtained from a measurement system compared to the amount that was expected to be obtained under correct normal conditions.

By this definition the influence of the laboratory on completeness involves three areas:

- 1) appropriate sample handling and storage,
- 2) conformance to holding time requirements and
- 3) data validity as measured by meeting acceptance criteria for the quality control parameters.

We do not track completeness as a measurable form at this point. We do strive to provide data packages that are 100% complete and give explanations when there are deficiencies.

Specific Routine Procedures used to assess Data Precision, Accuracy, and Completeness

14.5 Control Charts

FGL is in the process of formalizing the use of quality assurance data. Many EPA and standard methods do not have formal quality assurance objectives. Also, EPA does not have criteria for dropping outliers from control charts. Below is an outline of the approach FGL is taking to provide for these deficiencies.

14.5.1 Control Chart Limits

FGL will be using several different control limits. The following is a list of limits with definitions:

- a) EPA limit - limit specified in the method and required by EPA
- b) FGL control chart fixed limit - used for CCV and LCS acceptance criteria. If an analysis or procedure does not have limits specified by the EPA the limits will be generated by control charts using a 99% confidence interval (3s). These limits will then be set and not allowed to be adjusted unless the control charts show a significant change in the method i.e. narrowing of 50%.
- c) FGL control chart variable limit - used for BS, MS and RPD acceptance criteria. If an analysis or procedure does not have limits specified by the EPA the limits will be generated by control charts using a 99% confidence interval (3s) and perhaps a 95% confidence interval (2s), if a warning limit is deemed useful. These limits will then be allowed to fluctuate based on control chart findings.
- d) Global - 3s control chart limits based on all points in the control chart less those points that are dropped based on criteria in section 2.
- e) Trend - 3s control chart limits based on the most recent 30 points in the control chart less those points dropped based on criteria in section 2.

14.5.2 Criteria for Dropping Outliers

- a) RPD or % Rec. point drop - low spike concentration - the RPD or % rec. point may be dropped if the spike concentration is less than MAV times the sample concentration. i.e. if the sample concentration is 2.5 mg/l and the MAV is 15%, a spike of 0.374 mg/L or lower would be rejected as too low and a spike of 0.375 or greater would be maintained.
- b) RPD point drop - low duplicate concentration - the RPD point may be dropped if the sample concentration is lower than the DLR times the MAV. i.e. if the DLR is 0.2 mg/L and the MAV is 15%, an average sample concentration (for the duplicates) of 2.9 or lower would be rejected and an average sample concentration of 3.0 or above would be maintain.
- c) RPD or % Rec. - outliers - prior to setting the limits the points are reviewed. The point may be dropped if it fails the following test: If the control limits are shifted by 30% of the limit (i.e. 85 - 115% changing to 89.5 - 110.5%) or more by any single point then the point is considered an outlier and dropped.

Corrective Actions

Corrective actions are necessary when trends of more than one out-of-control situations occur. Corrective action reports are used to document the corrections made. Corrective actions are not normally used in isolated out-of-control situations that have routine explanations as the data in these situations must be resolved before continuing and reporting analyses.

15.1 Corrective Action Reports

Each work area has a corrective action report logbook. When corrective actions are necessary, a corrective action report form (figure 15-1) is filled out identifying the analyst, date, method, client and lab number (if applicable), QA batch number (if applicable) problems encountered, investigation and proposed corrective actions. After implementing the actions another entry is required to verify that the problem was solved. This process may need to be repeated in some situations. The reports are on record and will be included in a project data package if that is required by the project plan. An example of a corrective action report form is shown in figure 15-1.

Corrective Actions

Figure 15-1 Corrective Action Report Form

This page intentionally left blank for the figure on the next page.

Corrective Actions

Corrective Action Report Form

Method: _____

Problem Assigned To: _____

Problem encountered: _____

Cause of the problem: _____

Corrective action: _____

Closure of Investigation:

Performed by: _____ Date: _____

Verified by: _____ Date: _____

Quality Assurance Reports to Management

In order to insure that the Quality Assurance program at the lab maintains a high profile, there are several mechanisms in place which insure the QA information is routinely conveyed to laboratory management. This includes a formal monthly QA inspection summary report, reports on internal and external PE samples and summary reports for external system audits.

16.1 Monthly QA Non-conformance Summary Reports

This report contains all the new non-conformance items, previously uncompleted non-conformance items and finally all non-conformance items completed. Dates are recorded when the non-conformance was found and when it was completed. This report is given to all supervisors and managers. With these steps an ongoing quantitative assessment of the analytical system is provided.

16.2 Annual QA Summary Reports

At the end of each year the QA director compiles all the quality assurance information for the previous year and provides a summary report to management. This report includes the number of non-conformances found throughout the year, trending information on the non-conformances, performance evaluation study summaries and evaluations of whether quality assurance inspection schedules were maintained.

16.3 Performance Evaluation Corrective Action Reports

Evaluations of any failures on external PE samples are outlined by department supervisors and prepared by the QA Director or Officer for certifying agencies. Copies are given to the department supervisors and Lab Director.

16.4 External System Audit Summary Reports

After debriefing by the auditors a summary report is prepared by the QA Director or Officer for the supervisors and Lab Director. Rather than waiting for an audit report, this initiates corrective actions for any non-conformance items promptly.

Quality Assurance Reports to Management

Figure 16-1 FGL Monthly QA Non-Comformance Summary Report

This page intentionally left blank for the figure on next page.

Quality Assurance Reports to Management

FGL Monthly QA Non-Comformance Summary Report

Current Non-conformance Items

[illegible]

Corrected Non-comformance Items

[illegible]

FGL Environmental Instrument and Equipment List

LAB	DIVISION	INSTRUMENT DESCRIPTION	SERIAL NUMBER	INST. TYPE	INST. ID	INV. CONTROL	REMARKS
SP	Organic	Hewlett Packard GC/MS 5890II/5972 with 7673A autosampler	3310A49023	GC/MS	202	26-93-0046	
SP	Organic	Hewlett Packard GC/MS 5890II/5972 with LSC2000/ALS2016 autosampler	3336A52456	GC/MS	204	26-94-0028	
SP	Organic	Hewlett Packard GC/MS 5890II/5971 with 7673A autosampler	3203A41750	GC/MS	201	26-92-0036	
SP	Organic	Hewlett Packard GC/MS 5890II/5971 with LSC2000/ALS2016 autosampler	2905A12089	GC/MS	205	26-95-0056-349	
SP	Organic	Hewlett Packard GC/MS 5890II/5970 with LSC2000/ALS2016 autosampler	3004A12738	GC/MS	206	26-95-0076-369	
SP	Organic	Varian 3400/Finnigan XL 50 with LSC2000/ALS2016/ALS2032 autosampler	IN001137	GC/MS	203	26-91-0025	
SP	Organic	Hewlett Packard GC 5890 with ECD + ECD detectors and 7673A autosampler	2750A15955	GC	202	26-95-0017-328	
SP	Organic	Hewlett Packard GC 5890 with ECD + ECD detectors and 7673A autosampler	2750A18077	GC			
SP	Organic	Hewlett Packard GC 5890 with ECD + ECD detectors and 7673A autosampler	2413A11796	GC			
SP	Organic	Hewlett Packard GC 5890 with FID + NPD detectors and 7673A autosampler	2415A01377	GC	204	26-91-0042	
SP	Organic	Hewlett Packard GC 5890 with NPD + FPD detectors and 7673A autosampler	2916A22297	GC	201		
SP	Organic	Hewlett Packard GC 5890 with PID + FID detectors and LSC2000/ALS2032 autosampler	2916A22291	GC	207	89-135	
SP	Organic	Hewlett Packard GC 5890 with PID + FID detectors and LSC2000/ALS2032 autosampler	323A42727	GC	213	26-95-0070-363	
SP	Organic	Hewlett Packard GC 5890 with ELCD + PID detectors and LSC2000/ALS2016 autosampler	2541A06581	GC	209	26-95-0018-342	
SP	Organic	Hewlett Packard GC 5890 with PID + FID detectors and LSC2000/ALS2016 autosampler	2541A06582	GC	203	26-95-0033-332	

FGL Environmental Instrument and Equipment List

LAB	DIVISION	INSTRUMENT DESCRIPTION	SERIAL NUMBER	INST. TYPE	INST. ID	INV. CONTROL	REMARKS
SP	Organic	Hewlett Packard GC 5890 with 2 ELCS/PID detectors and LSC2000/ALS2016 autosampler	2950A28076	GC	211	26-95-0063-356	
SP	Organic	Hewlett Packard GC 5890 with 2 ELCS/PID detectors and LSC2000/ALS2016 autosampler	3115A35121	GC	212		
SP	Organic	Hewlett Packard GC 5890II with FID and and LSC2000/ALS2016 autosampler	3033A30381	GC		26-95-0038-334-1	
SP	Organic	Hewlett Packard GC 5890 with ELCD + ECD detectors and 7673 autosampler		GC			
SP	Organic	Hewlett Packard HPLC 1090 with UV and Fluorescence detector and post column derivatization		HPLC	202	89-126	
SP	Organic	Hewlett Packard HPLC 1090 with diode array and fluorescence detectors	2623A00932	HPLC	201		
SP	Organic	Hitachi HPLC L-6200A with L-450 Diode Array and Shimadzu RF-551 Fluorescence detector	0312-054	HPLC	203	26-92-0018	
SP	Organic	Foxboro Miran 1FF Infra-red Spectrophotometer	2539	IR	201	26-93-0041	
SP	Organic	Horiba OCMA-220 Infra-red Spectrophotometer	202021	IR	202		
SP	Organic	MCI TOX 10	43C30238	TOX	201	88-099	
SP	Organic	ASTRO 2001	2390072501	TOC	201	90-190	
SP	Organic	Mettler PC 440 Analytical Balance	814108	SCALE	206		
SP	Inorganic	Fisons Plasma Quad 2 ICP/MS	970	ICP/MS	201	26-93-00348	
SP	Inorganic	Hewlett Packard 4500 ICP/MS	3528J00253	ICP/MS	202	26-95-0057-350	
SP	Inorganic	ARI. 3410 ICP with model 101 autosampler	1324	ICP	201	90-178	
SP	Inorganic	Thermo-Jerrell Ash Atomscan 16 ICP	1871	ICP	202	26-95-0001-323	
SP	Inorganic	Thermo-Jerrell Ash J6E Trace <i>LIE</i>	338490	ICP/TR	201	26-95-0048-344	
SP	Inorganic	Thermo-Jerrell Ash J6E Purge <i>LIE</i>	78290	ICP/PR	201		

FGL Environmental Instrument and Equipment List

LAB	DIVISION	INSTRUMENT DESCRIPTION	SERIAL NUMBER	INST. TYPE	INST. ID	INV. CONTROL	REMARKS
SP	Inorganic	Perkin-Elmer 5100Z GFAA with AS-60 autosampler	136513	GFAA	201	89-134	
SP	Inorganic	Perkin-Elmer 5100Z GFAA with AS-60 autosampler	137543	GFAA	202	26-95-0061-354	
SP	Inorganic	Perkin-Elmer 5000 FAA	123286	FAA	201	82-051	
SP	Inorganic	LEEMAN PS200 Automated Mercury Analyzer	1156/110/00012	CVAA	201	26-96-0028-411	
SP	Inorganic	Dionex 300 Ion Chromatograph and Spectrophysics AS3500 autosampler	921104	IC	201	26-92-0014	
SP	Inorganic	Dionex 100 Ion Chromatograph and Spectrophysics AS3500 autosampler	94110001	IC	202	26-95-002-324	
SP	Inorganic	Technicon AA2 Flow injection autoanalyzer	FGL-09304REP	FIA	202		
SP	Inorganic	Technicon AA2 Flow injection autoanalyzer	FGL-08304REP	FIA	201		
SP	Inorganic	Perkin-Elmer Lambda 3 UV/VIS Spectrophotometer	46034	UV/VIS	201	81-043	
SP	Inorganic	Sequoia-Turner model 690 Nephelometer (Turbidimeters)	2426	TURBID	201	87-091	
SP	Inorganic	Orion model 860 Oxygen Meter	19090015	O2	201		
SP	Inorganic	Orion model 160 Conductivity Meter	09050045	EC	201	26-91-0027	
SP	Inorganic	Fisher Scientific Accumet pH Meter # 25	C0006984	PH	201		
SP	Inorganic	Setflash	2010	FLASH	201		
sp	Inorganics	CEM MDS 2100 Microwave Digestor	Z4023	MICRO	201		
SP	Inorganic	Mettler AE 200 Analytical Balance	L19861	SCALE	202	26-93-0038	
SP	Inorganic	Mettler Toledo PB 303 Analytical Balance	1113242753	SCALE	201		
SP	Radio	Princeton Gamma Tech. Gamma Ray Spectroscope	2656	GS	201	26-94-0005	

FGL Environmental Instrument and Equipment List

LAB	DIVISION	INSTRUMENT DESCRIPTION	SERIAL NUMBER	INST. TYPE	INST. ID	INV. CONTROL	REMARKS
SP	Radio	Oxford Tennelec Oasis System, Alpha Spectrometer	30104	AS	201-208	26-95-0012-327	
SP	Radio	Radom 5C-5, Gas Scintillation	13371270	SC	201	26-93-0018	
SP	Radio	Packard 2500TR, Liquid Scintillation	2500	LSC	201	26-93-197	
SP	Radio	NMC PCC11T, Alpha Counter	79-2750-07	GP	201	26-79-999	
SP	Radio	NMC PCC11T, Alpha Counter	81-2750-14	GP	202	26-81-045	
SP	Radio	NMC PCC11T, Alpha Counter	89-2750-1-17	GP	205	26-89-153-1	
SP	Radio	NMC PCC11T, Alpha Counter	89-2750-1-18	GP	206	26-89-153-2	
SP	Radio	NMC PCC11T, Alpha Counter	90-2755-1-03	GP	207	26-90-167	
SP	Radio	Tennelec LB 1000, Alpha/Beta Counter	577	GP	203	26-87-083	
SP	Radio	Tennelec LB 1000, Alpha/Beta Counter	518	GP	204	26-89-111	
SP	Radio	Tennelec LB 5100, Alpha/Beta Counter, with autosampler	505	GP	208	26-93-0033	
SP	Radio	Sartorius L 420 P Balance	37080053	SCALE	204	90-165	
SP	Bact	2 Incubator	N/A	N/A	N/A	N/A	
SP	Bact	2 Autoclaves	N/A	N/A	N/A	N/A	
SP	Field Service	10 Vehicles	N/A	N/A	N/A	N/A	
SP	Field Service	9 Isco Autosamplers	N/A	N/A	N/A	N/A	
SP	Computers	3 Microvax with PCSA fileservers using Foxpro for DOS	N/A	N/A	N/A	N/A	
SP	Computers	1 WAN/LAN Xyplex Chassis	N/A	N/A	N/A	N/A	

FGL Environmental Instrument and Equipment List

LAB	DIVISION	INSTRUMENT DESCRIPTION	SERIAL NUMBER	INST. TYPE	INST. ID	INV. CONTROL	REMARKS
SP	Computers	1 BBS by Galaticomm	N/A	N/A	N/A	N/A	
SP	Computers	80 DOS Based Computers	N/A	N/A	N/A	N/A	
STK	Organic	Hewlett Packard GC/MS 5890II/5972 with LSC2000/ALS2016 autosampler	2921A22867	GC/MS	301		
STK	Organic	Hewlett Packard GC 5890II with ECD + ECD detectors and 7673A autosampler	3223A43094	GC	302	46-93-0029-126	
STK	Organic	Hewlett Packard GC 5890 with FID + FID detectors and 7673A autosampler	2463A72072	GC	304		
STK	Organic	Hewlett Packard GC 5890 with PID + FID detectors and LSC2000/ALS2016 autosampler	3336A53365	GC	303	46-94-0033	
STK	Organic	Hewlett Packard GC 5890 with PID + ELCD detectors and LSC2000/ALS2016 autosampler	2750A15950	GC	301		
STK	Organic	Horiba, OMA 220, Fixed IR	308023	IR	301	46-93-0051	
STK	Inorganic	Thermo-Jarrell Ash Atomscan 25	2508	ICP	301	46-93-0029	
STK	Inorganic	Hitachi 8270 Graphite Furnace AA with Zeeman Background Correction	0527-026	GFAA	302	46-94-0057	
STK	Inorganic	Perkin-Elmer 5100Z Graphite Furnace AA with Zeeman background correction and Flame AA	137931	GFAA	301	46-95-0041-131	
STK	Inorganic	Perkin-Elmer 5000 Flame AA set up for mercury cold vapor	117350		N/A		
STK	Inorganic	CEM MDS 2100 microwave digester	7-4101	MICRO	301	46-93-0014	
STK	Inorganic	Dionex DX-300 Ion Chromatograph and Spectrophysics AS3500 autosampler	930309/013-0176	IC	301	46-93-0015	
STK	Inorganic	Technicaon AA2 Flow injection autoanalyzer	171-A017-03/GC9683/GC12683	FIA	301		
STK	Inorganic	Orion model 860 Oxygen Meter	41555015	O2	301		

FGL Environmental Instrument and Equipment List

LAB	DIVISION	INSTRUMENT DESCRIPTION	SERIAL NUMBER	INST. TYPE	INST. ID	INV. CONTROL	REMARKS
STK	Inorganic	Orion model 160 Conductivity Meter	44524019	EC	301	46-95-0003	
STK	Inorganic	Fisher Scientific Accumet pH Meter # 25	C0017099	PH	301		
STK	Inorganic	Sequoia-Turner 690 UV/VIS spectrophotometer	B011224	UV/VIS	301		
STK	Inorganic	Turner 40 Nephelometer	01151	TURBID	301		
STK	Bact	Incubator	N/A	N/A	N/A	N/A	
STK	Bact	Autoclave	N/A	N/A	N/A	N/A	
STK	Field Services	3 Vehicles	N/A	N/A	N/A	N/A	
STK	Field Services	3 Isco Autosamplers	N/A	N/A	N/A	N/A	
STK	Computers	1 Microvax with PCSA pathworks fileserver using Foxpro for DOS	N/A	N/A	N/A	N/A	
STK	Computers	1 Xyplex bridge router	N/A	N/A	N/A	N/A	
STK	Computers	20 DOS based computers	N/A	N/A	N/A	N/A	

Document Control and Records Management -

This section is currently in the format of the actual SOP for Document control. Formal revision into the proper format used throughout the QA Manual will be forthcoming. Also, this currently only covers the document control portion of records management. Total records management will be addressed in the next revision.

Scope and Application:

This procedure outlines the overall document control for the laboratory. This includes outlines for determining if the document needs control and how to remove documents and turnover to archive. These methods will prevent document users from referencing outdated documents.

Equipment:

computers, files, binders etc.

Procedure:

The important decision that needs to be made for all documents is whether or not the document needs to be controlled. The following are a few criteria for deciding whether the document needs to be controlled

- 1) Does the document need to be retained for proof of analysis or procedures used?
- 2) Will the document be revised over time?
- 3) Will more than one copy of the document be in use?

The following is a list of documents known to require document control:

Standard Operating Procedures
Quality Assurance Manual
Statement of Qualifications
Fee Schedule

Document control:

Beginning control of a document:

- 1) Fill out the heading information on the Document Control Distribution Record Form.
- 2) Record the control number, who the document was issued to, the revision issued, and the date issued.
- 3) Stamp the front of the document with the controlled copy stamp and fill in the control number.

Continuing control of a document:

- 1) Upon the next revision of the document refer to the Document Control Distribution Record to determine who needs the new revision.
- 2) Stamp the front of the revised document with the controlled copy stamp and fill in the same control number if issued to the same recipient.
- 3) Issue the new controlled revision to each recipient of a controlled copy with a letter and return envelope requesting they return the outdated document.
- 4) The letter should also inquire if they need to remain on the list for receiving a controlled copy of the document.
- 5) Upon return of the controlled copy the Document Control Distribution Record should be updated recording that the document was returned. Also, document if the recipient no longer needs to receive a controlled copy.
- 6) One copy of the outdated document should be stamped with the superceded date stamp, dated and filed.
- 7) All other copies of the document should be destroyed after updating the Document Control Distribution Record.

**If a controlled document is released without document control it MUST be stamped
INFORMATION COPY ONLY**

Calculations:

N/A

Record Keeping and Storage:

There are two sets of files required for proper document control. Both sets of files must be stored in a central location under the supervision of the person responsible for upkeep. They are as follows:

- 1) Files for the Document Control Distribution Record Forms. A file for each department needs to be maintained for record storage.
- 2) Files for the superceded documents. A corresponding file must be created to store the superceded revisions of the document.

A list of files to be created can be easily obtained for the known documents requiring control. It is created as follows:

- 1) SOP's: All LIMS subdirectories under M:\FGLDOCS\SOP will require an individual file (which usually reflects the department).
- 2) QA Manual
- 3) Statement of Qualifications
- 4) Fee Schedule

Further documents to be controlled will be in future revisions of this document.


References:

N/A


Quality Assurance Manual - Amendment

Amendment Date: 8-20-96

Sections Amended: 2, 3, 4, 5, 6, 7, 9, 10, 11, 12, Appendix A

Reviewed by:  8/29/96
Yee Ren, M.S. Date
Data Validator

Concurred by:  8/27/96
Kurt Wilkinson, B.S. Date
Quality Assurance Director

Approved by:  8/31/96
Darrell H. Nelson, B.S. Date
Laboratory Director

This amendment should be inserted at the back of the quality assurance manual. The next formal revision (scheduled for April, 1997) will incorporate these amendments into their respective sections of the manual.

APPENDIX F

ANALYTICAL REPORTS FOR GROUND WATER MONITORING PARAMETERS



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802143-2

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW1 Quarterly Sampling Area 317

Sample Description: MW1/B/38

Sampled by : Abdun-Nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives: H2SO4 pH < 2

Sampled : March 25, 1998

Received : March 25, 1998

Extracted : N/A

Analyzed : March 27, 1998

QA/QC ID# : SP 98032700A A

TOTAL ORGANIC CARBON

CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOC	415.1	mg/L	0.5	ND	0.5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
mg/L = Milligrams Per Liter (ppm) ND = Not Detected at or above the DLR.
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

If you have any questions, please call.

FGL ENVIRONMENTAL

Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802143-3

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW1 Quarterly Sampling Area 317

Sample Description: MW1/C/38

Sampled by : Abdun-Nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives:

Sampled : March 25, 1998

Received : March 25, 1998

Extracted : N/A

Analyzed : April 7, 1998

QA/QC ID# : SP 98040700A A

TOTAL ORGANIC HALOGENS

CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOX	9020	ug/L	5	ND	5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
ug/L = Micrograms Per Liter (ppb) ND = Not Detected at or above the DLR.
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

If you have any questions, please call.

FGL ENVIRONMENTAL

Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802143-5

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW1 Quarterly Sampling Area 317

Sample Description: MW1/O/38

Sampled by: Abdun-Nur/Bricker

Container: VOA

Preservatives:

Sampled: March 25, 1998

Received: March 25, 1998

Extracted: N/A

Analyzed: April 2, 1998

QA/QC ID#: SP 98040201H A


EPA METHOD 624

CONSTITUENT	SAMPLE DLR ug/L	SAMPLE RESULTS ug/L	LAB DLR ug/L	BLANK RESULTS ug/L
Trichloroethylene	0.5	ND	0.50	ND
SURROGATES	AR	SAMPLE % REC.	LAB AR	BLANK % REC.
1,2-Dichloroethane-d4	40-140	120	40-140	110
Toluene-d8	64-139	96	64-139	93
BFB	50-149	100	50-149	95

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
ug/L = Micrograms Per Liter (ppb) ND = Not Detected at or above the DLR. AR = Acceptable Range
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

If you have any questions, please call.

FGL ENVIRONMENTAL


Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802143-1

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW1 Quarterly Sampling Area 317

Description: MW1/A/38

Sampled by : Abdun-Nur/Bricker

Type of Sample: Monitoring Well

Sampled : March 25, 1998

Received : March 25, 1998

Completed : March 27, 1998

QA/QC ID# : 80214301-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS
Conductivity	2510B	umhos/cm	1	810

DLR = Detection Limit for Reporting Purposes. ND = Not Detected at or above the DLR.
ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.
Preservatives: (1) Cool 4°C Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802143-4

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW1 Quarterly Sampling Area 317

Description: MW1/H/38

Sampled by : Abdun-Nur/Bricker

Type of Sample: Monitoring Well

Sampled : March 25, 1998

Received : March 25, 1998

Completed : March 25, 1998

QA/QC ID# : 80214304-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS
Chloride	300.0	mg/L	2.0*	180
Sulfate	300.0	mg/L	1	12

DLR = Detection Limit for Reporting Purposes. ND = Not Detected at or above the DLR.
ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram
* = DLR adjusted because of dilutions, concentrations, or limited sample.
Preservatives: (1) Cool 4°C Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802143-6

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW1 Quarterly Sampling Area 317

Description: MW1/R/38

Sampled by : Abdun-Nur/Bricker

Type of Sample: Monitoring Well

Sampled : March 25, 1998

Received : March 25, 1998

Completed : March 31, 1998

QA/QC ID# : 80214306-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS	MCL
Iron	200.7	ug/L	50	ND	300
Manganese	200.7	ug/L	30	ND	50
Sodium	200.7	mg/L	1	52	

DLR = Detection Limit for Reporting Purposes. ND = Not Detected at or above the DLR.
ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.
Preservatives: (1) Cool 4°C Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

May 12, 1998

LAB No: SP 802915-2

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW3 Quarterly Sampling Area 317

Sample Description: MW3/B/38

Sampled by : Abdun-Nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives: H2SO4 pH < 2

Sampled : April 23, 1998

Received : April 23, 1998

Extracted : N/A

Analyzed : May 12, 1998

QA/QC ID# : SP 98051200A B

TOTAL ORGANIC CARBON

CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOC	5310 C	mg/L	0.5	0.6	0.5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)

mg/L = Milligrams Per Liter (ppm)

ND = Not Detected at or above the DLR.

* = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL

Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:c1



ENVIRONMENTAL

ANALYTICAL CHEMISTS

May 6, 1998

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350


Subject: Total Organic Carbon Analysis - Lab No. SP 802915

Enclosed is the result of a Total Organic Carbon analysis conducted on your sample received on April 23, 1998.

Please note that the analysis was performed by Weck Laboratories, Inc.

Thank you for using FGL Environmental.

Sincerely,
FGL Environmental



Darrell H. Nelson, B.S.
President

DHN:kdm

Enclosure

This report package is not intended for use in the State of Utah unless bound or paginated

Weck Laboratories, Inc.

Analytical & Environmental Services

Client: FGL Environmental
853 Corporation Street
Santa Paula, CA 93061

Report Date: April 30, 1998

Received Date: April 24, 1998
Friday 11:32/TGN

Attn.: Shawn Peck

(805) 659-0910 x

FAX (805) 525-4172

Project Name:

Project #: 802915

Purchase Order #:

Normal Turnaround

Certificate of Analysis

Lab#: 9810163 **Sample ID:** 802915 **Matrix:** Water

Sampled By: Abdun-Nur Bricker **Date:** 04/23/1998 **Time:** 08:31 **Source:** MW3/B/38

Parameter	Result	Units	PQL	Method	Analyzed	Run #
Total Organic Carbon.....	0.77	mg/L	0.5	SM 5310C	04/29/1998	98079800

ND = Not Detected

PQL = Practical Quantifiable Limit

e = Estimated (> MDL, but < PQL)

Any remaining sample(s) for testing will be disposed of three weeks from the final report date unless other arrangements are made in advance.

Opus Kestura
Authorized Signature



ENVIRONMENTAL

ANALYTICAL CHEMISTS

May 6, 1998

LAB No: SP 802915-3

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW3 Quarterly Sampling Area 317

Sample Description: MW3/C/38

Sampled by : Abdun-Nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives:

Sampled : April 23, 1998

Received : April 23, 1998

Extracted : N/A

Analyzed : April 28, 1998

QA/QC ID# : SP 98042800A A

TOTAL ORGANIC HALOGENS

CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOX	9020	ug/L	5	ND	5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
ug/L = Micrograms Per Liter (ppb) ND = Not Detected at or above the DLR.

♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL

Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

May 6, 1998

LAB No: SP 802915-5

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW3 Quarterly Sampling Area 317

Sample Description: MW3/O/38

Sampled by : Abdun-Nur/Bricker

Container : VOA

Preservatives:

Sampled : April 23, 1998

Received : April 23, 1998

Extracted : N/A

Analyzed : April 25, 1998

QA/QC ID# : SP 98042501H B

EPA METHOD 624

CONSTITUENT	SAMPLE DLR ug/L	SAMPLE RESULTS ug/L	LAB DLR ug/L	BLANK RESULTS ug/L
Trichloroethylene	0.5	ND	0.5	ND

SURROGATES

Fluorobenzene	70-130	97	70-130	96
Pentafluorobenzene	70-130	105	70-130	103
4-Bromofluorobenzene	70-130	104	70-130	103

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
ug/L = Micrograms Per Liter (ppb) ND = Not Detected at or above the DLR. AR = Acceptable Range
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL

Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

May 6, 1998

LAB No: SP 802915-1

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW3 Quarterly Sampling Area 317

Description: MW3/A/38

Sampled by: Abdun-Nur/Bricker

Type of Sample: Monitoring Well

Sampled : April 23, 1998

Received : April 23, 1998

Completed : April 24, 1998

QA/QC ID# : 80291501-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS
Conductivity	2510B	umhos/cm	1	620
pH	4500-H B	units	---	7.3


DLR = Detection Limit for Reporting Purposes. ND = Not Detected at or above the DLR.
ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.
Preservatives: (1) Cool 4°C Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm





ENVIRONMENTAL

ANALYTICAL CHEMISTS

May 6, 1998

LAB No: SP 802915-4

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW3 Quarterly Sampling Area 317

Description: MW3/H/38

Sampled by : Abdun-Nur/Bricker

Type of Sample: Monitoring Well

Sampled : April 23, 1998

Received : April 23, 1998

Completed : April 29, 1998

QA/QC ID# : 80291504-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS
Chloride	300.0	mg/L	1	33
Sulfate	300.0	mg/L	1	71

DLR = Detection Limit for Reporting Purposes. ND = Not Detected at or above the DLR.

ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram

♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

Preservatives: (1) Cool 4°C Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm

This report package is not intended for use in the State of Utah unless bound or paginated



ENVIRONMENTAL

ANALYTICAL CHEMISTS

May 6, 1998

LAB No: SP 802915-6

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW3 Quarterly Sampling Area 317

Description: MW3/R/38

Sampled by: Abdun-Nur/Bricker

Type of Sample: Monitoring Well

Sampled : April 23, 1998

Received : April 23, 1998

Completed : April 28, 1998

QA/QC ID# : 80291506-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS	MCL
Iron	200.7	ug/L	50	50	300
Manganese	200.7	ug/L	30	ND	50
Sodium	200.7	mg/L	1	50	

DLR = Detection Limit for Reporting Purposes.

ND = Not Detected at or above the DLR.

ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram

♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

Preservatives: (1) Cool 4°C (2) HNO₃ pH < 2 Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802142-2

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW5 Quarterly Sampling Area 317

Sample Description: MW5/B/38

Sampled by : Abdun-nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives: H2SO4 pH < 2

Sampled : March 25, 1998

Received : March 25, 1998

Extracted : N/A

Analyzed : March 27, 1998

QA/QC ID# : SP 98032700A A

TOTAL ORGANIC CARBON

CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOC	415.1	mg/L	0.5	ND	0.5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
mg/L = Milligrams Per Liter (ppm) ND = Not Detected at or above the DLR.
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL


Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802142-3

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW5 Quarterly Sampling Area 317

Sample Description: MW5/C/38

Sampled by : Abdun-nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives:

Sampled : March 25, 1998

Received : March 25, 1998

Extracted : N/A

Analyzed : April 7, 1998

QA/QC ID# : SP 98040700A A

TOTAL ORGANIC HALOGENS

CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOX	9020	ug/L	5	ND	5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
ug/L = Micrograms Per Liter (ppb) ND = Not Detected at or above the DLR.
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL


Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802142-5

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW5 Quarterly Sampling Area 317

Sample Description: MW5/O/38

Sampled by : Abdun-nur/Bricker

Container : VOA

Preservatives:

Sampled : March 25, 1998

Received : March 25, 1998

Extracted : N/A

Analyzed : April 2, 1998

QA/QC ID# : SP 98040201H A

EPA METHOD 624


CONSTITUENT	SAMPLE DLR ug/L	SAMPLE RESULTS ug/L	LAB DLR ug/L	BLANK RESULTS ug/L
Trichloroethylene	0.5	ND	0.50	ND

SURROGATES	SAMPLE AR	% REC.	LAB AR	BLANK % REC.
1,2-Dichloroethane-d4	40-140	117	40-140	110
Toluene-d8	64-139	95	64-139	93
BFB	50-149	98	50-149	95

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
ug/L = Micrograms Per Liter (ppb) ND = Not Detected at or above the DLR. AR = Acceptable Range
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL


Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802142-1

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW5 Quarterly Sampling Area 317

Description: MW5/A/38

Sampled by : Abdun-nur/Bricker

Type of Sample: Monitoring Well

Sampled : March 25, 1998

Received : March 25, 1998

Completed : March 27, 1998

QA/QC ID# : 80214201-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS
Conductivity	2510B	umhos/cm	1	570

DLR = Detection Limit for Reporting Purposes. ND = Not Detected at or above the DLR.
ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.
Preservatives: (1) Cool 4°C Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802142-4

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW5 Quarterly Sampling Area 317

Description: MW5/H/38

Sampled by : Abdun-nur/Bricker

Type of Sample: Monitoring Well

Sampled : March 25, 1998

Received : March 25, 1998

Completed : March 25, 1998

QA/QC ID# : 80214204-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS
Chloride	300.0	mg/L	1	62
Sulfate	300.0	mg/L	1	29

DLR = Detection Limit for Reporting Purposes. ND = Not Detected at or above the DLR.
ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.
Preservatives: (1) Cool 4°C Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802142-6

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW5 Quarterly Sampling Area 317

Description: MW5/R/38

Sampled by : Abdun-nur/Bricker

Type of Sample: Monitoring Well

Sampled : March 25, 1998

Received : March 25, 1998

Completed : March 31, 1998

QA/QC ID# : 80214206-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS	MCL
Iron	200.7	ug/L	50	ND	300
Manganese	200.7	ug/L	30	ND	50
Sodium	200.7	mg/L	1	54	

DLR = Detection Limit for Reporting Purposes.

ND = Not Detected at or above the DLR.

ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram

♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

Preservatives: (1) Cool 4°C Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm

**ENVIRONMENTAL****ANALYTICAL CHEMISTS**

May 12, 1998

LAB No: SP 802916-2

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW6 Quarterly Sampling Area 317

Sample Description: MW6/B/38

Sampled by : Abdun-Nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives: H2SO4 pH < 2

Sampled : April 23, 1998

Received : April 23, 1998

Extracted : N/A

Analyzed : May 12, 1998

QA/QC ID# : SP 98051200A B

TOTAL ORGANIC CARBON

CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOC	5310 C	mg/L	0.5	0.6	0.5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
mg/L = Milligrams Per Liter (ppm) ND = Not Detected at or above the DLR.
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL



Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:c1



ENVIRONMENTAL

ANALYTICAL CHEMISTS

May 6, 1998

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350


Subject: Total Organic Carbon Analysis - Lab No. SP 802916

Enclosed is the result of a Total Organic Carbon analysis conducted on your sample received on April 23, 1998.

Please note that the analysis was performed by Weck Laboratories, Inc.

Thank you for using FGL Environmental.

Sincerely,
FGL Environmental



Darrell H. Nelson, B.S.
President

DHN:kdm

Enclosure

This report package is not intended for use in the State of Utah unless bound or paginated

Weck Laboratories, Inc.

Analytical & Environmental Services

Client: FGL Environmental
853 Corporation Street
Santa Paula, CA 93061

Report Date: April 30, 1998

Received Date: April 24, 1998
Friday 11:32/TGN

Attn.: Shawn Peck

(805) 659-0910 x

FAX (805) 525-4172

Project Name:

Project #: 802916

Purchase Order #:

Normal Turnaround

Certificate of Analysis

Lab#: 9810162 **Sample ID:** 802916 **Matrix:** Water

Sampled By: Abdun-Nur Bricker **Date:** 04/23/1998 **Time:** 08:52 **Source:** MW6/B/38

Parameter	Result	Units	PQL	Method	Analyzed	Run #
Total Organic Carbon.....	0.67	mg/L	0.5	SM 5310C	04/29/1998	98079800

ND = Not Detected

PQL = Practical Quantifiable Limit

e = Estimated (> MDL, but < PQL)

Any remaining sample(s) for testing will be disposed of three weeks from the final report date unless other arrangements are made in advance.

Abdun-Nur Bricker
Authorized Signature



ENVIRONMENTAL

ANALYTICAL CHEMISTS

May 6, 1998

LAB No: SP 802916-3

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW6 Quarterly Sampling Area 317

Sample Description: MW6/C/38

Sampled by : Abdun-Nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives:

Sampled : April 23, 1998

Received : April 23, 1998

Extracted : N/A

Analyzed : April 28, 1998

QA/QC ID# : SP 98042800A A

TOTAL ORGANIC HALOGENS

CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOX	9020	ug/L	5	ND	5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)

ug/L = Micrograms Per Liter (ppb)

ND = Not Detected at or above the DLR.

♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL

Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

May 6, 1998

LAB No: SP 802916-5

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW6 Quarterly Sampling Area 317

Sample Description: MW6/O/38

Sampled by: Abdun-Nur/Bricker

Container: VOA

Preservatives:

Sampled: April 23, 1998

Received: April 23, 1998

Extracted: N/A

Analyzed: April 25, 1998

QA/QC ID#: SP 98042501H B

EPA METHOD 624

CONSTITUENT	SAMPLE DLR ug/L	SAMPLE RESULTS ug/L	LAB DLR ug/L	BLANK RESULTS ug/L
Trichloroethylene	0.5	ND	0.5	ND

SURROGATES

Fluorobenzene	70-130	98	70-130	96
Pentafluorobenzene	70-130	107	70-130	103
4-Bromofluorobenzene	70-130	108	70-130	103

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
ug/L = Micrograms Per Liter (ppb) ND = Not Detected at or above the DLR. AR = Acceptable Range
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL

Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

May 6, 1998

LAB No: SP 802916-1

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW6 Quarterly Sampling Area 317

Description: MW6/A/38

Sampled by: Abdun-Nur/Bricker

Type of Sample: Monitoring Well

Sampled : April 23, 1998

Received : April 23, 1998

Completed : April 24, 1998

QA/QC ID# : 80291601-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS
Conductivity	2510B	umhos/cm	1	590
pH	4500-H B	units	---	7.5

DLR = Detection Limit for Reporting Purposes. ND = Not Detected at or above the DLR.

ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram

♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

Preservatives: (1) Cool 4°C Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

May 6, 1998

LAB No: SP 802916-4

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW6 Quarterly Sampling Area 317

Description: MW6/H/38

Sampled by: Abdun-Nur/Bricker

Type of Sample: Monitoring Well

Sampled : April 23, 1998

Received : April 23, 1998

Completed : April 29, 1998

QA/QC ID# : 80291604-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS
Chloride	300.0	mg/L	1	77
Sulfate	300.0	mg/L	1	30

DLR = Detection Limit for Reporting Purposes. ND = Not Detected at or above the DLR.
ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.
Preservatives: (1) Cool 4°C Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

May 6, 1998

LAB No: SP 802916-6

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW6 Quarterly Sampling Area 317

Description: MW6/R/38

Sampled by : Abdun-Nur/Bricker

Type of Sample: Monitoring Well

Sampled : April 23, 1998

Received : April 23, 1998

Completed : April 28, 1998

QA/QC ID# : 80291606-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS	MCL
Iron	200.7	ug/L	50	140	300
Manganese	200.7	ug/L	30	ND	50
Sodium	200.7	mg/L	1	54	

DLR = Detection Limit for Reporting Purposes.

ND = Not Detected at or above the DLR.

ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram

♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

Preservatives: (1) Cool 4°C (2) HNO₃ pH < 2 Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm

This report package is not intended for use in the State of Utah unless bound or paginated

Corporate Offices & Laboratory
PO Box 272 / 853 Corporation Street
Santa Paula, CA 93061-0272
TEL: 805/659-0910
FAX: 805/525-4172

Office & Laboratory
2500 Stagecoach Road
Stockton, CA 95215
TEL: 209/942-0181
FAX: 209/942-0423

Field Office
Visalia, CA
TEL: 209/734-9473
FAX: 209/734-8435
Mobile: 209/733-3200



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802144-2

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW10 Quarterly Sampling Area 317

Sample Description: MW10/B/38

Sampled by : Abdun-Nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives: H2SO4 pH < 2

Sampled : March 25, 1998

Received : March 25, 1998

Extracted : N/A

Analyzed : March 27, 1998

QA/QC ID# : SP 98032700A A


TOTAL ORGANIC CARBON

CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOC	415.1	mg/L	0.5	ND	0.5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
mg/L = Milligrams Per Liter (ppm) ND = Not Detected at or above the DLR.
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

If you have any questions, please call.

FGL ENVIRONMENTAL


Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802144-3

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW10 Quarterly Sampling Area 317

Sample Description: MW10/C/38

Sampled by : Abdun-Nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives:

Sampled : March 25, 1998

Received : March 25, 1998

Extracted : N/A

Analyzed : April 7, 1998

QA/QC ID# : SP 98040700A A

TOTAL ORGANIC HALOGENS

CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOX	9020	ug/L	5	ND	5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
ug/L = Micrograms Per Liter (ppb) ND = Not Detected at or above the DLR.

♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

If you have any questions, please call.

FGL ENVIRONMENTAL


Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802144-5

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW10 Quarterly Sampling Area 317

Sample Description: MW10/0/38

Sampled by : Abdun-Nur/Bricker

Container : VOA

Preservatives:

Sampled : March 25, 1998

Received : March 25, 1998

Extracted : N/A

Analyzed : April 2, 1998

QA/QC ID# : SP 98040201H A


EPA METHOD 624

CONSTITUENT	SAMPLE DLR ug/L	SAMPLE RESULTS ug/L	LAB DLR ug/L	BLANK RESULTS ug/L
Trichloroethylene	0.5	ND	0.50	ND
SURROGATES	AR	SAMPLE % REC.	LAB AR	BLANK % REC.
1,2-Dichloroethane-d4	40-140	117	40-140	110
Toluene-d8	64-139	94	64-139	93
BFB	50-149	101	50-149	95

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
ug/L = Micrograms Per Liter (ppb) ND = Not Detected at or above the DLR. AR = Acceptable Range
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

If you have any questions, please call.

FGL ENVIRONMENTAL


Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802144-1

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW10 Quarterly Sampling Area 317

Description: MW10/A/38

Sampled by : Abdun-Nur/Bricker

Type of Sample: Monitoring Well

Sampled : March 25, 1998

Received : March 25, 1998

Completed : March 27, 1998

QA/QC ID# : 80214401-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS
Conductivity	2510B	umhos/cm	1	640

DLR = Detection Limit for Reporting Purposes. ND = Not Detected at or above the DLR.
ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.
Preservatives: (1) Cool 4°C Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802144-4

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW10 Quarterly Sampling Area 317

Description: MW10/H/38

Sampled by : Abdun-Nur/Bricker

Type of Sample: Monitoring Well

Sampled : March 25, 1998

Received : March 25, 1998

Completed : March 25, 1998

QA/QC ID# : 80214404-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS
Chloride	300.0	mg/L	1	74
Sulfate	300.0	mg/L	1	43

DLR = Detection Limit for Reporting Purposes. ND = Not Detected at or above the DLR.
ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.
Preservatives: (1) Cool 4°C Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 10, 1998

LAB No: SP 802144-6

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Inorganic Analysis

Sample Site: MW10 Quarterly Sampling Area 317

Description: MW10/R/38

Sampled by : Abdun-Nur/Bricker

Type of Sample: Monitoring Well

Sampled : March 25, 1998

Received : March 25, 1998

Completed : March 31, 1998

QA/QC ID# : 80214406-

Analytical Results

CONSTITUENT	METHOD	UNITS	DLR	RESULTS	MCL
Iron	200.7	ug/L	50	ND	300
Manganese	200.7	ug/L	30	ND	50
Sodium	200.7	mg/L	1	81	

DLR = Detection Limit for Reporting Purposes. ND = Not Detected at or above the DLR.
ug/L = Micrograms Per Liter (ppb) mg/L = Milligrams Per Liter (ppm) mg/kg = Milligrams Per Kilogram
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.
Preservatives: (1) Cool 4°C Containers: (a) Plastic

If you have any questions, please call.

FGL ENVIRONMENTAL

Kurt Wilkinson, B.S.
QA Director

KW:kdm



ENVIRONMENTAL

Analytical Chemists

April 10, 1998

ORGANIC Quality Assurance Report for sample: 802142

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

Constituent	BATCH ID	EPA Method	Units	CALIBRATION QA/QC					METHOD QA/QC						
				Type	Conc.	% REC	AR	NOTE	Type	Conc.	% REC	% REC	AR	% DIF	MAV
1,2-Dichloroethane-d4	6H12A	624	ug/L	CCV	10.0	101	40-140		BS	10.0	111	107	40-140	3.2	30.0
Toluene-d8	6H12A	624	ug/L	CCV	10.0	97.5	64-139		BS	10.0	96.4	95.1	64-139	1.4	30.0
BFB	6H12A	624	ug/L	CCV	10.0	103	50-149		BS	10.0	98.7	96.9	50-149	1.9	30.0
Trichloroethylene	6H12A	624	ug/L	CCV	10.0	98.6	66-134		BS	10.0	107	105	37-151	1.4	23.0
TOC	0A 2A	415.1	mg/L	LCS	55.0	92.7	75-125		MS	50.0	100	98.0	75-125	2.0	20.0
TOX	11A 2A	TOX	ug/L	CCV	10.0	110	74-116		MS	100	107	105	75-125	1.9	20.0

FGL ID = 19980327 N/A => Not Applicable NOTE => See note indicated below.

KAD:kdm

FGL ENVIRONMENTAL, INC.

Kurt Wilkinson, B.S., QA Director



ENVIRONMENTAL

Analytical Chemists

April 10, 1998

INORGANIC Quality Assurance Report for sample: 802142

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

Constituent	BATCH ID	Method	Units	BLANK QA/QC			CALIBRATION QA/QC					METHOD QA/QC							
				DLR	Result	NOTE	Type	Conc.	% REC	AR	NOTE	Type	Conc.	% REC	% REC	AR	% DIF	MAV	NOTE
Iron	6D 2B	200.7	ug/L	50	ND		CCV	5000	104	90-110		MS	500	102	105	75-125	2.2	20.0	
Manganese	6D 2B	200.7	ug/L	30	ND		CCV	1000	102	90-110		MS	100	103	105	75-125	1.9	20.0	
Sodium	6D 2B	200.7	mg/L	1.0	ND		CCV	50.0	98.3	90-110		MS	5.00	96.9	112	75-125	1.2	20.0	
Chloride	0A 2B	300.0	mg/L	1.0	0.1		CCV	50.0	99.3	90-110		MS	500	102	101	85-111	0.8	4.1	
Conductivity	2A 2B	25108	umhos/c2	1.0	ND		CCV	995	99.2	95-105		Dup	572	N/A	N/A	N/A	0.2	0.8	
Sulfate	0A 2B	300.0	mg/L	1.0	ND		CCV	100	101	90-110		MS	1000	105	103	80-120	1.8	20.0	

FGL ID = 19980325 ND => Not Detected at or above DLR. DLR => Detection Limit for Reporting purposes. N/A => Not Applicable NOTE => See note indicated below.

KW:kdm

FGL ENVIRONMENTAL, INC.

Kurt Wilkinson, B.S., QA Director



ENVIRONMENTAL

Analytical Chemists

April 10, 1998

ORGANIC Quality Assurance Report for sample: 802143

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

Constituent	BATCH ID	EPA Method	Units	CALIBRATION QA/QC					METHOD QA/QC							
				Type	Conc.	% REC	AR	NOTE	Type	Conc.	% REC	% REC	AR	% DIF	MAV	NOTE
1,2-Dichloroethane-d4	6H12A	624	ug/L	CCV	10.0	101	40-140		BS	10.0	111	107	40-140	3.2	30.0	
Toluene-d8	6H12A	624	ug/L	CCV	10.0	97.5	64-139		BS	10.0	96.4	95.1	64-139	1.4	30.0	
BFB	6H12A	624	ug/L	CCV	10.0	103	50-149		BS	10.0	98.7	96.9	50-149	1.9	30.0	
Trichloroethylene	6H12A	624	ug/L	CCV	10.0	98.6	66-134		BS	10.0	107	105	37-151	1.4	23.0	
TOC	0A 2A	415.1	mg/L	LCS	55.0	92.7	75-125		MS	50.0	100	98.0	75-125	2.0	20.0	
TOX	11A 2A	TOX	ug/L	CCV	10.0	110	74-116		MS	100	107	105	75-125	1.9	20.0	

FGL ID = 19980327 N/A => Not Applicable NOTE => See note indicated below.

KAD:kdm

FGL ENVIRONMENTAL, INC.

Kurt Wilkinson, B.S., QA Director



ENVIRONMENTAL

Analytical Chemists

April 10, 1998

INORGANIC Quality Assurance Report for sample: 802143

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

Constituent	BATCH ID	Method	Units	BLANK QA/QC			CALIBRATION QA/QC					METHOD QA/QC							
				DLR	Result	NOTE	Type	Conc.	% REC	AR	NOTE	Type	Conc.	% REC	% REC	AR	% DIF	MAV	NOTE
Iron	6D 2B	200.7	ug/L	50	ND		CCV	5000	104	90-110		MS	500	102	105	75-125	2.2	20.0	
Manganese	6D 2B	200.7	ug/L	30	ND		CCV	1000	102	90-110		MS	100	103	105	75-125	1.9	20.0	
Sodium	6D 2B	200.7	mg/L	1.0	ND		CCV	50.0	98.3	90-110		MS	5.00	96.9	112	75-125	1.2	20.0	
Chloride	0A 2B	300.0	mg/L	1.0	0.1		CCV	50.0	99.3	90-110		MS	500	102	101	85-111	0.8	4.1	
Conductivity	2A 2B	25108	umhos/cm	1.0	ND		CCV	995	99.2	95-105		Dup	572	N/A	N/A	N/A	0.2	0.8	
Sulfate	0A 2B	300.0	mg/L	1.0	ND		CCV	100	101	90-110		MS	1000	105	103	80-120	1.8	20.0	

FGL ID = 19980325 ND => Not Detected at or above DLR. DLR => Detection Limit for Reporting purposes. N/A => Not Applicable NOTE => See note indicated below.

KW:kdm

FGL ENVIRONMENTAL, INC.

Kurt Wilkinson, B.S., QA Director



ENVIRONMENTAL

Analytical Chemists

April 10, 1998

ORGANIC Quality Assurance Report for sample: 802144

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

Constituent	BATCH ID	EPA Method	Units	CALIBRATION QA/QC					METHOD QA/QC						
				Type	Conc.	% REC	AR	NOTE	Type	Conc.	% REC	% REC	AR	% DIF	MAV
1,2-Dichloroethane-d4	6H12A	624	ug/L	CCV	10.0	101	40-140		BS	10.0	111	107	40-140	3.2	30.0
Toluene-d8	6H12A	624	ug/L	CCV	10.0	97.5	64-139		BS	10.0	96.4	95.1	64-139	1.4	30.0
BFB	6H12A	624	ug/L	CCV	10.0	103	50-149		BS	10.0	98.7	96.9	50-149	1.9	30.0
Trichloroethylene	6H12A	624	ug/L	CCV	10.0	98.6	66-134		BS	10.0	107	105	37-151	1.4	23.0
TOC	0A 2A	415.1	mg/L	LCS	55.0	92.7	75-125		MS	50.0	100	98.0	75-125	2.0	20.0
TOX	11A 2A	TOX	ug/L	CCV	10.0	110	74-116		MS	100	107	105	75-125	1.9	20.0

FGL ID = 19980327 N/A => Not Applicable NOTE => See note indicated below.

KAD:kdm

FGL ENVIRONMENTAL, INC.

Kurt Wilkinson, B.S., QA Director



ENVIRONMENTAL

Analytical Chemists

April 10, 1998

INORGANIC Quality Assurance Report for sample: 802144

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

Constituent	BATCH ID	Method	Units	BLANK QA/QC			CALIBRATION QA/QC					METHOD QA/QC							
				DLR	Result	NOTE	Type	Conc.	% REC	AR	NOTE	Type	Conc.	% REC	% REC	AR	% DIF	MAV	NOTE
Iron	6D 2B	200.7	ug/L	50	ND		CCV	5000	104	90-110		MS	500	102	105	75-125	2.2	20.0	
Manganese	6D 2B	200.7	ug/L	30	ND		CCV	1000	102	90-110		MS	100	103	105	75-125	1.9	20.0	
Sodium	6D 2B	200.7	mg/L	1.0	ND		CCV	50.0	98.3	90-110		MS	5.00	96.9	112	75-125	1.2	20.0	
Chloride	0A 2B	300.0	mg/L	1.0	0.1		CCV	50.0	99.3	90-110		MS	500	102	101	85-111	0.8	4.1	
Conductivity	2A 2B	2510B	umhos/c2	1.0	ND		CCV	995	99.2	95-105		Dup	572	N/A	N/A	N/A	0.2	0.8	
Sulfate	0A 2B	300.0	mg/L	1.0	ND		CCV	100	101	90-110		MS	1000	105	103	80-120	1.8	20.0	

FGL ID = 19980325 ND => Not Detected at or above DLR. DLR => Detection Limit for Reporting purposes. N/A => Not Applicable NOTE => See note indicated below.

FGL ENVIRONMENTAL, INC.

Kurt Wilkinson, B.S., QA Director

KW:kdm



ENVIRONMENTAL

Analytical Chemists

May 6, 1998

ORGANIC Quality Assurance Report for sample: 802915

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

Constituent	BATCH ID	EPA Method	Units	CALIBRATION QA/QC					METHOD QA/QC							
				Type	Conc.	% REC	AR	NOTE	Type	Conc.	% REC	% REC	AR	% DIF	MAV	NOTE
Fluorobenzene	0H12B	624	ug/L	CCV	10.0	103	70-130		BS	10.0	99.4	99.7	70-130	0.4	30.0	
Pentafluorobenzene	0H12B	624	ug/L	CCV	10.0	106	70-130		BS	10.0	105	105	70-130	0.1	30.0	
4-Bromofluorobenzene	0H12B	624	ug/L	CCV	10.0	101	70-130		BS	10.0	101	103	70-130	1.6	30.0	
Trichloroethylene	0H12B	624	ug/L	CCV	10.0	98.6	66-134		BS	10.0	108	106	37-151	2.4	23.0	
TOX	3A 2A	TOX	ug/L	CCV	10.0	100	74-116		BS	100	98.1	85.7	68-126	13.5	16.7	

FGL ID = 19980425 N/A => Not Applicable NOTE => See note indicated below.

FGL ENVIRONMENTAL, INC.

Kurt Wilkinson, B.S., QA Director

KAD: kdm



Analytical Chemists

May 6, 1998

INORGANIC Quality Assurance Report for sample: 802915

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

Constituent	BATCH ID	Method	Units	BLANK QA/QC			CALIBRATION QA/QC					METHOD QA/QC							
				DLR	Result	NOTE	Type	Conc.	% REC	AR	NOTE	Type	Conc.	% REC	% REC	AR	% DIF	MAV	NOTE
Iron	5D 2A	200.7	ug/L	50	ND		CCV	5000	101	90-110		MS	500	98.2	98.3	75-125	0.0	20.0	
Manganese	5D 2A	200.7	ug/L	30	ND		CCV	1000	101	90-110		MS	100	98.7	98.9	75-125	0.3	20.0	
Sodium	5D 2A	200.7	mg/L	1.0	ND		CCV	50.0	97.9	90-110		MS	5.00	101	98.6	75-125	0.3	20.0	
Chloride	6A 2C	300.0	mg/L	1.0	ND		CCV	50.0	106	90-110		MS	500	105	106	85-111	0.9	4.1	
Conductivity	1A 2A	25108	umhos/c2	1.0	ND		CCV	995	98.4	95-105		Dup	914	N/A	N/A	N/A	0.2	0.8	
pH	0A 2A	4500-H B	units		N/A		CCV	8.00	99.5	95-105		Dup	10.6	N/A	N/A	N/A	0.0	1.4	
Sulfate	6A 2C	300.0	mg/L	1.0	ND		CCV	100	106	90-110		MS	1000	126	126	80-120	0.4	20.0	405

FGL ID = 19980423 ND => Not Detected at or above DLR. DLR => Detection Limit for Reporting purposes. N/A => Not Applicable NOTE => See note indicated below.

Notes:

405 Matrix Spike (MS) not within the Acceptance Range (AR) and/or Relative Percent Difference (RPD) not within the Maximum Allowable Value (MAV) because of low concentrations of the spike or sample. Batch qualified based on the LCS, CCV or ICV recovery.

FGL ENVIRONMENTAL, INC.

Kurt Wilkinson, B.S., QA Director

KW:kdm



ENVIRONMENTAL

Analytical Chemists

May 6, 1998

INORGANIC Quality Assurance Report for sample: 802916

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

Constituent	BATCH ID	Method	Units	BLANK QA/QC			CALIBRATION QA/QC					METHOD QA/QC							
				DLR	Result	NOTE	Type	Conc.	% REC	AR	NOTE	Type	Conc.	% REC	% REC	AR	% DIF	MAV	NOTE
Iron	5D 2A	200.7	ug/L	50	ND		CCV	5000	101	90-110		MS	500	98.2	98.3	75-125	0.0	20.0	
Manganese	5D 2A	200.7	ug/L	30	ND		CCV	1000	101	90-110		MS	100	98.7	98.9	75-125	0.3	20.0	
Sodium	5D 2A	200.7	mg/L	1.0	ND		CCV	50.0	97.9	90-110		MS	5.00	101	98.6	75-125	0.3	20.0	
Chloride	6A 2C	300.0	mg/L	1.0	ND		CCV	50.0	106	90-110		MS	500	105	106	85-111	0.9	4.1	
Conductivity	1A 2A	2510B	umhos/c2	1.0	ND		CCV	995	98.4	95-105		Dup	914	N/A	N/A	N/A	0.2	0.8	
pH	0A 2A	4500-H B	units		N/A		CCV	8.00	99.5	95-105		Dup	10.6	N/A	N/A	N/A	0.0	1.4	
Sulfate	6A 2C	300.0	mg/L	1.0	ND		CCV	100	106	90-110		MS	1000	126	126	80-120	0.4	20.0	405

FGL ID = 19980423 ND => Not Detected at or above DLR. DLR => Detection Limit for Reporting purposes. N/A => Not Applicable NOTE => See note indicated below.

Notes:

405 Matrix Spike (MS) not within the Acceptance Range (AR) and/or Relative Percent Difference (RPD) not within the Maximum Allowable Value (MAV) because of low concentrations of the spike or sample. Batch qualified based on the LCS, CCV or ICV recovery.

KW:kdm

FGL ENVIRONMENTAL, INC.

Kurt Wilkinson, B.S., QA Director

APPENDIX G

TRIP AND FIELD BLANK SAMPLE ANALYTICAL REPORTS



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 7, 1998

LAB No: SP 802141-1

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW5-1A Quarterly Sampling Area 317

Sample Description: MW5/B/38/1A

Sampled by : Abdun-nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives: H2SO4 pH < 2

Sampled : March 25, 1998

Received : March 25, 1998

Extracted : N/A

Analyzed : March 27, 1998

QA/QC ID# : SP. 98032700A A

TOTAL ORGANIC CARBON


CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOC	415.1	mg/L	0.5	ND	0.5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
mg/L = Milligrams Per Liter (ppm) ND = Not Detected at or above the DLR.

♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL


Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:cea



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 7, 1998

LAB No: SP 802141-2

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW5-1A Quarterly Sampling Area 317

Sample Description: MW5/C/38/1A

Sampled by : Abdun-nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives:

Sampled : March 25, 1998

Received : March 25, 1998

Extracted : N/A

Analyzed : April 6, 1998

QA/QC ID# : SP 98040600A A


TOTAL ORGANIC HALOGENS

CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOX	9020	ug/L	5	ND	5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
ug/L = Micrograms Per Liter (ppb) ND = Not Detected at or above the DLR.
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL


Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:cea



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 7, 1998

LAB No: SP 802141-3

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW5-1A Quarterly Sampling Area 317

Sample Description: MW5/O/38/1A

Sampled by: Abdun-nur/Bricker

Container: VOA

Preservatives:

Sampled: March 25, 1998

Received: March 25, 1998

Extracted: N/A

Analyzed: April 2, 1998

QA/QC ID#: SP 98040201H A

EPA METHOD 624


CONSTITUENT	SAMPLE DLR ug/L	SAMPLE RESULTS ug/L	LAB DLR ug/L	BLANK RESULTS ug/L
Trichloroethylene	0.5	ND	0.50	ND

SURROGATES	AR	SAMPLE % REC.	LAB AR	BLANK % REC.
1,2-Dichloroethane-d4	40-140	114	40-140	110
Toluene-d8	64-139	92	64-139	93
BFB	50-149	100	50-149	95

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
ug/L = Micrograms Per Liter (ppb) ND = Not Detected at or above the DLR. AR = Acceptable Range
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL


Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:cea



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 7, 1998

LAB No: SP 802140-1

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW6-1A Quarterly Sampling Area 317

Sample Description: MW6/B/38/1A

Sampled by : Abdun-nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives: H2SO4 pH < 2

Sampled : March 25, 1998

Received : March 25, 1998

Extracted : N/A

Analyzed : March 27, 1998

QA/QC ID# : SP 98032700A A


TOTAL ORGANIC CARBON

CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOC	415.1	mg/L	0.5	ND	0.5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
mg/L = Milligrams Per Liter (ppm) ND = Not Detected at or above the DLR.
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL


Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:cea



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 7, 1998

LAB No: SP 802140-2

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW6-1A Quarterly Sampling Area 317

Sample Description: MW6/C/38/1A

Sampled by : Abdun-nur/Bricker

Container : Amber Glass TFE-Cap

Preservatives:

Sampled : March 25, 1998

Received : March 25, 1998

Extracted : N/A

Analyzed : April 6, 1998

QA/QC ID# : SP 98040600A A

TOTAL ORGANIC HALOGENS

CONSTITUENT	EPA METHOD	UNITS	SAMPLE DLR	SAMPLE RESULTS	LAB DLR	BLANK RESULTS
TOX	9020	ug/L	5	ND	5	ND

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
ug/L = Micrograms Per Liter (ppb) ND = Not Detected at or above the DLR.
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL


Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:cea



ENVIRONMENTAL

ANALYTICAL CHEMISTS

April 7, 1998

LAB No: SP 802140-3

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

RE: Organic Analysis
Matrix: Monitoring Well

Project/Site: MW6-1A Quarterly Sampling Area 317

Sample Description: MW6/O/38/1A

Sampled by : Abdun-nur/Bricker

Container : VOA

Preservatives:

Sampled : March 25, 1998

Received : March 25, 1998

Extracted : N/A

Analyzed : April 2, 1998

QA/QC ID# : SP 98040201H A


EPA METHOD 624

CONSTITUENT	SAMPLE DLR ug/L	SAMPLE RESULTS ug/L	LAB DLR ug/L	BLANK RESULTS ug/L
Trichloroethylene	0.5	ND	0.50	ND
SURROGATES	AR	SAMPLE % REC.	LAB AR	BLANK % REC.
1,2-Dichloroethane-d4	40-140	115	40-140	110
Toluene-d8	64-139	94	64-139	93
BFB	50-149	97	50-149	95

DLR = Detection Limit for Reporting Purposes. MCL = Maximum Contaminant Level (--- indicates none determined.)
ug/L = Micrograms Per Liter (ppb) ND = Not Detected at or above the DLR. AR = Acceptable Range
♦ = DLR adjusted because of dilutions, concentrations, or limited sample.

See attached for Quality Assurance report. If you have any questions, please call.

FGL ENVIRONMENTAL


Kelly A. Dunnahoo, B.S.
Organic Laboratory Manager

KAD:cea



ENVIRONMENTAL

Analytical Chemists

April 7, 1998

ORGANIC Quality Assurance Report for sample: 802140

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

Constituent	BATCH ID	EPA Method	Units	CALIBRATION QA/QC					METHOD QA/QC						
				Type	Conc.	% REC	AR	NOTE	Type	Conc.	% REC	% REC	AR	% DIF	MAV
1,2-Dichloroethane-d4	6H12A	624	ug/L	CCV	10.0	101	40-140		BS	10.0	111	107	40-140	3.2	30.0
Toluene-d8	6H12A	624	ug/L	CCV	10.0	97.5	64-139		BS	10.0	96.4	95.1	64-139	1.4	30.0
BFB	6H12A	624	ug/L	CCV	10.0	103	50-149		BS	10.0	98.7	96.9	50-149	1.9	30.0
Trichloroethylene	6H12A	624	ug/L	CCV	10.0	98.6	66-134		BS	10.0	107	105	37-151	1.4	23.0
TOC	0A 2A	415.1	mg/L	LCS	55.0	92.7	75-125		MS	50.0	100	98.0	75-125	2.0	20.0
TOX	10A 2A	TOX	ug/L	CCV	10.0	98.0	74-116		MS	100	101	110	75-125	7.9	20.0

FGL ID = 19980327 N/A => Not Applicable NOTE => See note indicated below.

KAD:cea

FGL ENVIRONMENTAL, INC.

Kurt Wilkinson, B.S., QA Director



ENVIRONMENTAL

Analytical Chemists

April 7, 1998

ORGANIC Quality Assurance Report for sample: 802141

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

Constituent	BATCH ID	EPA Method	Units	CALIBRATION QA/QC					METHOD QA/QC						
				Type	Conc.	% REC	AR	NOTE	Type	Conc.	% REC	% REC	AR	% DIF	MAV
1,2-Dichloroethane-d4	6H12A	624	ug/L	CCV	10.0	101	40-140		BS	10.0	111	107	40-140	3.2	30.0
Toluene-d8	6H12A	624	ug/L	CCV	10.0	97.5	64-139		BS	10.0	96.4	95.1	64-139	1.4	30.0
BFB	6H12A	624	ug/L	CCV	10.0	103	50-149		BS	10.0	98.7	96.9	50-149	1.9	30.0
Trichloroethylene	6H12A	624	ug/L	CCV	10.0	98.6	66-134		BS	10.0	107	105	37-151	1.4	23.0
TOC	0A 2A	415.1	mg/L	LCS	55.0	92.7	75-125		MS	50.0	100	98.0	75-125	2.0	20.0
TOX	10A 2A	TOX	ug/L	CCV	10.0	98.0	74-116		MS	100	101	110	75-125	7.9	20.0

FGL ID = 19980327 N/A => Not Applicable NOTE => See note indicated below.

FGL ENVIRONMENTAL, INC.

Kurt Wilkinson, B.S., QA Director

KAD:cea



ENVIRONMENTAL

Analytical Chemists

May 12, 1998

ORGANIC Quality Assurance Report for sample: 802915

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

Constituent	BATCH ID	EPA Method	Units	CALIBRATION QA/QC					METHOD QA/QC						
				Type	Conc.	% REC	AR	NOTE	Type	Conc.	% REC	% REC	AR	% DIF	MAV NOTE
TOC	QA 28	5310 C	mg/L	LCS	55.0	67.3	75-125		BS	50.0	98.0	96.0	75-125	2.1	20.0

FGL ID = 19980512 M/A => Not Applicable NOTE => See note indicated below.

KAD:c1

FGL ENVIRONMENTAL, INC.

Kurt Wilkinson, B.S., QA Director



ENVIRONMENTAL

Analytical Chemists

May 12, 1998

ORGANIC Quality Assurance Report for sample: 802916

Bermite Division of Whittaker
22116 W. Soledad Canyon Road
Santa Clarita, CA 91350

Constituent	BATCH ID	EPA Method	Units	CALIBRATION QA/QC					METHOD QA/QC						
				Type	Conc.	% REC	AR	NOTE	Type	Conc.	% REC	% REC	AR	% DIF	MAV
TOC	0A 2B	5310 C	mg/L	LCS	55.0	87.3	75-125		MS	50.0	98.0	96.0	75-125	2.1	20.0

FGL ID = 19980512 N/A => Not Applicable NOTE => See note indicated below.

FGL ENVIRONMENTAL, INC.

Kurt Wilkinson, B.S., QA Director

KAD:c1

APPENDIX H

STATISTICAL ANALYSES

TABLE H-1

THIRTY-EIGHTH QUARTER SAMPLING EVENT

Parameter	Units	Tolerance Limit	Well No.		
			MW-5	MW-6	MW-10
Conductivity	$\mu\text{mhos/cm}$	802.6	570	590	640
pH		7.01/8.01	7.8	7.5	7.9
TOC	mg/l	2.75	<0.5	0.6	<0.5
TOX	$\mu\text{g/l}$	49.1	<5	<5	<5
Chloride	mg/l	201.6	62	77	74
Sulfate	mg/l	102.3	29	30	43
TCE	$\mu\text{g/l}$	0.5 ^a	<0.5	<0.5	<0.5
Iron	$\mu\text{g/l}$	171.4	<50	140	<50
Manganese	$\mu\text{g/l}$	30 ^a	<30	<30	<30
Sodium	mg/l	59.7	54	54	81

Note: All tolerance limits are upper limits except pH which has both upper and lower limits.

^aTolerance limit set at detection limit.

TABLE H-2

CONCENTRATIONS OF GROUND WATER MONITORING PARAMETERS
IN SAMPLES FROM BACKGROUND MONITORING WELL MW-1

Date	Quarter	pH ^a	Conductivity ^a (μmhos/cm)	TOC ^a (mg/l)	TOX ^a (μg/l)	Cl (mg/l)	SO ₄ ²⁻ (mg/l)	TCE (μg/l)	Fe (μg/l)	Mn (μg/l)	Na (mg/l)
10/04/88 ^b	1	7.5	598	<3	<100		11	<5			
01/25/89	2	7.48	572	2.4 ^c	<100		22				
04/17/89	3	7.2		<3	<100		11				
07/27/89	4	7.48	500	2.4 ^c	<100		13				
10/31/89	5	7.6	524	<3	<100	83	10				
01/25/90	6	7.4	570	<3	<100	85	16				
04/17/90	7	7.55	504	<4	<20	88	11				
07/17/90	8	8.28	530	<4	<20	82	10				
10/18/90	9	7.4	544	<1	75 ^c	98	23				
01/29/91	10	7.5	573	1.4	<5	96	8				
04/23/91	11	7.68	559	1.8	<5	100	10				
07/19/91	12	7.33	575	1.2	<5	97	11				
10/08/91 ^d	—	—	—	—	—	—	—				
03/13/92	14	7.5	639	0.4 ^c	<5	131	13				
04/21/92	15	7.5	643	<0.5	<5	130	9				
07/29/92	16	7.55	660	<0.5	6.9	133	11				
10/20/92	17	7.5	676	<0.5	<5	138	10				
01/27/93	18	7.68	707	<0.5	<5	137	6				
06/09/93	19	7.5	715	<0.5	<5	134	9		250	<30	52
07/14/93	20	—	—	—	—	—	—		220	<30	46
08/11/93	20	—	—	—	—	—	—		60	<30	54
09/22/93	20	7.5	720	<0.5	9	161	13		100	<30	52
12/08/93	21	7.4	726	<0.5	<5	151	10		50	<30	57
03/10/94	22	7.5	730	<0.5	<5	150	10	<0.5	200	<30	48
06/22/94	23	7.5	740	<0.5	<5	150	15	<0.5	150	<30	54
09/14/94	24	7.4	750	<0.5	8	160	9	<0.5	60	2.5	57
12/14/94	25	7.5	770	<0.5	<5	150	10	<0.5	80	4	51
03/29/95	26	7.5	770	<0.5	<5	160	12	<0.5	60	1.6	49
06/27/95	27	7.4	760	<0.5	10	170	13	<0.5	50	2.8	45
09/12/95	28	7.5	780	<0.5	6	160	12	<0.5	90	3	53
12/08/95	29	6.9	780	<0.5	<5	180	12	<0.5	<50	2.7	50
03/20/96	30	7.4	770	<0.5	<5	180	13	<0.5	<50	2.1	51
06/26/96	31	7.7	760	<0.5	<5	150	13	<0.5	<50	2.1	53
09/19/96	32	7.6	750	<0.5	7	160	12	<0.5	80	1.8	52
12/05/96	33	7.5	750	<0.5	<5	160	10	<0.5	<50	2.6	55
03/19/97	34	7.8	770	<0.5	<5	170	10	<0.5	100	3.2	53
06/24/97	35	7.4	810	<0.5	<5	180	12	<0.5	130	<30	54
09/30/97	36	7.1	790	<0.5	7	170	11	<0.5	<50	<30	53
12/03/97	37	7.0	795	<0.5	<5	160	11	<0.5	70	<30	52
03/25/98	38	7.8	810	<0.5	<5	180	12	<0.5	<50	<30	52

^aEach value reported before 06/09/93 is the average result from four replicate samples. Beginning 06/09/93, reported values are for a single sample as replicate sampling was stopped.

^bSamples from 01/27/88, 07/29/88, 08/15/88, and 10/04/88 reported TCE at <5 μg/l.

^cThe replicates included a portion with results below the detection limit. The average was calculated after assigning a value of one-half the detection limit for the samples below the detection limit.

^dNot sampled because water elevation dropped below elevation of sampling pump intake.

TABLE H-3

CONCENTRATIONS OF GROUND WATER MONITORING PARAMETERS
IN SAMPLES FROM BACKGROUND MONITORING WELL MW-3

Date	Quarter	pH ^a	Conductivity ^a (µmhos/cm)	TOC ^a (mg/l)	TOX ^a (µg/l)	Cl ⁻ (mg/l)	SO ₄ ²⁻ (mg/l)	TCE (µg/l)	Fe (µg/l)	Mn (µg/l)	Na (mg/l)
10/04/88 ^b	1	7.48	699	<3	361.25		73	<5			
01/25/89	2	7.73	664	<3	<100		74				
04/17/89	3	7.3		<3	<100		9				
07/27/89	4	7.5	661	<3	<100		65				
10/31/89	5	7.53	617	<3	<100	35	68				
01/25/90	6	7.18	641	7.1 ^c	<100	36	74				
04/17/90	7	7.33	590	<4	<20	46	60				
07/17/90	8	8.23	589	<4	<20	39	67				
10/18/90	9	7.63	642	0.7 ^c	<100	34	15				
01/29/91	10	7.28	656	2.2	<5	54	80				
04/23/91	11	7.55	629	2.0	<5	34	77				
07/19/91	12	7.23	633	1.3	<5	45	85				
10/09/91	13	7.65	642	<0.5	<5	37	34				
03/13/92	14	7.45	648	0.6	3.3 ^c	33	85				
04/21/92	15	7.5	644	<0.5	<5	37	81				
07/29/92	16	7.55	643	0.34 ^c	<5	33	74				
10/20/92	17	7.55	641	<0.5	<5	34	67				
01/27/93	18	7.6	640	<0.5	<5	30	69				
06/09/93	19	7.6	627	<0.5	<5	28	70		50	<30	48
07/14/93	20	--	--	--	--	--	--		<50	<30	44
08/11/93	20	--	--	--	--	--	--		<50	<30	50
09/22/93	20	7.4	630	<0.5	<5	37	87		<50	<30	50
12/08/93	21	7.4	627	<0.5	<5	35	72		<50	<30	54
03/10/94	22	7.4	620	<0.5	<5	31	74	<0.5	<50	<30	47
06/22/94	23	7.6	630	<0.5	8 ^d	29	71	<0.5	<50	<30	53
09/14/94	24	7.5	630	<0.5	<5	31	80	<0.5	<50	0.7	52
12/14/94	25	7.5	630	<0.5	<5	28	69	<0.5	<50	<1	48
03/29/95	26	7.7	620	<0.5	7	28	71	<0.5	<50	0.8	49
06/27/95	27	7.6	620	<0.5	7	32	76	<0.5	<50	0.6	53
09/12/95	28	7.6	620	<0.5	<5	34	73	<0.5	<50	<1	53
12/06/95	29	7.5	620	<0.5	<5	29	77	<0.5	<50	<0.5	54
03/20/96	30	7.6	610	<0.5	<5	35	91	<0.5	<50	<0.5	57
06/26/96	31	7.9	600	<0.5	<5	31	78	<0.5	<50	3.3	61
09/19/96	32	8.0	610	<0.5	<5	30	71	<0.5	<50	<0.5	56
12/05/96	33	7.6	600	<0.5	<5	26	62	<0.5	<50	<0.5	56
03/19/97	34	7.6	600	<0.5	<5	29	71	<0.5	<50	<0.5	60
06/18/97	35	7.7	600	<0.5	<5	31	71	<0.5	<50	<30	52
09/10/97	36	7.2	600	<0.5	<5	32	71	<0.5	<50	<30	55
12/03/97	37	7.3	614	<0.5	<5	32	72	<0.5	<50	<30	53
04/23/98	38	7.3	620	0.6	<5	33	71	<0.5	50	<30	50

^aEach value reported before 06/09/93 is the average result from four replicate samples. Beginning 06/09/93, reported values are for a single sample as replicate sampling was stopped.

^bSamples from 02/17/88, 05/27/88, 07/19/88, 08/15/88, and 10/04/88 reported TCE at <5 µg/l.

^cThe replicates included a portion with results below the detection limit. The average was calculated after assigning a value of one-half the detection limit for the samples below the detection limit.

^dDuplicate sample analytical result also 8 µg/l.


TABLE H-4
TOLERANCE LIMIT CALCULATIONS

	pH	Conductivity	TOC	TOX	Chloride	Sulfate	Iron	Sodium
Σx	563.4	47,827	58.19	909.2	5,782	3,069	2,500	2,298
n (number of samples)	75	73	75	74	67	75	44	44
\bar{x} (mean)	7.51	655.16	0.78	12.29	86.30	40.92	56.82	52.23
s (sample standard deviation)	0.2189	76.47	1.00	18.65	57.79	31.12	54.59	3.55
k (from tables)	2.285	1.978	1.972	1.975	1.994	1.972	2.099	2.099
Upper Tolerance Limit ^a	8.01	806.4	2.7	49.1	201.6	102.3	171.4	59.7
Lower Tolerance Limit ^b	7.01							

^aUpper Tolerance Limit = $\bar{x} + ks$.


^bLower Tolerance Limit = $\bar{x} - ks$.

pH
MONITORING WELLS MW-1 AND MW-3




▲ MW-1 ▼ MW-3


CONDUCTIVITY MONITORING WELLS MW-1 AND MW-3



TOTAL ORGANIC CARBON MONITORING WELLS MW-1 AND MW-3




TOTAL ORGANIC HALOGENS MONITORING WELLS MW-1 AND MW-3




▲ MW-1 ▼ MW-3


CHLORIDE MONITORING WELLS MW-1 AND MW-3




SULFATE MONITORING WELLS MW-1 AND MW-3



SODIUM MONITORING WELLS MW-1 AND MW-3



IRON MONITORING WELLS MW-1 AND MW-3



MANGANESE MONITORING WELLS MW-1 AND MW-3

